

# PRELIMINARY ASSESSMENT

## V I P CLEANERS

AKA: MORRISTOWN TIRE  
MORRISTOWN, MORRIS COUNTY

EPA ID NO. NJD 982744740



New Jersey Department of Environmental Protection and Energy  
Division of Responsible Party Site Remediation  
Bureau of Field Operations - Site Assessment Section

V I P CLEANERS  
AKA: MORRISTOWN TIRE  
89 MORRIS STREET  
MORRISTOWN, MORRIS COUNTY, NEW JERSEY  
EPA ID NO. NJD982744740

TABLE OF CONTENTS

NARRATIVE

MAPS

1. UNITED STATES GEOLOGICAL SURVEY (USGS) TOPOGRAPHIC MAP - MORRISTOWN QUADRANGLE
2. SITE MAP
3. LOCAL TAX MAP (1985)
4. COUNTY ROAD MAP (1989)
5. WATER WITHDRAWAL POINTS MAP
6. NATIONAL WETLANDS INVENTORY MAP, MORRISTOWN QUADRANGLE
7. NATIONAL FLOOD INSURANCE RATE MAP (FIRM)

ATTACHMENTS

- A. NJDEPE, BUREAU OF APPLICABILITY AND COMPLIANCE (BAC), UNDERGROUND STORAGE TANK CLOSURE PLAN AND REMEDIAL INVESTIGATION REPORT; SEPTEMBER 27, 1991 - NOVEMBER 23, 1992
- B. NJDEPE, BAC, SUMMARY OF SOIL AND GROUND WATER SAMPLING, MARCH 1992 - OCTOBER 1992
- C. NJDEPE, BAC, ONE-MILE WELL RADIUS MAP AND WELL RECORDS; NOVEMBER 23, 1992
- D. NEW JERSEY DEPARTMENT OF CONSERVATION AND ECONOMIC DEVELOPMENT, DIVISION OF WATER POLICY AND SUPPLY, SPECIAL REPORT 25 - GROUND WATER IN MORRIS COUNTY; 1965
- E. NJDEPE, BAC, MONITORING WELL RECORDS FOR V I P CLEANERS
- F. NJDEPE, DIVISION OF WATER RESOURCES (DWR), PUBLIC COMMUNITY WATER SUPPLY RECORDS
- G. UNITED STATES DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, SOIL SURVEY OF MORRIS COUNTY

H. NJDEPE, DIVISION OF PUBLICLY FUNDED SITE REMEDIATION  
(DPFSR), SITE ASSESSMENT, PHONE MEMO RE: PERMISSION TO  
INSPECT VIP SITE; NOVEMBER 4, 1993

I. NJDEPE, DPFSR, SITE ASSESSMENT, MEMO RE: DECEMBER 13, 1993  
PRE-SAMPLING ASSESSMENT

J. NJDEPE, DPFSR, SITE ASSESSMENT, MEMO RE: 4-MILE RADIUS  
POPULATION CALCULATIONS; DECEMBER 1993

NARRATIVE



## PRELIMINARY ASSESSMENT REPORT

### PART I: GENERAL INFORMATION

Site Name: V I P Cleaners  
Aka: Morristown Tire  
Address: 89 Morris Street  
Municipality: Morristown State: New Jersey Zip Code: 07960  
County: Morris  
EPA ID No.: NJD982744740  
Block: 4801 Lot(s): 11  
Latitude: 40° 47' 47" Longitude: 74° 28' 40"  
Acreage: <1 SIC Code: 7216

Current Owner: P. Austin and W. Austin  
Mailing Address: P.O. Box 29  
City: Morris Plains State: New Jersey Zip Code: 07950  
Telephone No.: 201-267-8435

Current Operator: Sonny Din  
Mailing Address: 89 Morris Street  
City: Morristown State: New Jersey Zip Code: 07960  
Telephone No.: 201-539-2922

### Owner/Operator History:

<u>NAME</u>	<u>OPERATOR/ OWNER</u>	<u>FROM</u>	<u>DATES</u> <u>TO</u>
P. Austin, W. Austin	owner	1987	present
VIP Cleaners	operator	1989	present
The Finishing Touch	operator	1987	present
Isabel H. Austin	owner	1970	1987
William B. Austin	owner	1935 1942 1948	1970
Caroline Laundry	operator	unknown	1970
Sarah J. Austin	owner	unknown	1935
Philip W. Drake Doris S. Drake	owners	unknown	1942
Serena Salmon Ira P. Salmon	owners	unknown	1948

**Surrounding Land Use (zoning, adjacent properties):**

Land use in the vicinity of the VIP Cleaners site is primarily commercial and residential properties. ✓

**Distance to Nearest Residence:** 500 feet

**Direction:** east

**Population Density (residents per square mile):** 5,510

**PART II: SITE OPERATIONS**

**Discuss all current and past operations at the site.**

A review of aerial photographs indicate that the VIP Cleaners site was vacant until at least 1940. The existing building was evident in 1951 photographs but was not present in 1940 photographs indicating that the building was built within this time frame. Mr. Peter Austin indicated, during a December 1993 phone interview, that he had operated a Caroline Cleaners at the site until 1970 when the building was leased in parts to different stores and vendors. Operations of Caroline Cleaners dealt primarily with common laundering of clothes and other materials. Only a small portion of the operations involved dry cleaning. Mr. Austin indicated that dry cleaning chemicals were reused repeatedly and that the only loss of product was to the atmosphere via volatilization. Reportedly the site has always been on sanitary sewer and no floor drains existed at the site until they were installed by tenant Curt Bush, owner of The Finishing Touch car detailing operation approximately 6 years ago. This was verified by inspection of the Finishing Touch building after an inspection of the VIP Cleaners building.

(Attachment I)

Since the building was divided for lease in 1970, several different operations have been conducted at the site. These include a hospital laundry, lawn mower repair shop, hair salon, computer shop, auto detailing and audio, garden center and dry cleaners.

(Attachment H,I)

An inspection of the site was conducted by NJDEPE, Site Assessment personnel on December 13, 1993. At this time the current dry cleaning operation, VIP Cleaners, and the Finishing Touch auto detailing building were inspected. The entire interior of both of these buildings building were inspected and did not reveal any drains, dry wells or other pathways to ground water. Site representative of VIP Cleaners, Sonny Din, indicated that dry cleaning operations ceased at the site approximately 1 1/2 years ago and that only small scale cleaning of spots on garments is conducted on site. The VIP Cleaners store acts primarily as a drop off and pick up shop for clothes that are cleaned at other locations. The Finishing Touch details autos and installs audio equipment. No hazardous materials are used by the Finishing Touch operation.

(Attachment I)

The exterior of the building was also conducted and no areas of concern were observed. Current operations at the site include VIP Cleaners, The Finishing Touch auto detailing and Garden on the Green garden center.  
(Attachments H,I)

**PART III: PERMITS**

**A. NJPDES**

<u>Number</u>	<u>Discharge Activity</u>	<u>Date Issued</u>	<u>Expiration Date</u>	<u>Formation or Body of Water Discharged To</u>
---------------	---------------------------	--------------------	------------------------	---

N/A

**B. New Jersey Air Pollution Control Certificates**

Plant ID No.: L2527

No. of Certificates: 1 (094029)

Equipment Permitted: Dry Cleaning Machine

**C. BUST Registration**

Registration No.: 0228873

No. of Tanks: 1

<u>Tank No.</u>	<u>Capacity (gallons)</u>	<u>Contents of Tank</u>	<u>Integrity</u>
001	7,000	#6 Heating oil	Removed 2/92

(Attachment A)

**D. Other Permits**

<u>Agency Issuing Permit</u>	<u>Type of Permit</u>	<u>Permit No.</u>	<u>Date Issued</u>	<u>Expiration Date</u>
------------------------------	-----------------------	-------------------	--------------------	------------------------

N/A

#### **PART IV: GROUND WATER ROUTE**

##### **A. HYDROGEOLOGY**

**Describe geologic formations and aquifer(s) of concern. Include interconnections, confining layers, discontinuities, composition and permeability.**

Ground water in Morris County occurs in the voids in unconsolidated sediments and fractures in the underlying bedrock. Crystalline rocks of Precambrian age underlie almost the entire northwestern two-thirds of the county. They are primarily granitoid gneisses and pegmatites but include schists, crystalline limestone or marble, magnetite and a few small quartz veins. In most of the county Precambrian rocks are the only source of ground water. Quaternary rocks comprise the unconsolidated surficial deposits which mantle the bedrock surface. These deposits consist of clay, silt, sand, gravel and boulders. These stratified drift deposits form the mineral framework for the most developed ground water reservoir in the county.

**Depth to aquifer of concern:** <20 feet

**Thickness of aquifer:** unknown

**Direction of ground water flow:** unknown

**Karst (Y/N):** No

**Wellhead Protection Area (Y/N):** No  
(Attachments A,D)

**Distance:** N/A

##### **B. MONITORING WELL INFORMATION**

<u>Well No.</u>	<u>Screen Depth(feet)</u>	<u>Formation</u>	<u>Location</u>
MW-1	12-22	Glacial deposits	See site map

**Identify the upgradient well(s):** N/A  
(Attachment A)

**Briefly discuss why the monitoring wells were installed and describe contaminants identified in the monitoring wells. Include Well No., sampling date, sampling agency or company, contaminant levels and cleanup standards.**

Soil contamination was discovered in the excavation of a 7,000-gallon #6 heating oil tank which was removed from the site in February 13, 1992. Subsequently, a monitoring well was installed in the vicinity of the tank's previous location to determine if the tank had any impact on ground water. On September 24, 1992 representatives of the PMK Group of Union, New Jersey collected ground water samples from the subject well. The sample results indicate that trichloroethene, tetrachloroethene and trans-1,2-dichloroethene were present in the ground water at concentrations of 58, 510 and 69 parts per billion (ppb), respectively. The

NJDEPE Ground Water Quality Standards for trichloroethene, tetrachloroethene and trans-1,2-dichloroethene are 1, 1 and 100 ppb, respectively. In the analysis for base/neutral compounds, tetrachloroethene was identified to be present at a concentration of 99 ppb. Three additional unidentified base/neutral compounds were detected in concentrations ranging from 6 to 10 ppb. (Attachment B)

### C. POTABLE WELL INFORMATION

Distance to nearest potable well: 0.2 mile

Identify all public supply wells within 4 miles of the site:

<u>Water Company</u>	<u>Distance from site (miles)</u>	<u>Depth (feet)</u>	<u>Formation</u>
Southeast Morris County MUA	0.9	265	Brunswick
Southeast Morris County MUA	1.1-1.8 (5 wells)	58-496	Quaternary Dep. & Brunswick
Southeast Morris County MUA	2.1-2.9 (6 wells)	60-210	Quaternary Dep. & Brunswick
Southeast Morris County MUA	3.0-3.8 (3 wells)	60-124	Quaternary Dep.
Parsippany-Troy Hills	3.5 (2 wells)	87-90	Quaternary Dep.
Madison Borough	3.7	160	Quaternary Dep.
Florham Park Borough (Map 5)	3.8	105-139	Quaternary Dep.

Discuss private potable well use within 4 miles of the site. Include depth, formation and distance, if available.

A search of private wells was conducted by the PMK Group of Union, New Jersey during the underground tank removal and subsequent discharge investigation. Three domestic wells were identified within 1 mile of the site. The closest of these is approximately 0.2 mile south of the facility, screened in the Brunswick Formation at 320 feet. (Attachment C)

**Distance from site (miles)****Population utilizing ground water**

0 - 1/4	3
1/4 - 1/2	50
1/2 - 1	4,075
1 - 2	20,375
2 - 3	24,450
3 - 4	29,145

(Attachment C,F)

**Discuss any evidence of contaminated drinking water or wells closed due to contamination.**

Ground water contamination has been identified in the on-site monitoring well; however, no evidence exists to link this site with any local well closures.

(Attachment B)

**Identify industrial/irrigational wells within the vicinity of the site. Include depth, formation, distance and direction, if available.**

The closest industrial/irrigational well is located approximately 0.25 mile east of the site. This well is 298 feet deep, is screened in the Brunswick Formation, and is used by the Powers Motor Company for irrigational purposes.

(Map 5)

**D. POTENTIAL**

**Discuss the potential for ground water contamination, including any other information concerning the ground water contamination route.**

During the December 13, 1993 Pre-Sampling Assessment, no floor drains, septic or other direct pathway to ground water was discovered at the site. The site is entirely paved which should prevent contamination to ground water in the event of a spill or release. No evidence was discovered to link this site with the associated ground water contamination below the site.

(Attachment I)

**PART V: SURFACE WATER ROUTE****A. SURFACE WATER**

**Does a migration pathway to surface water exist (Y/N): No**

**Flood plain: >500 year (Map 7)**

**Slope: <3% (Map 1)**

**Does contaminated ground water discharge to surface water (Y/N): No**

Identify known or potentially contaminated surface water bodies. Follow the pathway of the surface water and indicate all adjoining bodies of water along a route of 15 stream miles.

<u>Surface Water Body</u>	<u>Distance from site</u>	<u>Flow(cfs)</u>	<u>Usage(s)</u>
---------------------------	-------------------------------	------------------	-----------------

No surface water pathway was identified for this site.  
(Map 1)

Identify drinking water intakes within 15 miles downstream (or upstream in tidal areas) of the site. For each intake identify the distance from the point of surface water entry, the name of the supplier and population served.

No surface water pathway was identified for this site.  
(Map 1)

Briefly discuss surface water or sediment sampling conducted in relation to the site. Discuss visual observations if analytical data is not available (include date of observation). Include surface water body, sampling date, sampling agency or company, contaminant.

No surface water pathway was identified for this site, therefore no sampling of sediments or surface water has occurred.

Discuss the potential for surface water contamination, include any additional information concerning the surface water route.

The V I P Cleaners site is entirely paved and all operations take place indoors. Contaminated runoff from this site is unlikely.  
(Attachment I)

#### B. SENSITIVE ENVIRONMENTS

Identify all sensitive environments, including wetlands, along the 15 stream-mile pathway from the site:

<u>Environment Type</u>	<u>Surface Water Body</u>	<u>Flow (cfs)</u>
-------------------------	---------------------------	-------------------

No surface water pathway was identified for this site.  
(Map 1)

## **PART VI: AIR ROUTE**

### **Discuss observed or potential air release.**

An air permit has been issued to VIP Cleaners for a dry cleaning machine. Currently, no cleaning of materials is conducted on-site. The potential for an air release at this site is minimal.  
(Attachment I)

### **Populations that reside within 4 miles of the site.**

<u>Distance (miles)</u>	<u>Population</u>
0 - 1/4	1,080
1/4 - 1/2	3,245
1/2 - 1	5,875
1 - 2	13,285
2 - 3	6,260
3 - 4	29,145

(Attachment J)

### **Identify sensitive environments and wetland acreage within 1/2 mile of the site.**

No sensitive environments or wetland acreage was identified within 0.5 mile of the site.  
(Map 6)

## **PART VII: SOIL EXPOSURE**

### **Describe soil type. Include soil series, makeup of the soil and permeability of the soil.**

The United States Department of Agriculture, Soil Conservation Service lists the soils below the site as Urban land series-Riverhead complex. The Urban land series are areas that have been cut or reworked to the extent that the original profile cannot be recognized. The characteristics of the material are variable. The Riverhead complex typically consists of well-drained, nearly level to strongly sloping sandy and gravelly soils. Slopes range from 0 to 20 percent, but are typically 5 to 12 percent. The underlying material is loose, unweathered, stratified and sorted sand and gravel outwash, mostly of granitic material that contains some shale, sandstone, quartzite and conglomerate. Coarse fragments are mainly gravel and cobbles, but in a few places there are stones and boulders. Permeability is rapid and runoff is moderate.  
(Attachment G)



**Briefly discuss contaminants identified in the soil. Include sampling date, sampling agency or company, sample locations, depth and contaminant level.**

On February 20 and 21, 1992, eight soil samples were collected by the PMK Group of Union, New Jersey within the excavation of the 7,000-gallon underground storage tank which was removed on February 10, 1992. Seven of the samples were collected at 9.5 feet below normal grade at various locations of the excavation and analyzed for petroleum hydrocarbons (TPHC). Two of the samples displayed contamination at 74 and 875 parts per million (ppm) TPHC. The sample with the highest TPHC concentration (875 ppm) was sampled again on February 21, 1992, one foot below the original sample at 10.5 feet, and analyzed for TPHC and base/neutral compounds. This sample revealed TPHC contamination at 210 ppm with no base/neutral compounds detected.  
(Attachment B)

**If no soil sampling has been conducted, discuss areas of potentially contaminated soil, areas that are visually contaminated or results from soil gas surveys.**

The entire site was paved at the time of inspection. No soil gas surveys could be conducted at this time. No areas of stained soil were observed.  
(Attachment I)

**Number of people that occupy residences or attend school or day care on or within 200 feet of the site: 0**  
**Number of workers on or within 200 feet of the site: 20**

**Does a subsurface gas threat exist? (Y/N): No**  
**If so, discuss the threat (include if in homes or occupied building).**

#### **PART VIII: DIRECT CONTACT**

**Describe accessibility of the site (fencing, site security, evidence of unauthorized entry).**

The VIP Cleaners site is not fenced; however, operations take place indoors which would prevent a direct contact threat by unauthorized personnel.

**Number of on-site employees: 10**

## **PART IX: FIRE AND EXPLOSION**

Discuss all incidents on site which have involved a fire or explosion. Indicate the date of the incident and the materials involved.

No incidents of fire were discovered during the file search.

Discuss site conditions which indicate a potential exists for fire or explosion (reactivity, incompatibility, ignitability, storage practices, container condition).

Flammable materials are used at the site; however, they are used in relatively small quantities and are not stored in a manner which would create an explosion or fire threat.

## **PART X: ADDITIONAL CONSIDERATIONS**

Discuss evidence of wildlife or vegetation that has been or could be potentially impacted by on-site operations. Include areas exhibiting stressed vegetation or damage to wildlife.

Operations at this site do not appear to be causing adverse affects on surrounding wildlife or vegetation.

Determine if a contaminant on site displays bioaccumulative properties. Name all bioaccumulative substances that may impact the food chain.

Contaminants detected at the V I P Cleaners site are not bioaccumulative in nature.

Discuss observed or potential damage to off-site property. Consider migration routes from the site to an off-site property via soil, air or runoff.

Operations conducted at the VIP Cleaners site do not pose a threat to surrounding properties.

## **PART XI: PREVIOUS OR ONGOING REMEDIAL ACTIONS**

Discuss for each media all previous and ongoing remedial activities at the site. Include why initiated, type of action, date and present status.

In February 1992 a 7,000-gallon underground storage tank of #6 fuel oil was removed by Anco Environmental Contracting Inc. under the supervision of the PMK Group of Union, New Jersey. As a result of the tank removal, approximately 130 tons of contaminated soil were

removed from the excavation. Subsequently, a monitoring well was installed to determine if ground water was impacted by the tank. Sample results did not indicate a release to ground water had occurred; however, tetrachloroethene (PCE), trichloroethene (TCE) and trans-1,2-dichloroethene were detected in the ground water. Ground Water Quality Standards were exceeded for PCE and TCE. It is possible that historic dry cleaning operations may have contributed to this ground water contamination. Currently, this case is closed within the NJDEPE, Bureau of Underground Storage Tanks.

(Attachments A,B)

## **PART XII: ENFORCEMENT ACTIONS**

No enforcement actions were discovered for the VIP Cleaners site during the file search.

## **PART XIII: CONCLUSIONS AND RECOMMENDATIONS**

Historic and recent operations at this site have used chlorinated solvents; however, no evidence was discovered during the file search and subsequent inspection of the site to link it with the discovered ground water contamination. A review of historic aerial photographs found no suspect areas at the site. No pathway to ground water was discovered. It is recommended that additional monitoring wells be installed both upgradient and downgradient to determine if the site is a source of ground water contamination.

**Submitted by:** David Dibblee

**Title:** HSMS IV

**NJDEPE, Bureau of Field Operations - Site Assessment Section**

**Date:** December 20, 1993


**PART XIV: POTENTIALLY RESPONSIBLE PARTIES**

<u>NAME</u>	<u>OWNER/OPERATOR/ KNOWN DISCHARGER</u>	<u>CURRENT ADDRESS</u>
Caroline Laundry	operator	c/o Peter Austin P.O. Box 29 Morris Plains, New Jersey 07950

MAPS



**MORRIS STREET**




**VIP CLEANERS  
89 MORRIS STREET  
MORRISTOWN, MORRIS COUNTY  
SITE MAP, MAP #2**

**NOT TO SCALE**







V I P CLEANERS  
89 MORRIS STREET  
MORRISTOWN, MORRIS COUNTY  
COUNTY ROAD MAP  
MAP #4

LATITUDE 404747  
LONGITUDE 742840

DRAFT


SCALE: 1:63,360  
(1.5 Inch = 1 Mile)

\* 100,000 GPD WATER WITHDRAWAL POINTS ONLY

1 MILE AND 5 MILE RADII INDICATED

PLOT PRODUCED BY:  
NJDEPE  
WATER SUPPLY ELEMENT  
BUREAU OF WATER ALLOCATION  
CN-426  
TRENTON, NJ 08625

DATE: 09/29/93



SUBJECT TO REVISION

NUMBER	NAME	SOURCEID	LOCID	LAT	LON	LLACC	DISTANCE	COUNTY	MUN	DEPTH	GEO1	GEO2	CAPACITY
10015W	SUBURBAN PROPANE	2511349	3	404919	742425		4.1	27	12	75	GOSD		100
10021W	SISTERS CHARITY ST ELIZABETH	2522434	#1	404705	742547		2.6	27	11	300	GTRB		525
10068W	PRECISION ROLLED PRODUCTS, INC	2510680	1	404750	742413	T	3.9	27	10	107	GOSD		500
10180W	J & P & L/MORRISTOWN OFFICE	2511968	1	404656	742700	F	1.8	27	22	600	GTRB		150
10248W	CHATHAM TOWNSHIP/COLONY POOL	2515137	#1	404408	742347	T	6.0	27	05	293			100
10297W	SCHERING-PLOUGH CORPORATION	2523876		404659	742726		1.4	27	17	165	GOSU		90
10395W	CARTERET SAVINGS & LOAN ASSOC.	2503936	WELL 1	404715	742815	T	0.7	27	24	500			150
	CARTERET SAVINGS & LOAN ASSOC.	2515508	WELL 2	404725	742825	T	0.5	27	24	500			125
10396W	CHEMICAL BANK OF NEW JERSEY NA	2502685	1	404710	742733		1.2	27	24	300	GTRB		300
10464W	HAMILTON PARK ASSOCIATES	2526568	WELL 1	404652	742442	T	3.6	27	11	330			400
10554W	NEW JERSEY BELL TELEPHONE	2513372	1	404944	742622	F	3.0	27	12	198	GOSD		120
10575W	SCHINDLER ELEVATOR CORP.		2	405139	743241	F	5.7	27	32	50	GOSD		200
	SCHINDLER ELEVATOR CORP.	2526977	3	405139	743241	F	5.7	27	32	75	GOSD		545
10615W	MORRIS TOWNSHIP/CANCELLED	PROPOSED		404833	743010	T	1.6	27	22				
2021P	SPRING BROOK COUNTRY CLUB	POND	1	404651	742940	F	1.4	27	24		SP		600
2025P	MORRIS COUNTY GOLF CLUB	2510487	1	404702	742632	F	2.1	27	24	271	GOSD		175
	MORRIS COUNTY GOLF CLUB	2516215	2	404701	742640	F	2.0	27	24	238	GOSD		15
	MORRIS COUNTY GOLF CLUB		POND	404710	742630	F	2.0	27	24	14	GOSD		1100
	MORRIS COUNTY GOLF CLUB	2534663	3	404702	742629	F	2.1	27	24	292	GOSD		150
2078P	MENNEN COMPANY	2501891	1	404847	742822	F	1.2	27	22	85	GOTM		200
	MENNEN COMPANY	2513682	2	404848	742821	F	1.2	27	22	100	GOTM		200
2117P	ALLIED-SIGNAL INC.	2504286	1	404726	742623	F	2.0	27	22	767	GTRB		100
	ALLIED-SIGNAL INC.	2509253	2	404729	742608	F	2.2	27	22	188	GOSU		200
	ALLIED-SIGNAL INC.	2515313	4 NOT USED	404719	742656	F	1.6	27	22	253	GOSU		0
	ALLIED-SIGNAL INC.	2522302	10	404725	742613	F	2.2	27	22	198	GOSU		200
	ALLIED-SIGNAL INC.	2529037	14	404735	742639	F	1.8	27	22	235	GOSU		230
2118P	SANDOZ PHARMACEUTICALS CORP.	4500044	1	404836	742338		4.5	27	10	49	GOSD		500
	SANDOZ PHARMACEUTICALS CORP.	4500045	2	404829	742338		4.5	27	10	58	GOSD		500
	SANDOZ PHARMACEUTICALS CORP.	2500635	3	404821	742336		4.5	27	10	81	GOSD		500
	SANDOZ PHARMACEUTICALS CORP.	2513934	4	404812	742335		4.5	27	10	84	GOSD		500
	SANDOZ PHARMACEUTICALS CORP.	2513935	5	404818	742350		4.3	27	10	132	GOSD		500
2195P	WARNER LAMBERT COMPANY	2500695	3	405026	742842		3.0	27	23	102	GOSD		150
	WARNER LAMBERT COMPANY	2503447	4	405023	742835		3.0	27	23	70	GOSD		250
	WARNER LAMBERT COMPANY	2504274	6	405038	742823		3.3	27	23	102	GOSD		500
2196P	MORRISTOWN MEMORIAL HOSPITAL	2505647	1	404720	742720		1.3	27	24	504	GTRB		300
	MORRISTOWN MEMORIAL HOSPITAL	2506577	2	404712	742750		1.0	27	24	507	GTRB		300
2206P	PFIZER, INC.-CONSUMER PRODUCTS	2506488	1	405105	742512	F	4.9	27	29	95	GOSD		275
	PFIZER, INC.-CONSUMER PRODUCTS	2511876	3	405105	742518	F	4.8	27	29	85	GOSD		450
	PFIZER, INC.-CONSUMER PRODUCTS	4500256	4	405108	742514	F	4.9	27	29	85	GOSD		450
	PFIZER, INC.-CONSUMER PRODUCTS	2528629	6	405105	742515	T	4.8	27	29		GOSD		
2271P	GREYSTONE PSY. HOSP. SEE 5300	2514303	WELL #1-67	404940	742955		2.4	27	29	298	GTRB		150
	GREYSTONE PSY. HOSP. SEE 5300	2514417	WELL #2-67	404940	742955		2.4	27	29	270	GTRB		200
2304P	NDE PIERSON CORPORATION	4500306	1	404415	742534		4.9	27	04	294	GTRB		200
2305P	FAIRMOUNT COUNTRY CLUB	4500084	1	404425	742510		4.9	27	04	390	GTRB		325
2333P	BOONTON ELECTRONICS	2525494	5	405126	742455	F	5.3	27	29	78	GOSD		200
2339P	EXXON RESEARCH & ENGINEERING	2500067	1	404650	742500	U	3.4	27	11	250	GOTM		60
	EXXON RESEARCH & ENGINEERING	2515953	RAW-3	404647	742527	F	3.0	27	11	88	GOTM		0
	EXXON RESEARCH & ENGINEERING	2506994	FW-1	404648	742517	F	3.2	27	11	94	GOTM		1030
	EXXON RESEARCH & ENGINEERING	2514658	EM-2	404632	742518	F	3.3	27	11	88	GOTM		24
	EXXON RESEARCH & ENGINEERING	4500326	DEWELL DB4	404649	742545	F	2.8	27	11		GOTM		0
2342P	MORRIS COUNTY PARK COMMISSION	4500355	WELL 1	404728	742320	F	4.7	27	11	250	GTRB		313
	MORRIS COUNTY PARK COMMISSION	STORAGE POND	POND	404728	742310	F	4.8	27	11	14	GOS		1100
2358P	MENDHAM GOLF AND TENNIS CLUB	2514439	WELL #1	404639	743402		4.9	27	19	75	GOTM		50
	MENDHAM GOLF AND TENNIS CLUB	2514799	WELL #2	404638	743404		4.9	27	19	50	GOTM		140
	MENDHAM GOLF AND TENNIS CLUB	POND 1		404640	743400		4.8	27	19		G		

NUMBER	NAME	SOURCEID	LOCID	LAT	LON	LLACC	DISTANCE	COUNTY	MUN	DEPTH	GEO1	GEO2	CAPACITY
5013	MENDHAM GOLF AND TENNIS CLUB	POND 2		404640	743400		4.8	27	19		G		
5046	NEW JERSEY-AMERICAN WATER CO.	2510173	N.E. WELL	404340	743250	T	6.0	35	02	1450	GTRB		350
	CHATHAM BOROUGH	4500270	1	404439	742323		5.9	27	05	143	GCSD		1050
	CHATHAM BOROUGH	4500271	2	404439	742323		5.9	27	05	140	GCSD		560
	CHATHAM BOROUGH	2505687	3	404439	742323		5.9	27	05	150	GCSD		1200
5058	MORRIS COUNTY MUA	2510770	MUSIKER 1	404937	743345	F	4.9	27	32	130	GFC		375
5069	MADISON BOROUGH	2501962	A	404505	742355		5.2	27	17	130	GCSD		750
	MADISON BOROUGH	2504207	B	404505	742355		5.2	27	17	143	GCSD		1200
	MADISON BOROUGH	2504209	C	404524	742554		3.7	27	17	160	GCSD		1200
	MADISON BOROUGH	2504423	D	404514	742405		5.0	27	17	181	GCSD		1000
	MADISON BOROUGH	2514041	E-STANDBY	404505	742355		5.2	27	17	140	GCSD		1500
5072	EAST HANOVER TOWNSHIP	2514205	2	404856	742322	F	4.8	27	10	115	GCSD		1000
	EAST HANOVER TOWNSHIP	2513672	1	404854	742318	F	4.9	27	10	130	GCSD		500
5214	FLORHAM PARK BOROUGH	4500299	2	404713	742423	S	3.8	27	11	105	GCSD		1000
	FLORHAM PARK BOROUGH	2521204	4	404713	742423	S	3.8	27	11	139	GCSD		1300
5236	PARSIFFANY-TROY HILLS	2507381	1A	405206	742530	F	5.7	27	29	138	GCSD		420
	PARSIFFANY-TROY HILLS	4500032	3	405206	742358	F	6.4	27	29	75	GCSD		350
	PARSIFFANY-TROY HILLS	4500033	4	405205	742502	F	5.9	27	29	82	GCSD		225
	PARSIFFANY-TROY HILLS	2507545	4A	405205	742502	F	5.9	27	29	150	GCSD		900
	PARSIFFANY-TROY HILLS	2507620	7	405102	742506	F	4.9	27	29	66	GCSD		500
	PARSIFFANY-TROY HILLS	4500034	B-1	405033	742343	F	5.4	27	29	90	GCSD		300
	PARSIFFANY-TROY HILLS	4500035	B-2	405033	742343	F	5.4	27	29	80	GCSD		400
	PARSIFFANY-TROY HILLS	4500036	B-3	405033	742343	F	5.4	27	29	80	GCSD		600
	PARSIFFANY-TROY HILLS	2511628	10	405204	742618	F	5.3	27	29	129	GCSD		500
	PARSIFFANY-TROY HILLS	2512635	11	405050	742320		5.8	27	29	80	GCSD		70
	PARSIFFANY-TROY HILLS	2512718	12	405140	742540	F	5.2	27	29	100	GCSD		300
	PARSIFFANY-TROY HILLS	2511106	13	405112	742258	F	6.3	27	29	47	GCSD		425
	PARSIFFANY-TROY HILLS	2513259	14	405031	742650	F	3.5	27	29	90	GCSD		700
	PARSIFFANY-TROY HILLS	2515809	15	405031	742650	F	3.5	27	29	87	GCSD		150
	PARSIFFANY-TROY HILLS	2527259	20	405120	742425		5.5	27	29	95	GCSD		700
	PARSIFFANY-TROY HILLS	PROPOSED	21	405123	742637	U	4.5	27	29	85	GCSD		1400
5264	SOUTHEAST MORRIS COUNTY MUA	2514520	LIDGERWOOD	404700	742835	F	0.9	27	24	265	GTRB		410
	SOUTHEAST MORRIS COUNTY MUA	2513439	TURNBULL	404708	742741	F	1.1	27	24	496	GTRB		450
5299	SOUTHEAST MORRIS COUNTY MUA	4500350	SAND SPRG	404540	743017	F	2.8	27	13	94	GTRB		600
	SOUTHEAST MORRIS COUNTY MUA	2500048	WING	404941	742645	F	2.8	27	12	136	GCSD		3200
	SOUTHEAST MORRIS COUNTY MUA	2503527	TODD	404948	742645	F	2.9	27	12	144	GCSD		1200
	SOUTHEAST MORRIS COUNTY MUA	2514181	BLACK BRK 1	404751	742429	F	3.7	27	12	124	GCSD		1400
	SOUTHEAST MORRIS COUNTY MUA	2514182	BLACK BRK 2	404802	742422	F	3.8	27	12	122	GCSD		1400
	SOUTHEAST MORRIS COUNTY MUA	4500351	NORMANDY	404750	742540	F	2.6	27	12	80	GCSD		400
5300	SOUTHEAST MORRIS COUNTY MUA	4500038	WELL NO. 1	404920	742905	F	1.8	27	23	138	GCSD		300
	SOUTHEAST MORRIS COUNTY MUA	4500039	WELL NO. 2	404920	742901	F	1.8	27	23	125	GCSD		500
	SOUTHEAST MORRIS COUNTY MUA	2508493	WELL NO. 3	404920	742858	F	1.8	27	23	139	GCSD		500
	SOUTHEAST MORRIS COUNTY MUA	2508627	WELL NO. 4	404920	742858	F	1.8	27	29	58	GCSD		100
	SOUTHEAST MORRIS COUNTY MUA	2514034	SHONGUM	404932	742946	F	2.2	27	22	150	GTRB		400
	SOUTHEAST MORRIS COUNTY MUA	4500316	WELL #1	405019	742755	F	3.0	27	29	60	GCSD		350
	SOUTHEAST MORRIS COUNTY MUA	4500317	WELL #2	405011	742747	F	2.9	27	12	60	GCSD		400
5371	SOUTHEAST MORRIS COUNTY MUA	2533503	MOORE EST.	404620	742713	F	2.1	27	22	210	GCSD		600
PRO011	ARNOLD FARMS	SILVER CREEK	STREAM 1	404543	742915	F	2.4	27	13		SPUPP		1200

Number of Observations: 103

WATER WITHDRAWAL POINTS  
REFERENCE SHEET

THE FOLLOWING CODES DENOTE THE TYPE OF WELL OR SURFACE WATER INTAKE  
AS LISTED ON WATER WITHDRAWAL POINTS MAPS.

- 1000D - DEWATERING PERMIT OR TEMPORARY PUMPING PERMIT
  - 2000 - INDUSTRIAL PERMITS, GOLF COURSES AND REMEDIATION PUMPING  
PERMITS
  - 4000 - SURFACE DIVERSION AND SURFACE WATER INTAKES
  - 5000 - PUBLIC WATER SUPPLY WELLS
  - 10000 - WELLS WITH THE CAPACITY TO PUMP >100,000 GALLONS BUT DO  
NOT
  - XX0000 - AGRICULTURAL CERTIFICATION, FIRST TWO LETTERS ARE THE  
FIRST TWO LETTERS OF THE COUNTY IN WHICH THE PERMIT IS  
ISSUED.
- P - PRIVATE WELL  
PS - PRIVATE SURFACE INTAKE

# CODES USED IN THE WATER WITHDRAWAL POINTS LISTING

This packet contains information on the database codes that the Bureau of Water Allocation uses in the Water Withdrawal Points Listing.

COUNTY:	01 - Atlantic	15 - Gloucester	29 - Ocean
	03 - Bergen	17 - Hudson	31 - Passaic
	05 - Burlington	19 - Hunterdon	33 - Salem
	07 - Camden	21 - Mercer	35 - Somerset
	09 - Cape May	23 - Middlesex	37 - Sussex
	11 - Cumberland	25 - Monmouth	39 - Union
	13 - Essex	27 - Morris	41 - Warren

GEO: RECENT  
Surficial Deposits

GRS

PLEISTOCENE  
Glacial Undifferentiated  
Stratified Drift  
Terminal Moraine  
Bridgeton  
Cape May  
Holly Beach Mbr.  
Estuarine Sand  
Pennsauken

GQGU  
GQSD  
GQTM  
GQBS  
GQCM  
GQCHB  
GQES  
GQPS

## TERTIARY

Beacon Hill -  
Cohansey  
Cohansey & Kirkwood  
Kirkwood  
Upper  
Rio Grande  
Lower  
Piney Point Mbr.  
Shark River Marl  
Manasquan Marl  
Vincentown Sand  
Hornerstown Marl

GTBH  
GTCH  
GTCK  
GTKW  
GTKWU  
GTKRG  
GTKWL  
GTKPP  
GTSR  
GTMQ  
GTVT  
GTHT

## CRETACEOUS

Red Bank  
Navesink  
Mount Laurel  
Wenonah  
Mount Laurel & Wenonah  
Marshalltown  
Englishtown  
Woodbury  
Merchantville  
Magothy

GKRB  
GKNS  
GKML  
GKWE  
GKMW  
GKMT  
GKET  
GKWB  
GKMV  
GKM

Old Bridge	GKROB
Raritan	GKR
Sayreville Sand	GKRSS
Farrington	GKRF
Raritan/Magothy	GKMR
Potomac	GKP
 TRIASSIC	
Brunswick Formation	GTRB
Lockatong Formation	GTRL
Stockton Formation	GTRS
Basalt	GTRBS
Diabase	GTRDB
Conglomerate	GTRCG
 DEVONIAN	
Undifferentiated	GD
 SILURIAN	
Bossardville Limestone	GSBD
Decker Formation	GSPK
Longwood Shale	GSLS
Poxono Island Fm	GSPI
Greenpond Conglomerate	GSGP
High Falls	GSHF
Shawangunk Fm	GSSG
 ORDOVICIAN	
Martinsburg Fm	GOMB
Jacksonburg Fm	GOJB
Kittatinny Group	GOK
Outleane Fm	GOKO
Harmonyvale Mbr	GOKOH
Beaver Run Mbr	GOKOB
Epler	GOKE
Rickenbach	GOKR
 CAMBRO ORDOVICIAN	
Kittatinny Fm	GCOK
 CAMBRIAN	
Hardyston Quartzite	GCH
Allentown Fm	GCKA
Upper Mbr	GCKU
Limeport Mbr	GCKLP
Leithsville Fm	GCKL
Walkill Mbr	GCKLW
Hamburg Mbr	GCKLH
Califon Mbr	GCKLC
 PRECAMBRIAN	
Granite	GPCGR
Gneiss	GPCGN
Undifferentiated	GPC

# Franklin Lms

## DELAWARE RIVER BASIN

Unknown or Non-Specific  
 Alloways Creek  
 Alexsocken Creek  
 Assiscunk Creek  
 Assunpink Creek  
 Big Timber Creek  
 Blacks Creek  
 Cooper's Creek  
 Crafts Creek  
 Crosswicks Creek  
 Delaware River  
 Flat Brook  
 Hakiwokake Creek  
 Hariwokake Creek  
 Jacob's Creek  
 Lockatong Creek  
 Lopatcong Creek  
 Mantua Creek  
 Musconetcong River  
 Nichisakawick Creek  
 Old Man's Creek  
 Paulins Kill  
 Pennsauken Creek  
 Pequest River  
 Pohatcong Creek  
 Raccoon Creek  
 Rancocas Creek  
 Salem River  
 Wickecheoke Creek

## RARITAN RIVER BASIN

Unknown or Non-Specific  
 Lawrence Brobk  
 Lower Raritan  
 Millstone River  
 North Branch Raritan  
 South Branch Raritan  
 South River

## PASSAIC RIVER BASIN

Unknown or Non-Specific  
 Canoe Brook  
 Lower Mid-Passaic River  
 Lower Passaic  
 Passaic River  
 Peckman River  
 Pequannock River  
 Pompton River  
 Ramapo River  
 Rockaway River  
 Saddle River

## GPCFL

SD  
 SDALL  
 SDALE  
 SDASC  
 SDASP  
 SDBIG  
 SDBLA  
 SDCOO  
 SDCRA  
 SDCRO  
 SDDLE  
 SDFLA  
 SDHAK  
 SDHAR  
 SDJAC  
 SDLOC  
 SDLOP  
 SDMNT  
 SDMUS  
 SDNIC  
 SDOLD  
 SDPAU  
 SDPEN  
 SDPST  
 SDPOH  
 SDRAC  
 SDRAN  
 SDSAL  
 SDWIC

SR  
 SRLAW  
 SRLOW  
 SRMIL  
 SRNBR  
 SRSBR  
 SRSRV

SP  
 SPCAN  
 SPLMP  
 SPLOW  
 SPPAS  
 SPPEC  
 SPPNK  
 SPPOM  
 SPRAM  
 SPROC  
 SPSAD



Upper Mid-Passaic River  
 Upper Passaic River  
 Wanaque River  
 Whippany River

SPUMP  
 SPUPP  
 SPWAN  
 SPWHI

ATLANTIC COASTAL BASIN  
 Unknown or Non-Specific  
 Atlantic County Coastal  
 Cape May County Coastal  
 Cedar Creek  
 Great Egg Harbor River  
 Manasquan River  
 Metedeconk River  
 Monmouth County Coastal  
 Mullica River  
 Navesink River  
 Ocean County Coastal  
 Raritan Bay  
 Shark River  
 Shrewsbury River  
 Toms River  
 Tuckahoe River

SC  
 SCATL  
 SCCAP  
 SCCED  
 SCGRE  
 SCMSQ  
 SCMET  
 SCMON  
 SCMUL  
 SCNAV  
 SCOCE  
 SCRAR  
 SCSHA  
 SCSHR  
 SCTOM  
 SCTUC

HUDSON RIVER BASIN  
 Unknown or Non-Specific  
 Hudson River  
 Papakating Creek  
 Pochuck Creek  
 Wallkill River

SH  
 SHHUD  
 SHPAP  
 SHPOC  
 SHWAL

HACKENSACK RIVER BASIN  
 Unknown or Non-Specific  
 Hackensack River

SK  
 SKHAC

RAHWAY RIVER BASIN  
 Unknown or Non-Specific  
 Rahway River

SY  
 SYRAH

ELIZABETH RIVER BASIN  
 Unknown or Non-Specific  
 Elizabeth River


SE  
 SEELI

DELAWARE BAY BASIN  
 Unknown or Non-Specific  
 Cohansey River  
 Maurice River  
 Stow Creek

SB  
 SBCOH  
 SBMAU  
 SBSTO

LLACC:

S - accurate to +- 1 second  
 F - accurate to +- 5 seconds  
 T - accurate to +- 10 seconds  
 M - accurate to +- 1 minute  
 U - accuracy unknown



VIP CLEANERS  
89 MORRIS STREET  
MORRISTOWN, MORRIS COUNTY  
MAP #6  
NATIONAL WETLANDS INVENTORY

**NATIONAL FLOOD INSURANCE PROGRAM**

**FIRM**  
**FLOOD INSURANCE RATE MAP**

TOWN OF  
**MORRISTOWN,**  
**NEW JERSEY**  
MORRIS COUNTY

**MAP INDEX**

PANELS PRINTED: 1, 2

**COMMUNITY-PANEL NUMBERS**


**340352 0001-0002**

**MAP REVISED:**

**JULY 3, 1986**



Federal Emergency Management Agency



340352 0002 D

ATTACHMENT A



*State of New Jersey*  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 DIVISION OF WATER RESOURCES  
 CN 029  
 Trenton, N.J. 08625-0029  
 ATTN: BUST Program  
 (609) 984-3156

For State Use Only

Date Rec'd. \_\_\_\_\_  
 Auth. \_\_\_\_\_  
 Routing \_\_\_\_\_  
 UST NO. \_\_\_\_\_

STANDARD REPORTING FORM  
 for reporting activities at an UST facility:

- |   |   |
|---|---|
| <input type="checkbox"/> General Facility Information Changes<br><input checked="" type="checkbox"/> Closure (Abandonment or Removal)<br><input type="checkbox"/> Temporary Closure<br><input type="checkbox"/> Change in Service | <input type="checkbox"/> Sale or Transfer<br><input type="checkbox"/> Substantial Modification<br><input type="checkbox"/> Financial Responsibility<br><input type="checkbox"/> Address Change Only |
|---|---|

Check ONLY One Type of Activity – Complete Form For That Activity

(More than one tank can be listed per activity)

\*\*\* NOTE \*\*\* ALL NEW tank installations at existing registered  
 facilities must submit a Registration Questionnaire for the new tanks.

Answer questions 1 through 5 and others as applicable.

1. Company name and address (as it appears on registration questionnaire):
 

P. AUSTIN, W. AUSTIN  
POST OFFICE BOX 29  
MORRIS PLAINS, NEW JERSEY 07950
2. Facility name and location (if different from above):
 

MORRISTOWN TIRRE  
89 MORRIS STREET  
MORRISTOWN, NEW JERSEY 07960
3. Contact person for this activity:
 

JAMES JOHNSTON, P.E.  
 Telephone Number: ( 908 , ) 686-0044
4. The identification number of the affected tank as it appears in Question Number 12 on the Registration Questionnaire:
 

P1 (0001)
5. Registration Number (if known):
 

UST - 0228873
6. For GENERAL FACILITY INFORMATION changes (address, telephone, contact person, etc. – supply NEW information only):
  - a. Facility name: PETER AUSTIN
  - b. Facility location: \_\_\_\_\_
  - c. Owner's mailing address: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_ NJ \_\_\_\_\_
  - d. Block: \_\_\_\_\_ Lot: \_\_\_\_\_
  - e. Contact person (facility operator): PETER AUSTIN
  - f. Contact telephone number: ( 201 ) 267-8435 - \_\_\_\_\_
  - g. Other (Specify): \_\_\_\_\_

ATTACHMENT AI



September 27, 1991

**PRINCIPALS:**

Philip M. Keegan  
James Ferris, P.E.  
Gerald Perricone, P.E.  
James Johnston, P.E.

New Jersey Department of  
Environmental Protection and Energy  
Division of Responsible Party Site Remediation  
Bureau of Underground Storage Tanks  
CN029  
Trenton, New Jersey 08625-0029

Attn: Ms. Diane Pupa

**UNDERGROUND STORAGE TANK CLOSURE PLAN  
MORRISTOWN TIRE  
89 MORRIS AVENUE  
MORRISTOWN, NEW JERSEY  
PMK, F&P #5182**

Dear Ms. Pupa:

INTRODUCTION

This report presents the underground storage tank closure plan for the underground storage tank removal which will be performed at the Morristown Tire facility located at 89 Morris Avenue in Morristown, New Jersey. The underground storage tank (UST) scheduled for removal is a 5,000 gallon #6 heating oil tank.

SITE ASSESSMENT PLAN

A site assessment plan will be implemented during the underground storage tank removal to evaluate the potential that soil and/or groundwater have been impacted by releases and/or discharges from the subject underground storage tank system. During the course of the removal operations, a representative of PMK, Ferris & Perricone, Inc. will be on-site to visually observe the excavation for evidence of discolored soils, soil staining, free product and/or odors indicative of a product release. Where feasible, field test methods will be utilized to determine the presence of residual saturation of contaminants within the soil in accordance with the recommended procedures in the NJDEPE document "Appendix 10 Soil Sampling and Analysis Requirements". Our representative would utilize portable field screening equipment to evaluate the potential presence of organic vapors within the soils located adjacent to the tank. In the event that there is no visual evidence of soil contamination and field screening equipment does not indicate the presence of elevated levels of organic vapor, sampling will be performed on the soil located below the subject tank. All samples will be extracted from the natural soils located

New Jersey Department of  
Environmental Protection and Energy  
September 27, 1991  
Page Two

below the tank bedding material. Biased samples would be obtained where field screening methods indicate the presence of elevated levels of organic vapors.

Based on the reported product historically stored within the tank, it is anticipated that the following sample frequency and parameters for analysis will be implemented as part of the sampling plan:

5,000 gallon #2 Heating Oil USTs:	7	Total	Petroleum
	Hydrocarbon		(TPH)
	Analysis		

\*If any of the samples are observed to have a TPH concentration in excess of 100 parts per million (ppm), the two highest samples in excess of 100 ppm would be subject to Base Neutral +15 analysis in accordance with EPA Method 625 +15.

Any of the above samples which is found to have TPH concentrations in excess of 500 ppm would be subjected to an Acid-Base Partition Clean-Up in accordance with EPA Test Method 3650, as presented in the EPA publication Test Methods for Evaluating Solid Waste.

Based on available information, there does not appear to be any product bearing piping runs in excess of 15 feet. In the event that significant piping runs are encountered, one sample for each additional 15 feet would be obtained. These samples would be subject to the same laboratory analysis as detailed above.

In the event that a discharge is confirmed by our visual observations and/or field screening methods, the owner shall notify the NJDEPE Environmental Hotline and provide information regarding the nature, scope and extent of the subject release.

All soil sampling operations will be performed in accordance with the guidelines presented in the NJDEPE Field Sampling Procedures Manual and the NJDEPE Interim Closure Requirements for USTs. Soil samples will be obtained using a stainless steel hand trowel, placed in a laboratory prepared sample jar, and capped with lined lids. Sampling equipment will be decontaminated between sample locations to prevent potential cross contamination between sampling events. The samples will be transmitted to a New Jersey certified



New Jersey Department of  
Environmental Protection and Energy  
September 27, 1991  
Page Three

laboratory for chemical analysis for the above noted parameters using appropriate chain of custody procedures.

Based on the tank closure requirements of the New Jersey Underground Storage Tank regulations, groundwater assessment is not required for the closure of USTs containing heating fuel. Consequently groundwater monitoring wells are not proposed as part of this closure plan.

#### TANK DECOMMISSIONING PLAN

The procedures used to perform the excavation, removal and disposal of the subject underground storage tank system shall be in conformance with the requirements of the American Petroleum Institute Recommended Practice 1604 (API 1604).


The tank removal procedures consist of the following procedures:

1. The tank will be cleaned and washed in accordance with the recommended procedures of API Publication 2015, "Cleaning Petroleum Storage Tanks", and the National Fire Protection Association Publication 327, "Standard Procedures for Cleaning or Safeguarding Small Tanks and Containers".
2. The tank removal area will be prepared by cleaning the site, setting up barricades, and setting up storage areas using 6 mil plastic.
3. The tank will be purged of residual vapors using dry ice or other appropriate methods.
4. Combustible gases and oxygen level in the tank will be tested using a combustible gas indicator and an oxygen meter, respectively.
5. The tank will be excavated and removed with the upper soil being segregated from the lower materials, where feasible. Potentially impacted materials will be stockpiled atop plastic and covered with the same.
6. The tank system will be transported to a scrap dealer for disposal and a confirming bill of sale will be obtained.

New Jersey Department of  
Environmental Protection and Energy  
September 27, 1991  
Page Four

Please do not hesitate to contact us if you have any questions  
regarding the information contained herein.

Respectfully submitted,  
PMK, Ferris & Perricone, Inc.

  
James Johnston, P.E.  
Principal

  
Michael Mergardt  
Environmental Scientist

MM/brm/1077r8

**MORRIS**

**STREET**

**PARKING AREA**

**MORRISTOWN  
TIRE**

**WILMOT**

**STREET**

**PARKING  
AREA**

**VENT**

**APPROXIMATE LOCATION OF  
5,000 GALLON HEATING  
OIL TANK**

**PLOT PLAN**

**MORRISTOWN TIRE  
MORRISTOWN, NEW JERSEY**



**PMK** Ferris and  
Perricone, Inc.  
CONSULTING ENGINEERS

493 Lehigh Avenue, Union, NJ 07083  
908/686-0044

DRAWN BY	D.M.	DATE	10/15/91
CHECKED BY	M.M.	SCALE	1"=40'
PROJECT NO.	5182	SHEET NO.	



**ANTICIPATED IMPLEMENTATION SCHEDULE  
UNDERGROUND STORAGE TANK REMOVAL  
MORRISTOWN TIRE  
MORRISTOWN, NEW JERSEY  
PMK, F & P #5182**

Tank Cleaning: November 4, 1991

Tank Removal: November 5th-6th, 1991

Site Assessment (Soil Sampling): November 5th-6th, 1991

Site Assessment Summary Report: Week of February 6, 1992



May 8, 1992

**PRINCIPALS:**

Philip M. Keegan  
James Ferris, P.E.  
Gerald Perricone, P.E.  
James Johnston, P.E.

**MANAGING PARTNERS**

Terry C. Damon  
Robert M. Gerard

State of New Jersey  
Department of Environmental Protection  
and Energy  
Division of Responsible Party Site Remediation  
Bureau of Underground Storage Tanks  
CN 029  
Trenton, New Jersey 08625-0029

Attention: Ms. Diane Pupa

**CLOSURE PLAN IMPLEMENTATION SUMMARY**  
**89 MORRIS STREET**  
**MORRISTOWN, NEW JERSEY**  
**APPROVAL #C-91-4319**  
**PMK, F & P #5182**

91-2-14-1003-15

**INTRODUCTION**

92

This report presents the results of the Closure Plan Site Assessment performed during the removal of an underground storage tank system located at 89 Morris Street, Morristown, New Jersey. The tank removed for this closure was a 7,000 gallon capacity number 6 heating oil underground storage tank (UST). The subject UST had been initially registered with the New Jersey Department of Environmental Protection and Energy (NJDEPE) Bureau of Underground Storage Tanks (BUST) as a 5,000 gallon UST and was assigned registration number UST 0228873. The location of the site is presented on the Site Location Map, Plate 1. A cross-sectional view of the subject site is presented on Plate 2.

**CLOSURE PLAN APPROVAL**

On September 27, 1992, an Underground Storage Tank Closure Plan application was submitted to the Bureau of Underground Storage Tanks. On December 20, 1991 the Bureau assigned Closure Plan Approval number C-91-4319 to the project. In accordance with the requirements of N.J.A.C. 7:14B-9, the Construction Code Official for the Town of Morristown was contacted prior to initiation of the UST removal operations. A copy of the demolition permit issued by the Town of Morristown for the tank removal is provided as Plate 3.

**TANK DECOMMISSIONING OPERATIONS**

On February 10, 1992, representatives of ANCO Environmental Construction, Inc. were present at the subject site to commence tank decommissioning operations. The first phase of the tank

VIP CLEANERS  
(FORMER MORRISTOWN TFE)

92-02-14-1003  
CJ  
JA

State of New Jersey  
May 8, 1992  
Page 2

removal operations consisted of the removal of an approximately 12 inch thick reinforced concrete and asphalt layer from atop the tank location. An overburden soil layer of approximately 9 inches was then removed to expose the tank surface.

The tank was purged of residual vapors, drained of product and sludges, and then cleaned of the residual bottom sludges and liquids. Associated product bearing piping was also drained of residual product to prevent a potential discharge during the removal of same. The product removed from the tank, as well as the sludges and liquids generated during the tank cleaning operations, were transported to the L and L Oil Service facility in Aberdeen, New Jersey for treatment and/or disposal. Copies of the Uniform Hazardous Waste Manifests for the removal of the above liquids are presented as Plates 4A through 4F.

Subsequent to the tank cleaning operations, the tank and associated piping were excavated and removed. Upon removal, the tank was visually inspected by our on-site representative, the Town of Morristown Construction Code Official, and a representative of the Town of Morristown Engineering Office for indications of potential corrosion, pitting and/or holes. None of the referenced personnel reportedly observed any evidence of holes or significant signs of corrosion on the exterior tank surface. The associated product bearing piping was observed by our representative to contain corrosion in limited areas. The tank and piping were subsequently removed from the site and transported to Riverside Scrap Iron and Metal in Rahway, New Jersey where the tank and piping were sold as scrap metal. The Certification of Weight for the scrapped tank is presented as Plate 5.

#### SITE ASSESSMENT

During the course of the tank decommissioning operations, a representative of PMK, Ferris and Perricone, Inc. was present at the site to observe the existing site conditions and to implement the requirements of the Site Assessment. Our representative examined the excavation and adjacent site conditions to evaluate the potential presence of stained soils, free product and/or odors indicative of a product spill or discharge. Upon removal of the concrete/asphalt layer, the overburden soil and the subject UST, our representative visually observed product stained soil in the vicinity of the product bearing piping. Headspace analysis was performed on composite soil samples collected from the vicinity of the stained soils, using an organic vapor analyzer (OVA) to determine the potential presence of volatile organic compounds within the same. The results of the headspace analysis revealed volatile organic concentrations of 50 to 70 parts per million above background concentrations.

State of New Jersey  
May 8, 1992  
Page 3

Based on the visual observations of our representative and the results of the field screening operations, corrective action measures were implemented at the site. These activities consisted of the excavation and stockpiling of potentially impacted soil from the bottom of the excavation. The corrective action measures extended the excavation to a depth of approximately 11 feet below the surface grade, approximately 2 1/2 feet beyond the former UST invert level. Very slight groundwater infiltration was observed within the clayey silt layer encountered at the bottom of the excavation. In addition, a slight petroleum sheen was observed atop water that collected within the excavation. Potentially impacted water was removed from the excavation and transported to L and L Oil Service in Aberdeen, New Jersey for disposal. A copy of the Hazardous Waste Manifest for the disposal of these liquids has been included within Plate 4. As a result of the above, the NJDEPE Hotline was notified and BUST Case #91-214-1003-15 was assigned.

Petroleum contaminated soil removed from the excavation was stockpiled at the site atop and covered by plastic sheeting, and subsequently loaded into tandem trucks that were then transported to Pittsburgh, Pennsylvania for off-loading onto barges. The barges were transported to the Vernor Material and Equipment Company facility in Clute, Texas, where the soil was recycled into a usable asphalt road base. The facility permit as well as the letter indicating the acceptance of the material for reuse activities are presented on Plates 6A and 6B.

Subsequent to the implementation of corrective action measures, eight soil samples were obtained from the excavation in accordance with the protocol and sampling parameters established in the Closure Plan. The soil samples were obtained from the side walls of the excavation and from the soil remaining at the bottom of the excavation subsequent to the tank removal. In addition, composite soil samples had been previously collected from the visibly stained overburden soil which had originally been used as bedding and backfill material at the time of the UST installation. The locations of the soil samples relative to existing site features are presented on the Soil Sample Location Plan, Plate 7. Subsequent to the collection of soil samples, the excavation was backfilled with an imported fill material obtained from the Millington Quarry of Millington, New Jersey.

The soil samples were collected utilizing a stainless steel hand trowel, which was decontaminated prior to and between sampling events. The soil samples were placed in laboratory prepared sample jars capped with lined lids, and transported to Envirotech Research, Inc. in Edison, New Jersey (NJDEPE Certified Lab Number 12543) for laboratory chemical analysis. The laboratory analysis program consisted of the determination of total petroleum

hydrocarbon (TPH) concentrations utilizing USEPA Method 418.1. The samples were analyzed for potential TPH concentrations on March 3, 1992. Based on the results of the TPH analysis, an additional quantity of soil was excavated at and in the vicinity of the location from which Sample 1 was retrieved. Subsequent to the additional excavation, Sample 1A was collected at a depth of approximately one foot beyond the depth from which Sample 1 had been collected. Sample 1A was analyzed on March 10, 1992 for potential concentrations of base neutral extractable compounds utilizing USEPA Method 8270, and for TPH.

#### LABORATORY ANALYSIS RESULTS

The results of the laboratory chemical analyses performed on the soil samples obtained as a part of this study indicate that the TPH concentrations in Sample Nos. 2 through 7 were observed to either be not detected above analytical instrument detection levels or below the existing Interim NJDEPE Action Level of 100 parts per million for TPH concentrations in soil. Sample Nos. 1 and 1A were observed to contain respective TPH concentrations of 875 ppm and 210 ppm.

Based on the results of TPH analysis for Samples 1 and 1A, and in accordance with the sampling requirements of the approved Closure plan, analysis for base neutral extractable compounds (BN) was performed on Sample No. 1A. The results of this analysis indicated that targeted base neutral compounds were not present at concentrations in excess of analytical instrument detection levels.

The Results of the Laboratory Chemical Analyses, the Chain of Custody documents and the Quality Assurance/Quality Control (QA/QC) Checklist are presented as Appendix A. A Summary of the laboratory analysis results is presented as Table 1.

The completed certifications as required by N.J.A.C. 7:14B-9.5a, the Underground Storage Tank Site Summary Report Form and the Standard Reporting Form are presented as Appendix B.

#### RESULTS OF SITE ASSESSMENT

Based on the information obtained during the course of the tank closure, as well as a review of the laboratory analysis results, we have determined the following:

1. A 7,000 gallon #6 heating oil tank was opened, cleaned, purged, excavated, removed and disposed of in accordance with the requirements of the Approved Closure Plan. The subject tank was not observed to contain significant corrosion, holes or pitting. The associated piping was observed to contain limited areas of corrosion, although no holes nor pitting was



observed.

2. Subsequent to the removal of the subject tank and piping, petroleum impacted soils were visually observed within the excavation in the vicinity of the piping, and were consequently addressed, excavated and removed. Additionally, a sheen was observed atop standing rainwater/groundwater located within the excavation. The potentially impacted water was then pumped, containerized and removed. As a result of the above, a discharge was reported to the NJDEPE Hotline, where the incident was assigned BUST Case Number 92-214-1003-15.
3. Remedial measures implemented at the site entailed the excavation and removal of impacted soil to a varying depth of up to approximately two and one-half feet below the former UST invert level. The impacted soil was segregated, stockpiled atop and covered with plastic sheeting at the site, and subsequently removed and transported to an out of state reuse/recycling facility.
4. In accordance with the Approved Closure Plan, seven soil samples were obtained from the bottom of the excavation and subjected to analysis for total petroleum hydrocarbon concentrations. The results of the analyses indicated that Sample No. 1 contained a TPH concentration of 875 parts per million, whereas Sample Nos. 2 through 7 did not contain TPH concentrations in excess of the NJDEPE Action Levels for #6 heating oil concentrations in soil. Analysis of Sample No. 1A indicated a TPH concentration of 210 ppm. Base neutral extractable compounds analysis of Sample No. 1A revealed that targeted compounds were not detected above analytical instrument detection levels.

#### CONCLUSIONS/RECOMMENDATIONS

Based on a review of the site assessment results presented above, we recommend the following:

1. Based on the results of the soil sampling and subsequent laboratory chemical analysis performed for this study, it appears soil impacted by the presence of total petroleum hydrocarbons in excess of existing Action Levels have been removed from the former tank location with the exception of the soil in the vicinity of Sample No.1. At this location the TPH concentration was observed to decrease with increasing depth below the existing ground surface grade. In addition, the associated base neutral analysis for the sample obtained from this location did not yield detectable concentrations of carcinogenic polyaromatic hydrocarbons. Consequently, the

State of New Jersey  
May 8, 1992  
Page 6

observed total petroleum hydrocarbon concentrations do not appear to pose a potential risk to groundwater at the subject site.

2. As the subject tank and piping did not visually appear to contain any holes and/or significant corrosion, the observed discharge is likely the result of historic overfills and/or spills during the course of the operation.
3. The subject UST has been closed in accordance with N.J.A.C. 7:14B-9.2 and consequently should be removed from the NJDEPE Registered Underground Storage Tank Listing.

The following plates, tables and appendices are attached and complete this report:

Plate 1 - Site Location Map  
Plate 2 - Cross-sectional View of Site  
Plate 3 - Town of Morristown Permit  
Plates 4A through 4F - Hazardous Waste Manifests  
Plate 5 - Certification of Weight  
Plates 6A through 6C - Certification of Soil Recycle and  
Recycling Facility Permit and  
Plate 7 - Soil Sample Location Plan

Table 1 - Summary of Laboratory Analysis Results

Appendix A - Laboratory Analytical Results  
Appendix B - Certifications, UST Site Summary Report Form and  
Standard Reporting Form

Please do not hesitate to contact our office if you have any questions regarding the information contained herein.


Respectfully submitted,  
PMK, Ferris & Perricone, Inc.

  
James Johnston, P.E.  
Principal

  
Walter A. Kokola  
Project Manager

JJ/WK/gm/1571r8

cc: Peter Austin



RED-BROWN CLAYEY SILT


**CROSS-SECTIONAL  
VIEW OF UST**

VIEW FACING NORTH

89 MORRIS STREET  
MORRISTOWN, NEW JERSEY

**PMK** Ferris and  
Perricone, Inc.  
CONSULTING ENGINEERS  
493 Lehigh Avenue, Union, NJ 07083  
(908) 686-0044

DRAWN BY D.M.	DATE 5/4/92
CHECKED BY W.K.	SCALE N.T.S.
PROJECT NO. 5182	SHEET NO.



APPROXIMATE  
LIMITS OF  
EXCAVATION

WILMOT  
STREET

EXISTING  
STRUCTURE

LEGEND:



NUMBER AND APPROXIMATE LOCATION OF SOIL SAMPLE

SOIL SAMPLE  
LOCATION PLAN

89 MORRIS STREET  
MORRISTOWN, NEW JERSEY



**PMK** Ferris and  
Perricone, Inc.  
CONSULTING ENGINEERS

493 Lehigh Avenue, Union, NJ 07083  
(908) 686-0044

DRAWN BY	D.M.	DATE	5/4/92
CHECKED BY	W.K.	SCALE	N.T.S.
PROJECT NO.	5182	SHEET NO.	



November 23, 1992

**PRINCIPALS:**

Philip M. Keegan  
James Ferris, P.E.  
Gerald Perricone, P.E.  
James Johnston, P.E.

**MANAGING PARTNERS**

Terry C. Damon  
Robert M. Gerard

State of New Jersey  
Department of Environmental Protection  
and Energy  
Division of Responsible Party Site Remediation  
CN 028  
Trenton, New Jersey 08625-0028

Attention: Mr. David S. Rubin

**REMEDIAL INVESTIGATION ADDENDUM REPORT  
UNDERGROUND STORAGE TANK REMOVAL  
VIP CLEANERS/FORMER MORRISTOWN TIRE FACILITY  
89 MORRIS STREET  
MORRISTOWN, NEW JERSEY  
UST #0228873  
TMS #C91-4319  
CASE #92-02-14-1003  
PMK GROUP #5182**

**INTRODUCTION**

This report presents the results of the supplemental Remedial Investigation activities performed subsequent to the closure and removal of an underground storage tank (UST) system located at 89 Morris Street, Morristown, Morris County, New Jersey. The location of the site is presented on the Site Location Map, Plate 1.

**SUMMARY OF PREVIOUS STUDY**

The subject 7,000 gallon underground storage tank, which had historically contained #6 heating oil, was excavated and removed from the subject site on February 13, 1992 by Anco Environmental Contracting, Inc., under the direct observation of representatives of the PMK Group (PMK). Subsequent to removal, seven post-excavation soil samples were collected by PMK. Laboratory chemical analysis performed on these samples indicated that Total Petroleum Hydrocarbons (TPH) were detected in one of the samples at a concentration of 875 parts per million (ppm). A subsequent soil sample was collected from this location at a depth of approximately one foot below the previous sample depth, or 10 1/2 feet below the surface grade. Laboratory analysis of this sample revealed TPH at a concentration of 210 parts per million, and no targeted base neutral extractable compounds (BN) were detected at concentrations in excess

State of New Jersey  
November 23, 1992  
Page 2

gof laboratory analytical instrument detection limits. The remaining soil samples obtained for this study revealed TPH concentrations that were observed to either be not detected above analytical instrument detection levels, or to be below the existing Interim NJDEPE Action Level for #6 heating oil of 100 ppm for TPH concentrations in soil.

Based on visual observations of petroleum impacted soils within the excavation during UST closure/removal operations and the subsequent laboratory test results, remedial measures were implemented at the site. The activities entailed the excavation and removal of approximately 130 tons of potentially impacted soil. The excavation operations extended to a varying depth of approximately two and one-half feet below the former UST invert level, or approximately 11 feet below the surface grade. The impacted soil was subsequently transported to an out of state recycling facility. Imported fill material was subsequently utilized to achieve the desired grade.

#### **PURPOSE AND SCOPE OF WORK**

Based on the review of the findings contained in the document titled, "Closure Plan Implementation Summary, 89 Morris Street, Morristown, New Jersey" dated May 8, 1992 prepared by the PMK Group, representatives of the New Jersey Department of Environmental Protection and Energy (NJDEPE) issued correspondence dated July 22, 1992, requiring that the following additional remedial activities be performed at the site:

1. Install a groundwater monitoring well in the vicinity of the removed UST, collect representative groundwater samples from the installed well, and submit the samples for laboratory analysis.
2. Conduct a groundwater supply well search within the vicinity of the removed UST to determine the proximity of the same to the potential receptors that may be affected by the potential introduction of contaminants discharged to the groundwater.

The following report sections detail the remedial investigation activities performed by the PMK Group on behalf of Peter Austin, in accordance with the directives of the Department as set forth in the document dated July 22, 1992.



State of New Jersey  
November 23, 1992  
Page 3

## **REMEDIAL INVESTIGATION**

### **Monitoring Well Installation**

On September 8, 1992, representatives of Summit Drilling Company of Bridgewater, New Jersey (New Jersey well driller license M1212) installed a 2" diameter PVC groundwater monitoring well at the subject site in accordance with the NJDEPE specifications for monitoring well installations in unconsolidated geologic formations. The well was installed to a depth of approximately 22 feet below the existing surface grade in the vicinity of the former UST location. The well was screened across the estimated groundwater level using 0.020" slot PVC screen material, and completed at the ground surface with a flushmount well cover. Subsequent to the installation operations, the well was developed utilizing a centrifugal pump until a clear, sediment-free discharge of groundwater was observed. The development water was collected and containerized.

The groundwater monitoring well installation operations were performed under the direct technical supervision of a representative from PMK Group. Our representative located the well in the field, maintained a continuous log as the exploration was advanced, and supervised the soil sampling procedures in order to develop the required subsurface information. Representative soil samples suitable for identification purposes were collected at closely spaced intervals in accordance with the procedures of the Standard Penetration Test.

Details regarding the subsurface conditions encountered during the well installation operations are presented on the Log of Boring, Plate 2A. The soils have been visually classified in accordance with the Unified Soil Classification System, presented on Plate 2B. Details regarding the construction of the well are presented on the Well Construction Log, Plate 2C. A copy of the NJDEPE Monitoring Well Record as completed by the driller is presented on Plate 2D. The Monitoring Well Construction Certification (Form A) is presented as Plate 2E.

The location of the monitoring well was subsequently certified by a New Jersey licensed land surveyor (N.J.L.S. License No. 26791). The groundwater Monitoring Well Location Certification (Form B) and the copies of the Monitoring Well Location Plot Plan are presented as Plates 3A and 3B.

### **Groundwater Sampling**

On September 24, 1992, over two weeks subsequent to the time of the well installation and development, a representative of the PMK Group was present at the site to obtain groundwater samples from the subject well.

State of New Jersey  
November 23, 1992  
Page 4

Prior to sampling, our representative performed a measurement of the depth to groundwater within the well casing. No evidence of free product or product odors were detected within the well at that time. A centrifugal pump was then utilized to evacuate approximately three times the volume of water that had been measured to be standing within the well casing. The groundwater samples were then obtained utilizing a laboratory decontaminated teflon bailer in accordance with the groundwater sampling procedures and protocol as detailed in the NJDEPE Field Sampling Procedures Manual. Field and trip blanks were implemented to verify the integrity of the decontamination procedures, and to assess any potential contamination encountered during the transport of the sample containers and samples from and to the analytical laboratory. Standard Chain of Custody procedures were implemented to track the samples. The groundwater samples were placed in laboratory prepared glass sample jars, sealed with teflon-lined lids, placed in a chilled cooler, and transmitted to Envirotech Research Laboratories in Edison, New Jersey (NJDEPE Certified Lab Number 12543), where they were subsequently subjected to analysis for the potential presence of base neutral compounds plus the identification of 15 non-targeted compounds (EPA method 625+15) and volatile organic compounds plus the identification of 15 non-targeted compounds (EPA method 624+15).

#### Laboratory Analysis Results

The results of the laboratory chemical analyses performed on the groundwater samples collected on September 24, 1992 from the monitoring well at the subject site indicate that trichloroethene, tetrachloroethene and trans-1,2-dichloroethene were present in the groundwater sample at respective concentrations of 58 parts per billion (ppb), 510 ppb and 69 ppb. The concentrations of trichloroethene and tetrachloroethene were observed to be in excess of the proposed NJDEPE cleanup standards for Class II A groundwater. In addition, tentatively identified compounds were present in the collected groundwater sample. In the analysis for base neutral compounds, tetrachloroethene was identified to be present in a concentration of 99 ppb. Three additional, unidentified base neutral compounds were detected in concentrations ranging from 6 to 10 ppb.

No additional targeted or non-targeted volatile organic or base neutral compounds were observed to be present at concentrations above the laboratory analytical instrument detection limits. In addition, neither volatile organic compounds nor base neutral compounds were detected in the field or trip blank. A summary of the laboratory analysis results for the collected groundwater sample is presented on Table 1.

The results of the laboratory analysis and the chain of custody documents are presented in Appendix A.



State of New Jersey  
November 23, 1992  
Page 5

### NJDEPE Well Search

A search of NJDEPE permitted groundwater supply well records was performed to determine the potential presence of permitted residential wells within a one-half mile radius, and permitted industrial wells within a one mile radius of the subject site.

Based on the information provided in the well records obtained from the NJDEPE Bureau of Water Allocation, the following observations were noted:

1. Three permitted domestic groundwater supply wells are located within a radial distance of one-half mile from the subject site.
2. Seven permitted industrial and/or commercial groundwater supply wells are located within a radial distance of one mile from the subject site.
3. A Morristown Water Company municipal water supply well is located approximately one mile southeast of the subject site.

The well locations are presented on the Well Radius Map, Plate 4A. A listing of the wells, including their nature and location, is presented as the Summary of Groundwater Supply Wells, Plate 4B. The well registration forms as provided by the NJDEPE Bureau of Water Allocation are presented as Appendix B.

To supplement the well search, representatives of the Town of Morristown were contacted to determine the potential presence of known additional, non-permitted groundwater supply wells that may be located in the vicinity of the subject site. According to Kevin Cray of the Morristown Health Department, a well that is utilized for a backup water supply at Morristown Memorial Hospital is the only known groundwater supply well in the Town, according to Department records. Other facilities in Morristown supplied by the municipal water system.

The present property owner identified a potential groundwater supply well that was utilized in an historic commercial laundry that had been located at the subject site. According to Peter Austin, the site owner, the referenced well had not been utilized for over ten years. However, the well has not been formally closed and sealed. This well was not observed to be included in the listing of permitted wells as supplied by the NJDEPE. No other evidence indicative of the existence of groundwater supply wells in the vicinity of the subject site was observed by our representative.

State of New Jersey  
November 23, 1992  
Page 6

Additionally, a review of the United States Geological Survey 7.5 Minute Series Morristown Quadrangle Topography Map was performed to evaluate the potential presence of surface water bodies and water courses in the vicinity of the subject site. Based on this review, it appears that a portion of the Whippany River is located approximately one-quarter to one-half miles north of the subject site. This watercourse is fed by Lake Pocahontas, which is located between one-half and one mile north of the subject site. No other surface water bodies were observed to be located within an approximate radial distance of one-half mile from the subject site.

### **SUPPLEMENTAL REMEDIAL INVESTIGATION RESULTS**

Based on the information obtained during the groundwater monitoring well installation and sampling operations performed at the subject site and a review of the results of the laboratory analysis performed on the groundwater samples collected from the subject well, as well as the review of the provided NJDEPE well search records, we have determined the following:

1. A groundwater monitoring well was installed at the subject site on September 8, 1992 by a New Jersey licensed well driller. The subject well was installed in the vicinity of the historic UST that had been previously excavated and removed.
2. Representative groundwater samples obtained from the subject well on September 24, 1992 were analyzed by a NJDEPE certified laboratory. The results of the sample analyses for base neutral and volatile organic compounds indicated that trichloroethene, tetrachloroethene, and trans-1,2-dichloroethene were detected to be present in concentrations ranging from 58 to 510 parts per billion. The trichloroethene and tetrachloroethene concentrations were observed to be in excess of proposed groundwater cleanup standards.
3. A search of records of permitted groundwater supply wells that had been installed in the vicinity of the subject site, as provided by the NJDEPE Bureau of Water Allocation, indicated that three domestic groundwater supply wells are located within one-half mile and seven industrial/commercial groundwater supply wells are located within one mile of the subject site, and one municipal water supply well is located approximately one mile southeast of the subject site. Additionally, a groundwater supply well that was once utilized in an historic commercial laundry was observed at the subject site. One surface watercourse was observed to be located within one-half mile of the subject site.

State of New Jersey  
November 23, 1992  
Page 7

### **CONCLUSIONS/RECOMMENDATIONS**

Based on the findings listed above, we present the following conclusions:

1. Upon review of the nature and relative concentrations of the contaminants detected within the groundwater samples collected at the subject site, it does not appear that the discharges from the subject underground storage tank formerly located at the subject site has impacted the groundwater at the subject site. Consequently, the underground storage tank case should be closed.
2. Based on the nature and concentrations of the contaminants detected to be present within the groundwater sample collected from the monitoring well installed at the subject site, the contaminants are likely related to existing or historical dry cleaning operations at the site. In addition, there exists the potential that the same is the result of an off-site source.

The conclusions presented above indicate that the discharge from the subject UST has not impacted the groundwater at the subject site. Consequently, we recommend that no further remedial activity relative to the UST closure is necessary at the subject site.

Please do not hesitate to contact our office should you have any questions regarding the information presented in this report.

The following attachments are enclosed and complete this report:

- Plate 1 - Site Location Map
- Plate 2A - Log of Boring
- Plate 2B - Unified Soil Classification System
- Plate 2C - Well Construction Log
- Plate 2D - NJDEPE Monitoring Well Record
- Plate 2E - Monitoring Well Construction Certification
- Plate 3A - Groundwater Monitoring Well Location Certification
- Plate 3B - Monitoring Well Location Plot Plan
- Plate 4A - Well Radius Map
- Plate 4B - Summary of Groundwater Supply Wells

State of New Jersey  
November 23, 1992  
Page 8

Table 1 - Summary of Laboratory Analysis Results

Appendix A - Laboratory Analysis Results  
Appendix B - NJDEPE Well Registration Forms

Respectfully submitted,  
**PMK Group**



James Johnston, P.E.  
Vice President



Walter A. Kokola  
Project Geologist

JJ/WK/kh/2086r8

ATTACHMENT B

TABLE 1

## SUMMARY OF LABORATORY ANALYSIS RESULTS

Facility Name, Address: Former Morristown Tire Facility  
89 Morris Street  
Morristown, New Jersey 07960

Facility Owner, Address: P. Austin and W. Austin  
Post Office Box 29  
Morris Plains, New Jersey 07950

UST Registration Number: UST-0228873

UST Closure Approval: C-91-4319

BUST Discharge Case: 91-214-1003-15

Laboratory and Field Sample IDs:	63783 S1	63784 S2	63785 S3	63786 S4	63787 S5	63788 S6	63789 S7	63897 S1A
----------------------------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	--------------

Sample Locations:	South Wall	SE Wall	NE Wall	SW Wall	NW Wall	North Wall	Pit Bottom	South Wall
-------------------	------------	---------	---------	---------	---------	------------	------------	------------

Depth of sample: (below ground surface, in feet)	9.5	9.5	9.5	9.5	9.5	9.5	10.5	10.5
---	-----	-----	-----	-----	-----	-----	------	------

Matrix Analyzed:	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil
------------------	------	------	------	------	------	------	------	------

Parameters Analyzed:	TPH	TPH	TPH	TPH	TPH	TPH	TPH	TPH/ BN+15
----------------------	-----	-----	-----	-----	-----	-----	-----	---------------

Results (concentrations in PPM):	875	ND	ND	ND	74	ND	ND	210/ ND
----------------------------------	-----	----	----	----	----	----	----	------------

Test Methods Used: EPA Method 418.1 (Total Petroleum Hydrocarbons),  
EPA Method 8270 (Base Neutral Extractable Organics)

Dates that Samples Were Collected: February 20, 1992 (all except 1A)  
February 21, 1992 (Sample 1A)

Dates that Samples Were Transmitted to Laboratory: February 20, 1992 (all except 1A)  
February 21, 1992 (Sample 1A)

Name, Address of Laboratory which Performed the Sample Analyses: Envirotech Research, Inc.  
777 New Durham Road  
Edison, New Jersey 08817

NJDEPE Laboratory Certification Number: 12543

Date of Laboratory Report: March 3, 1992/March 10, 1992

Person Completing Laboratory Report: Michael J. Urban, Manager

TPH: Total Petroleum Hydrocarbons PPM: Parts per Million  
BN+15: Base Neutral Extractable Compounds

# ENVIROTECH RESEARCH, INC.

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 3/3/92  
Job No.: B066 - Peter Austin  
N.J. Certified Lab No. 12543  
QA Batch 2283

## PETROLEUM HYDROCARBONS

<u>Envirotech Sample #</u>	<u>Client ID</u>	<u>% Solid</u>	<u>Petroleum Hydrocarbons mg/kg (Dry Wt.)</u>
63783	S1	81.7	875
63784	S2	83.3	ND
63785	S3	82.4	ND
63786	S4	84.9	ND
63787	S5	82.2	74
63788	S6	83.3	ND
63789	S7	84.1	ND
63790	Soil Pile	91.1	36700

Detection Limit for Petroleum Hydrocarbons is 25 mg/kg.

# ENVIROTECH RESEARCH, INC.

777 New Durham Road  
Edison, New Jersey 08817  
Tel: (908) 549-3900  
Fax: (908) 549-3679

March 3, 1992

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083

Attention: Mr. Walter Kokola

Re: Job No. B066 - Peter Austin


Dear Mr. Kokola:

Enclosed are the results you requested for the following  
samples taken 12/20/92:

<u>Lab No.</u>	<u>Client ID</u>	<u>Analysis Requested</u>
63783	S1, 9 1/2	PHC
63784	S2, 9 1/2	PHC
63785	S3, 9 1/2	PHC
63786	S4, 9 1/2	PHC
63787	S5, 9 1/2	PHC
63788	S6, 9 1/2	PHC
63789	S7, 10 1/2	PHC
63790	Soil Pile	PHC

An invoice for our services is also enclosed. Please call  
me at 549-3900 if you have any questions.

Very truly yours,



Michael J. Urban  
Laboratory Manager



## ENVIROTECH RESEARCH, INC.

---

777 New Durham Road  
Edison, New Jersey 08817  
Tel: (908) 549-3900  
Fax: (908) 549-3679

March 10, 1992

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083

Attention: Mr. Walter Kokola

Re: Job No. B084<sup>®</sup> - Peter Austin


Dear Mr. Kokola:

Enclosed are the results you requested for the following sample taken 2/21/92:

<u>Lab No.</u>	<u>Client ID</u>	<u>Analysis Requested</u>
63897	S1A	BN +15 & PHC

An invoice for our services is also enclosed. Please call me at 549-3900 if you have any questions.

Very truly yours,



Michael J. Urban  
Laboratory Manager

# ENVIROTECH RESEARCH, INC.

---

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 3/10/92  
Job No.: B084 - Peter Austin  
N.J. Certified Lab No. 12543  
QA Batch 2283

## PETROLEUM HYDROCARBONS

<u>Envirotech</u> <u>Sample #</u>	<u>Client ID</u>	<u>% Solid</u>	<u>Petroleum Hydrocarbons</u> <u>mg/kg (Dry Wt.)</u>
63897	S1A	80.9	210

Detection Limit for Petroleum Hydrocarbons is 25 mg/kg.

# ENVIROTECH RESEARCH, INC.

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 3/10/92  
Job No.: B084 - Peter Austin  
N.J. Certified Lab No. 12543  
QA Batch 1774

## BASE/NEUTRAL EXTRACTABLES

<u>Parameter</u>	<u>Units: ug/kg (Dry Weight)</u>	<u>Detection Limit</u> <u>Units: ug/kg</u>
1,3-Dichlorobenzene	ND	330
1,4-Dichlorobenzene	ND	330
Hexachloroethane	ND	330
Bis(2-chloroethyl) ether	ND	330
1,2-Dichlorobenzene	ND	330
Bis(2-chloroisopropyl) ether	ND	330
N-Nitrosodi-n-propylamine	ND	330
Nitrobenzene	ND	330
Hexachlorobutadiene	ND	330
1,2,4-Trichlorobenzene	ND	330
Isophorone	ND	330
Naphthalene	ND	330
Bis(2-chloroethoxy) methane	ND	330
Hexachlorocyclopentadiene	ND	330
2-Chloronaphthalene	ND	330
Acenaphthylene	ND	330
Acenaphthene	ND	330
Dimethyl phthalate	ND	330
2,6-Dinitrotoluene	ND	330
Fluorene	ND	330
4-Chlorophenyl phenyl ether	ND	330
2,4-Dinitrotoluene	ND	330
Diethylphthalate	ND	330
N-Nitrosodiphenylamine	ND	330
Hexachlorobenzene	ND	330


# ENVIROTECH RESEARCH, INC.

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 3/10/92  
Job No.: B084 - Peter Austin  
N.J. Certified Lab No. 12543  
QA Batch 1774

## BASE/NEUTRAL EXTRACTABLES (con't)

Parameter	Lab No. 63897 Client ID: S1A 80.9% Solid Units: ug/kg (Dry Weight)	Detection Limit Units: ug/kg
4-Bromophenyl phenyl ether	ND	330
Phenanthrene	ND	330
Anthracene	ND	330
Dibutyl phthalate	ND	330
Fluoranthene	ND	330
Pyrene	ND	330
Benzidine	ND	670
Butyl benzyl phthalate	ND	330
Bis(2-ethylhexyl) phthalate	ND	330
Chrysene	ND	330
Benzo(a)anthracene	ND	330
3,3'-Dichlorobenzidine	ND	670
Di-n-octyl phthalate	ND	330
Benzo(b)fluoranthene	ND	330
Benzo(k)fluoranthene	ND	330
Benzo(a)pyrene	ND	330
Indeno(1,2,3-c,d)pyrene	ND	330
Dibenzo(a,h)anthracene	ND	330
Benzo(ghi)perylene	ND	330
N-Nitrosodimethylamine	ND	330



**W.A.T.E.R. WORKS  
LABORATORY INC.**

364 Glenwood Ave., East Orange, NJ 07017  
(201) 678-3787 FAX (201) 678-6779

**LABORATORY ANALYSIS REPORT**

DATE : FEBRUARY 17, 1992  
CLIENT: ANCO ENVIRONMENTAL

SAMPLE COLLECTED: 2/13/92  
SAMPLE RECEIVED: 2/13/92  
GENERATOR : PETE AUSTIN  
88 MORRIS AVE  
MORRISTOWN, NJ

CLIENT ID # : PETE AUSTIN  
SAMPLE NUMBER 25116  
EXTRACTION METHOD #  
ANALYSIS METHOD #

TCLP METALS	MDL			
ARSENIC	0.01	ND		7060
BARIUM	0.01	0.32		7081
CADMIUM	0.01	ND		7130
CHROMIUM	0.03	0.12		7190
LEAD	0.03	ND		7421
MERCURY	0.001	ND		7471
SELENIUM	0.01	ND		7740
SILVER	0.01	ND		7760
pH, Corrosivity		7.47		9045
TPH	200	9350		418.1*
% SOLIDS		88.3		
FLASHPOINT		> 140 F		1010
REACTIVE CYANIDE	1.0	ND		SW826
REACTIVE SULFIDE	1.6	ND		SW826
PCB-1016	0.02	ND	3550	8080
PCB-1221	0.02	ND	3550	8080
PCB-1232	0.02	ND	3550	8080
PCB-1242	0.02	ND	3550	8080
PCB-1248	0.02	ND	3550	8080
PCB-1254	0.02	ND	3550	8080
PCB-1260	0.02	ND	3550	8080
BENZENE	0.03	ND	5030	8240
ETHYLBENZENE	0.03	0.12	5030	8240
TOLUENE	0.03	0.04	5030	8240
XYLENES	0.03	0.32	5030	8240

  
STEPHEN KROEMER  
LABORATORY MANAGER

All Results Reported As ppm  
MDL = Method Detection Limit  
ND = Not Detected Above MDL  
\* = EPA-600/4-79-020 March 1979  
\*\* MARCH 1990 40 CFR 261 Pg 11865

NJDEP LABORATORY ID # 07673

W.W.L.'S TOTAL LIABILITY FOR ANY WORK PERFORMED IS LIMITED TO THE COST OF SERVICES RENDERED.

ATTACHMENT B8

# ENVIROTECH RESEARCH, INC.

---

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 3/3/92  
Job No.: B066 - Peter Austin  
N.J. Certified Lab No. 12543  
QA Batch 2281

## PETROLEUM HYDROCARBONS

<u>Envirotech Sample #</u>	<u>Client ID</u>	<u>% Solid</u>	<u>Petroleum Hydrocarbons mg/kg (Dry Wt.)</u>
63790	Soil Pile (reanalysis)	91.1	36900

Detection Limit for Petroleum Hydrocarbons is 25 mg/kg.

# ENVIROTECH RESEARCH, INC.

PMK Ferris & Perricone, Inc.  
493 Lehigh Avenue  
Union, NJ 07083  
Attention: Mr. Walter Kokola

Report Date: 10/19/92  
Job No.: C518  
N.J. Certified Lab No. 12543  
QA Batch 2745A

## VOLATILE ORGANICS

<u>Parameter</u>	Lab No. 73838	Quantitation Limit
	Client ID: MW 1	
	<u>Units: ug/l</u>	<u>Units: ug/l</u>
Benzene	ND	50
Bromodichloromethane	ND	50
Bromoform	ND	50
Bromomethane	ND	100
Carbon tetrachloride	ND	50
Chlorobenzene	ND	50
Chloroethane	ND	100
2-Chloroethylvinyl ether	ND	100
Chloroform	ND	50
Chloromethane	ND	100
Dibromochloromethane	ND	50
1,1-Dichloroethane	ND	50
1,2-Dichloroethane	ND	50
1,1-Dichloroethene	ND	50
trans-1,2-Dichloroethene	69	50
1,2-Dichloropropane	ND	50
cis-1,3-Dichloropropene	ND	50
trans-1,3-Dichloropropene	ND	50
Ethyl benzene	ND	50
Methylene chloride	ND	50
1,1,2,2-Tetrachloroethane	ND	50
Tetrachloroethene	510	50
Toluene	ND	50
1,1,1-Trichloroethane	ND	50
1,1,2-Trichloroethane	ND	50
Trichloroethene	58	50
Trichlorofluoromethane	ND	50
Vinyl chloride	ND	100
Xylenes (Total)	ND	50

**TABLE 1**

**SUMMARY OF LABORATORY ANALYSIS RESULTS  
 89 MORRIS STREET  
 MORRISTOWN, NEW JERSEY  
PMK GROUP #5182**

<u>Sample Location</u>	<u>Sample Date</u>	<u>Medium Sampled</u>	<u>Detected Parameters</u>	<u>Detected Concentration (ppb)</u>
Groundwater monitoring well #MW-1	9/24/92	Groundwater	Volatile Organic	
			<u>Compounds:</u>	
			Trichloroethene	58
			Tetrachloroethene	510
			Trans-1,2-dichloroethene	69
			Base neutral analysis:	
			Tentatively Identified	
			<u>Compounds</u>	
			Tetrachloroethene	94
			Unknown base neutral compound	10
			Unknown base neutral compound	8
			Unknown base neutral compound	6



ATTACHMENT C



⊕ SUBJECT SITE LOCATION

WELL LOCATIONS ARE APPROXIMATE

0

1/2 ml.

1 ml.

## WELL RADIUS MAP

89 MORRIS STREET  
MORRISTOWN, NEW JERSEY



**PMK Group**

CONSULTING ENGINEERS

493 Lehigh Avenue, Union, NJ 07083  
908-686-0044

DRAWN BY	W.K.	DATE	11/23/92
CHECKED BY	W.K.	SCALE	AS SHOWN
PROJECT NO.	5182	SHEET NO.	

**SUMMARY OF GROUNDWATER SUPPLY WELLS  
89 MORRIS STREET  
MORRISTOWN, NEW JERSEY  
PMK GROUP # 5182**

WELL NO.	OWNER, LOCATION	N. J. ATLAS COORDINATES	PERMIT NO.	WELL UTILIZATION	WELL DEPTH	PUMPING DEPTH	YEAR INSTALLED
1	MAC COLLOUGH HALL 45 MAC COLLOUGH AVENUE	25-13-397	25-13043	DOMESTIC	150	74	1965
2	GEORGE GALLINI BLOCK 1059, LOT 30.2	25-13-697	25-25876	DOMESTIC	320	250	1985
3	POWERS MOTOR COMPANY 44 RIDGEDALE AVENUE	25-13-635	25-32177	IRRIGATION	298	80	1988
4	MAC COLLOUGH HALL 45 MAC COLLOUGH AVENUE	25-13-629	25-13043	DOMESTIC	155	74	1965
5	BENEFICIAL MANAGEMENT 200 SOUTH STREET	25-13-617	25-15508	COOLING	500	273	1971
6	TOWN OF MORRISTOWN WELL NO. 5-LIDGERWOOD	25-13-664	25-14520	MUNICIPALITY	265	150	1967
7	BENEFICIAL PROPERTIES 15 WASHINGTON STREET	25-13-663	25-3936	COOLING	500	150	1955
8	MORRISTOWN WATER CO. JOHNSON DRIVE AT TURTLE ROAD	25-14-142	25-13439	MUNICIPAL	496	191	1966
9	TECH ART PLASTICS CO. 111 RIDGEDALE ROAD	25-14-177	25-8717	INDUSTRIAL	163	150	1961
10	B. W. B. CORPORATION 16 RIDGEDALE AVENUE	25-14-177	25-15756	CAR WASH	350	275	1972
11	T. LANDI AND SON RIDGEDALE AVENUE	25-14-178	25-3701	WASHING GRAVEL	48	48	1955

**NOTES:**

ALL LOCATIONS ARE IN MORRISTOWN/MORRIS TOWNSHIP, NEW JERSEY  
INDICATED WELL UTILIZATION IS AT THE TIME OF INSTALLATION  
INDICATED DEPTHS ARE IN FEET BELOW THE SURFACE GRADE ELEVATION

**PLATE 4B**

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, ATTACHMENT 5

STATE OF NEW JERSEY  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES

Coord: 2513637

PERMIT NO. 2525876

APPLICATION NO. \_\_\_\_\_

COUNTY Morris

WELL RECORD

1. OWNER GALLINI, GEORGE ADDRESS 510 MILLBURN AVE.  
Owner's Well No. \_\_\_\_\_ SURFACE ELEVATION \_\_\_\_\_ Feet  
(Above mean sea level)
2. LOCATION Lot: 30.2 Block: 1059 Municipality: Morris Twp.
3. DATE COMPLETED March 15, 1985 DRILLER Somerville Well Drilling Co.
4. DIAMETER: Top 10 inches Bottom 6" inches TOTAL DEPTH 320' Feet
5. CASING: Type Drive Diameter 6" Inches Length 190' Feet
6. SCREEN: Type \_\_\_\_\_ Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
- Range in Depth { Top \_\_\_\_\_ Feet  
Bottom \_\_\_\_\_ Feet
- Geologic Formation \_\_\_\_\_
- Tail Piece: Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface
8. RECORD OF TEST: Date March 15, 1985 Yield 20 Gallons per minute  
Static water level before pumping 65' Feet below surface  
Pumping level 250' feet below surface after 8 hours pumping  
Drawdown 185' Feet Specific Capacity 2 Gals. per min. per ft. of drawdown  
How pumped Air How measured Weir  
Observed effect on nearby wells none
9. PERMANENT PUMPING EQUIPMENT:  
Type \_\_\_\_\_ Mfrs. Name \_\_\_\_\_  
Capacity \_\_\_\_\_ G.P.M. How Driven \_\_\_\_\_ H.P. \_\_\_\_\_ R.P.M. \_\_\_\_\_  
Depth of Pump in well \_\_\_\_\_ Feet Depth of Footpiece in well \_\_\_\_\_ Feet  
Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ Inches
10. USED FOR Domestic AMOUNT { Average \_\_\_\_\_ Gallons Daily  
Maximum \_\_\_\_\_ Gallons Daily
11. QUALITY OF WATER good Sample: Yes \_\_\_\_\_ No X  
Taste none Odor none Color clear Temp. \_\_\_\_\_ °F.
12. LOG 0-190 overburden 190-320 Are samples available? No  
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy.)
13. SOURCE OF DATA Somerville Well Drilling Co., Inc.
14. DATA OBTAINED BY Same Date March 15, 1985

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated,  
analysis of the water, sketch map, sketch of special casing arrangements, etc.)

ATTACHMENT CA

WELL RECORD

Well Permit No. 25 - 32177  
Atlas Sheet Coordinates 25 : 13 : 635

OWNER IDENTIFICATION - Owner POWERS MOTOR COMPANY

Address 44 RIDGEDALE AVE

City MORRISTOWN

State NJ

Zip Code 07960

WELL LOCATION - If not the same owner please give address.

Owner's Well No. \_\_\_\_\_

Address 44 Ridgedale Ave.

County Morris

Municipality MORRISTOWN TOWN

Lot No. 11-17

Block No. 1901

WELL USE Withdrawal - For Water Supply

Status Standby

WATER USE Irrigation

Average \_\_\_\_\_ gals. daily

Maximum \_\_\_\_\_ gals. daily

WELL CONSTRUCTION

BOREHOLE DIMENSIONS

Date well completed 9 / 9 / 88

Depths: Total 298 ft.

Finished \_\_\_\_\_ ft.

Diameter: Top 40 in.

Bottom 6" in.

Land Surface Elevation at well 400 ft.

Casing Height (stick-up) above land surface 1 1/2 ft.

Elevation was determined using Topographic Map #25

	DEPTH TO TOP (FT.)	LENGTH (FT.)	DIAMETER (IN.)	TYPE AND MATERIAL Screens: Note Slot Size(s)
Casing 1		<u>190</u>	<u>6"</u>	<u>250 Wall Steel</u>
Casing 2				
Casing 3				
Screen 1				
Screen 2				
Tail Piece				
Gravel Pack				
Grout				
Grouting Method		<u>drill + drive</u>		

WELL FLOWS NATURALLY \_\_\_\_\_ gals. per min. at \_\_\_\_\_ ft. above the land surface.

Water rises to \_\_\_\_\_ ft. above the land surface.

RECORD OF TEST

Test Date 9 / 9 / 88

Static water-level before pumping 80' ft. below land surface.

Water level \_\_\_\_\_ ft. below land surface after \_\_\_\_\_ hrs. of pumping.

Water level was measured using Estimated

Drawdown \_\_\_\_\_ ft.

Discharge rate measured using Estimated

Discharge Rate 40+ gals. per min.

Well was pumped using a/c

Specific Capacity \_\_\_\_\_ gals. per min. per ft. of drawdown

Observed effects on nearby wells \_\_\_\_\_

Water Quality (taste, odor, color, etc.) \_\_\_\_\_

PERMANENT PUMPING EQUIPMENT

Installed by Not Installing

Pump Type \_\_\_\_\_

Mfrs. Name \_\_\_\_\_

Model \_\_\_\_\_

CAPACITY: Pump delivers \_\_\_\_\_ GPM at \_\_\_\_\_ PSI pressure.

POWER: \_\_\_\_\_ HP at \_\_\_\_\_ RPM Power Source \_\_\_\_\_

DEPTHS: Pump \_\_\_\_\_ ft. Footpiece \_\_\_\_\_ ft. Airline \_\_\_\_\_ ft.

FLOW METER: Model \_\_\_\_\_ installed on \_\_\_\_\_ in. diameter pipe.

CONTRACTOR - Name of Drilling Contractor

DAN BALLENTINE

Address P.O. Box 178, Port Murray Road

City Port Murray

State N.J.

Zip Code 07865-0178

Name of Driller Robert Hagan

License No. 1246

Signature of Contractor

Date 9 / 26 / 88

COPIES:

White - DEP

Canary - Driller

Pink - Owner

Goldenrod - Health Dept.

ATTACHMENT 05

DEPARTMENT OF CONSERVATION  
 AND ECONOMIC DEVELOPMENT  
 DIVISION OF WATER POLICY & SUPPLY

Permit No. 25-13-629

Application No. \_\_\_\_\_

County \_\_\_\_\_

## WELL RECORD

1. OWNER James Mac Collough Hall Museum ADDRESS 45 Mac Collough Ave, Morristown, N.J.  
 Owner's Well No. 2537 SURFACE ELEVATION \_\_\_\_\_ Feet  
 (Above mean sea level)
2. LOCATION Same as above
3. DATE COMPLETED 7/15/65 DRILLER D.F. Well Drilling Co., Netcong, N.J.
4. DIAMETER: top \_\_\_\_\_ Inches Bottom \_\_\_\_\_ Inches TOTAL DEPTH 155 Feet
5. CASING: Type Solid steel Diameter \_\_\_\_\_ Inches Length 150 Feet
6. SCREEN: Type \_\_\_\_\_ Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
- Range in Depth { Top \_\_\_\_\_ Feet  
 Bottom \_\_\_\_\_ Feet Geologic Formation \_\_\_\_\_
- Tail piece: Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per Minute at \_\_\_\_\_ Feet above surface  
 Water rises to \_\_\_\_\_ Feet above surface
8. RECORD OF TEST: Date 7/16/65 Yield 24+ Gallons per minute  
 Static water level before pumping 74 Feet below surface  
 Pumping level 74 feet below surface after 1 hours pumping  
 Drawdown 0 Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown  
 How Pumped \_\_\_\_\_ How measured \_\_\_\_\_  
 Observed effect on nearby wells \_\_\_\_\_
9. PERMANENT PUMPING EQUIPMENT:  
 Type \_\_\_\_\_ Mfrs. Name \_\_\_\_\_  
 Capacity \_\_\_\_\_ G.P.M. How Driven \_\_\_\_\_ H.P. \_\_\_\_\_ R.P.M. \_\_\_\_\_  
 Depth of Pump in well \_\_\_\_\_ Feet Depth of Footpiece in well \_\_\_\_\_ Feet  
 Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ Inches
10. USED FOR Domestic AMOUNT { Average \_\_\_\_\_ Gallons Daily  
 Maximum \_\_\_\_\_ Gallons Daily
11. QUALITY OF WATER \_\_\_\_\_ Sample: Yes \_\_\_\_\_ No \_\_\_\_\_  
 Taste \_\_\_\_\_ Odor \_\_\_\_\_ Color \_\_\_\_\_ Temp. \_\_\_\_\_ °F
12. LOG \_\_\_\_\_ Are samples available? \_\_\_\_\_  
 (Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA \_\_\_\_\_
14. DATA OBTAINED BY Donald J. McBride Date 7/31/65

ATTACHMENT C6

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated.)

25-13-617

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
DIVISION OF WATER POLICY & SUPPLY

Permit No. 25-15508  
File Application No. A25-77  
County \_\_\_\_\_

5

**WELL RECORD**

1. OWNER Beneficial Management ADDRESS 200 South St. Morristown, N. J.  
Owner's Well No. #2 SURFACE ELEVATION 360 Feet  
(Above mean sea level)
2. LOCATION So Street. Morristown, New Jersey
3. DATE COMPLETED May 1971 DRILLER Burrows Well Drilling Co., Inc.
4. DIAMETER: top 8 inches Bottom 8 inches TOTAL DEPTH 500' Feet
5. CASING: Type 209 Diameter 8 inches Length 209 Feet
6. SCREEN: Type None Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet  
Range in Depth { Top \_\_\_\_\_ Feet  
Bottom \_\_\_\_\_ Feet Geologic Formation \_\_\_\_\_
- Tail piece: Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY No Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface
8. RECORD OF TEST: Date 7-16-70 Yield 133 Gallons per minute  
Static water level before pumping 138 Feet below surface  
Pumping level 273 feet below surface after 24 hours pumping  
Drawdown 135 Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown  
How Pumped Turbine How measured Orifice  
Observed effect on nearby wells Drew Well #1 Down 6 Ft.
9. PERMANENT PUMPING EQUIPMENT:  
Type Submersible Mfrs. Name Jacuzzi  
Capacity 125 G.P.M. How Driven Electric Motor H.P. 20 R.P.M. 3600  
Depth of Pump in well 300 Feet Depth of Footpiece in well 300 Feet  
Depth of Air Line in well 300 Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ inches
10. USED FOR Cooling AMOUNT { Average \_\_\_\_\_ Gallons Daily  
Maximum \_\_\_\_\_ Gallons Daily
11. QUALITY OF WATER \_\_\_\_\_ Sample: Yes \_\_\_\_\_ No \_\_\_\_\_  
Taste \_\_\_\_\_ Odor \_\_\_\_\_ Color \_\_\_\_\_ Temp. \_\_\_\_\_ °F
12. LOG \_\_\_\_\_ Are samples available? NO  
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA Drillings
14. DATA OBTAINED BY Burrows Well Drilling Co., Inc. Date 9-8-71

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

ATTACHMENT C1



6

25-13-664

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
DIVISION OF WATER POLICY & SUPPLY

Permit No. \_\_\_\_\_  
Application No. 25-14-520  
County \_\_\_\_\_

## WELL RECORD

1. OWNER Town of Morristown ADDRESS Morristown, N. J.  
Owner's Well No. Well #5-Lidgerwood SURFACE ELEVATION \_\_\_\_\_ Feet  
(Above mean sea level)
2. LOCATION Lidgerwood-Township of Morristown
3. DATE COMPLETED 11-10-67 DRILLER Burrows Well Drilling Co., Inc.
4. DIAMETER: top 12 Inches Bottom 12 Inches TOTAL DEPTH 265 Feet
5. CASING: Type Steel Drive Diameter 12 Inches Length 67'10" Feet
6. SCREEN: Type \_\_\_\_\_ Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet  
Range { Top \_\_\_\_\_ Feet Geologic Formation \_\_\_\_\_  
Bottom \_\_\_\_\_ Feet
- Tail piece. Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY NO Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface  
11-7-67 to
8. RECORD OF TEST: Date 11-10-67 Yield 800 Gallons per minute  
Static water level before pumping 40 Feet below surface  
Pumping level 150 feet below surface after \_\_\_\_\_ hours pumping  
Drawdown 33½ Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown  
How Pumped Diesel Driven Turbine How measured Orifice  
Observed effect on nearby wells None
9. PERMANENT PUMPING EQUIPMENT: is  
Type \_\_\_\_\_ Mfrs. Name \_\_\_\_\_  
Capacity \_\_\_\_\_ G.P.M. How Driven \_\_\_\_\_ H.P. \_\_\_\_\_ R.P.M. \_\_\_\_\_  
Depth of Pump in well \_\_\_\_\_ Feet Depth of Footpiece in well \_\_\_\_\_ Feet  
Depth of Air Line in well \_\_\_\_\_ Feet Depth of Meter on Pump \_\_\_\_\_
10. USED FOR Municipality AMOUNT Average \_\_\_\_\_ Gallons Daily  
Maximum \_\_\_\_\_ Gallons Daily
11. QUALITY OF WATER \_\_\_\_\_ Sample: Yes \_\_\_\_\_ No \_\_\_\_\_  
Taste \_\_\_\_\_ Odor \_\_\_\_\_ Color Clear Temp. 53° of \_\_\_\_\_
12. LOG over Are samples available yes  
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA Drillings
14. DATA OBTAINED BY Burrows Well Drilling Co., Inc. Date Throughout job.

(NOTE: Use other side of this sheet for additional information such as log of materials used, analysis of the water, sketch map, sketch of special casing arrangements etc.)

ATTACHMENT C8

(7)

**DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
Division of Water Policy & Supply  
WELL RECORD**

25.13.6.63

Permit No. 25-3936

Application No. \_\_\_\_\_

County: \_\_\_\_\_

1. OWNER Beneficial Properties Inc ADDRESS 15 Washington St. Morristown, N.J.  
Owner's Well No. 1 SURFACE ELEVATION 360 Feet  
(Above mean sea level)
2. LOCATION South street, Morristown, N.J.
3. DATE COMPLETED \_\_\_\_\_ DRILLER Burrows Well Drilling Co.
4. DIAMETER: Top 8 Inches Bottom 8 Inches TOTAL DEPTH 500 Feet
5. CASING: Type steel Diameter 8 Inches Length 206 Feet
6. SCREEN: Type X Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet  
Range in Depth { Top \_\_\_\_\_ Feet Geologic Formation lime shale  
Bottom \_\_\_\_\_ Feet  
Tail piece. Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY X Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface 150 for #3 bit
8. RECORD OF TEST: Date NO. 1, 305 dup Yield 30 Gallons per minute  
Static water level before pumping 90 Feet below surface  
Pumping level 150 feet below surface after 8 hours pumping  
Drawdown 70 Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown  
How Pumped turbine How measured watch + Drum  
Observed effect on nearby wells none
9. PERMANENT PUMPING EQUIPMENT: turbine  
Type not installed as yet Capacity 150 Gallons per minute  
How Driven Proposed - electric Horse Power 2.5 R.P.M. 1800  
Depth of pump in well 231 Feet Depth of Foot piece in well 231 Feet  
Depth of Air Line in well 200 Feet Type of Meter on Pump altitude gauge
10. USED FOR air conditioning Average under 90,000 Gallons Daily  
AMOUNT { Maximum 95,000 Gallons Daily
11. QUALITY OF WATER \_\_\_\_\_ Sample: Yes \_\_\_\_\_ No. X  
Taste None Odor None Color None Temperature 54 °F
12. LOG over Are samples available? yes  
(Give details on back of sheet or on separate sheet)
13. SOURCE OF DATA drillings
14. DATA OBTAINED BY JOHN E BURROWS DATE June 55

(Note: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements, etc.)

ATTACHMENT C9

(8)

25-14-442

Permit No. 65-13,439

Application No. \_\_\_\_\_

County \_\_\_\_\_

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
DIVISION OF WATER POLICY & SUPPLY

**WELL RECORD**

1. OWNER Morristown Water Co. ADDRESS Morristown, New Jersey  
Owner's Well No. \_\_\_\_\_ SURFACE ELEVATION \_\_\_\_\_ Feet  
(Above mean sea level)
2. LOCATION Johnson Drive & Turtle Road, Morristown, Morris County
3. DATE COMPLETED Dec. 20, 1965 DRILLER Wm. Stothoff Co., Inc.
4. DIAMETER: top 12 inches Bottom 12 inches TOTAL DEPTH 496 Feet
5. CASING: Type Std Steel, PE, Welded Diameter 12 inches Length 124 Feet
6. SCREEN: Type None Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet
- Range in Depth { Top \_\_\_\_\_ Feet  
Bottom \_\_\_\_\_ Feet
- Geologic Formation \_\_\_\_\_
- Tail piece: Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet
7. WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface
8. RECORD OF TEST: Date Dec. 16-18, 1965 Yield 420 Gallons per minute  
Static water level before pumping 44 Feet below surface  
Pumping level 191 feet below surface after 48 hours pumping  
Drawdown 147 Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown  
How Pumped Turbine Pump - Gasoline Engine How measured Orifice  
Observed effect on nearby wells None observed
9. PERMANENT PUMPING EQUIPMENT:  
Type \_\_\_\_\_ Mfrs. Name \_\_\_\_\_  
Capacity \_\_\_\_\_ G.P.M. How Driven \_\_\_\_\_ H.P. \_\_\_\_\_ R.P.M. \_\_\_\_\_  
Depth of Pump in well \_\_\_\_\_ Feet Depth of Footpiece in well \_\_\_\_\_ Feet  
Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ inches
10. USED FOR Municipal Water Supply AMOUNT { Average \_\_\_\_\_ Gallons Daily  
Maximum \_\_\_\_\_ Gallons Daily
11. QUALITY OF WATER \_\_\_\_\_ Sample: Yes \_\_\_\_\_ No \_\_\_\_\_  
Taste \_\_\_\_\_ Odor \_\_\_\_\_ Color \_\_\_\_\_ Temp. \_\_\_\_\_ °F
12. LOG See other Side Are samples available? No  
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA Wm. Stothoff Co., Inc.
14. DATA OBTAINED BY Wm. Stothoff Co., Inc. Date 2-23-66

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

ATTACHMENT C10

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
DIVISION OF WATER POLICY & SUPPLY

Permit No. 25-8717  
Application No. \_\_\_\_\_  
County \_\_\_\_\_

## WELL RECORD

RECEIVED  
OCT 26 61  
OWNER CONS. & ECON. DEV.  
Div. of Water Policy & Supply  
Plastics Co.

ADDRESS 111 Ridgedale Rd, Morris Twp.

Owner's Well No. \_\_\_\_\_ SURFACE ELEVATION 320 Feet  
(Above mean sea level)

LOCATION Morris Twp.

DATE COMPLETED Sept. 5, 1961 DRILLER Dimunzi Well Drilling Co.

DIAMETER: top 8 Inches Bottom 8 Inches TOTAL DEPTH 163 Feet

CASING: Type Steel Diameter 8 Inches Length 143 Feet

SCREEN: Type Wire Wound Size of Opening 50 Diameter 6 5/8 Inches Length 20 Feet

Range in Depth { Top 143 Feet  
Bottom 163 Feet } Geologic Formation Gravel

Tail piece: Diameter \_\_\_\_\_ Inches Length \_\_\_\_\_ Feet

WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per Minute at \_\_\_\_\_ Feet above surface

Water rises to \_\_\_\_\_ Feet above surface

RECORD OF TEST: Date Sept. 5, 1961 Yield 70 Gallons per minute

Static water level before pumping 30 Feet below surface

Pumping level 150 feet below surface after 48 hours pumping

Drawdown 120 Feet Specific Capacity .58 Gals. per min. per ft. of drawdown

How Pumped Submersible test pump How measured wier

Observed effect on nearby wells none

PERMANENT PUMPING EQUIPMENT: Not installed by driller

Type \_\_\_\_\_ Mfrs. Name \_\_\_\_\_

Capacity \_\_\_\_\_ G.P.M. How Driven \_\_\_\_\_ H.P. \_\_\_\_\_ R.P.M. \_\_\_\_\_

Depth of Pump in well \_\_\_\_\_ Feet Depth of Footpiece in well \_\_\_\_\_ Feet

Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ Inches

USED FOR Factory AMOUNT { Average 30,000 Gallons Daily

Maximum 10,000 Gallons Daily

QUALITY OF WATER Good Sample: Yes \_\_\_\_\_ No. X

Taste None Odor None Color None Temp. 50 of

LOG (other side) Are samples available? no

(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)

SOURCE OF DATA self

DATA OBTAINED BY self Date Sept. 5, 1961

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

ATTACHMENT C11

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
DIVISION OF WATER POLICY & SUPPLY  
**WELL RECORD**

Permit No. 25-15756  
Application No. \_\_\_\_\_  
County Morris

1. OWNER B. W. B. Corp. ADDRESS \_\_\_\_\_  
Owner's Well No. \_\_\_\_\_ SURFACE ELEVATION \_\_\_\_\_ Feet  
(Above mean sea level)

2. LOCATION 160 Ridgedale Ave Morris Township

3. DATE COMPLETED April 10-71 DRILLER Algeier Bros

4. DIAMETER: top 6 inches Bottom 6 inches TOTAL DEPTH 350 Feet

5. CASING: Type BIK Threaded Diameter 6 inches Length 175 Feet

6. SCREEN: Type \_\_\_\_\_ Size of Opening \_\_\_\_\_ Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet

Range in Depth { Top \_\_\_\_\_ Feet  
Bottom \_\_\_\_\_ Feet  
Geologic Formation START NOTM RB

Tail piece: Diameter \_\_\_\_\_ inches Length \_\_\_\_\_ Feet

7. WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface

8. RECORD OF TEST: Date April 10-71 Yield 45 Gallons per minute

Static water level before pumping 50 Feet below surface

Pumping level 275 feet below surface after 4 hours pumping

Drawdown \_\_\_\_\_ Feet Specific Capacity \_\_\_\_\_ Gals. per min. per ft. of drawdown

How Pumped Submersible How measured \_\_\_\_\_

Observed effect on nearby wells \_\_\_\_\_

9. PERMANENT PUMPING EQUIPMENT:

Type Submersible Mfrs. Name Fairbanks & Morse

Capacity 50 G.P.M. How Driven elect. H.P. 7 1/2 R.P.M. 3450

Depth of Pump in well 280 Feet Depth of Footpiece in well \_\_\_\_\_ Feet

Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump \_\_\_\_\_ Size \_\_\_\_\_ inches

10. USED FOR Car Wash AMOUNT { Average \_\_\_\_\_ Gallons Daily  
Maximum \_\_\_\_\_ Gallons Daily

11. QUALITY OF WATER good Sample: Yes \_\_\_\_\_ No \_\_\_\_\_

Taste None Odor None Color clear Temp. \_\_\_\_\_ °F

12. LOG \_\_\_\_\_ Are samples available? \_\_\_\_\_

(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)

13. SOURCE OF DATA \_\_\_\_\_

14. DATA OBTAINED BY Conrad Algeier Date March 16-72

(11)

25.14.1.7.8

**DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT  
Division of Water Policy & Supply  
WELL RECORD**

Permit No. 25-3701  
Application No. \_\_\_\_\_  
County \_\_\_\_\_

1. OWNER T. LANDI + SON ADDRESS MORRISTOWN NJ  
Owner's Well No. 2 SURFACE ELEVATION ± 310' Feet  
(Above mean sea level)
2. LOCATION RIDGEDALE AVE MORRISTOWN NJ
3. DATE COMPLETED 8-25-54 DRILLER DALE H. FEAKINS
4. DIAMETER: Top 8 Inches Bottom 8 Inches TOTAL DEPTH 48 Feet
5. CASING: Type STEEL Diameter 8 Inches Length 39 Feet
6. SCREEN: Type JOHNSON Size of Opening 50 Diameter 8" Inches Length 10 Feet  
Range in Depth { Top 38 Feet Geologic Formation SAND + GRAVEL  
Bottom 48 Feet  
Tail piece. Diameter 0 Inches Length 0 Feet
7. WELL FLOWS NATURALLY \_\_\_\_\_ Gallons per Minute at \_\_\_\_\_ Feet above surface  
Water rises to \_\_\_\_\_ Feet above surface
8. RECORD OF TEST: Date 8-1-55 Yield 90 Gallons per minute  
Static water level before pumping 28 Feet below surface  
Pumping level 48 feet below surface after 3 MIN hours pumping  
Drawdown 20 Feet Specific Capacity 4 1/2 Gals. per min. per ft. of drawdown  
How Pumped DEEP WELL TURBINE How measured ORIFICE  
Observed effect on nearby wells NONE
9. PERMANENT PUMPING EQUIPMENT:  
Type DEEP WELL TURBINE Capacity 100 Gallons per minute  
How Driven ELECTRIC Horse Power 7 1/2 R.P.M. 1750  
Depth of pump in well 40 Feet Depth of Foot piece in well 0 Feet  
Depth of Air Line in well \_\_\_\_\_ Feet Type of Meter on Pump 0
10. USED FOR WASHING GRAVEL AMOUNT { Average 42-45000 Gallons Daily  
Maximum 50,000 Gallons Daily
11. QUALITY OF WATER Good Sample: Yes \_\_\_\_\_ No. \_\_\_\_\_  
Taste 0 Odor 0 Color 0 Temperature \_\_\_\_\_ °F
12. LOG SAND + GRAVEL TO 50' - 50'-90' HARD PAN Are samples available? \_\_\_\_\_  
(Give details on back of sheet or on separate sheet)
13. SOURCE OF DATA DALE H. FEAKINS
14. DATA OBTAINED BY D. H. Feakins DATE 1/27/55

(Note: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements, etc.)

ATTACHMENT C13

ATTACHMENT D

STATE OF NEW JERSEY  
DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT

DIVISION OF WATER POLICY  
AND SUPPLY



SPECIAL REPORT 25

AVAILABILITY OF GROUND WATER  
IN MORRIS COUNTY, NEW JERSEY

Prepared in cooperation with  
United States Department of the Interior  
Geological Survey

1965

ATTACHMENT P1

G

SIC



ground-water resources of the county. This report represents the first detailed discussion of the ground-water resources of Morris County.

### ACKNOWLEDGMENTS

The authors wish to thank the numerous well drillers, office of the New Jersey Bureau of Geology and Topography, and other State, municipal, and industrial officials, and private individuals who supplied data on which this report is based. The cooperation of many of these who permitted use of their wells for water-level observations, collection of water samples, logging purposes, and pumping tests is gratefully acknowledged.

## GEOGRAPHY

### TOPOGRAPHY

Morris County is part of the Appalachian Highland, one of eight major physiographic divisions of the United States. The Appalachian Highland consists of several physiographic provinces; two of these, the New England and the Piedmont, are present in the county.

The New England province, locally known as the New Jersey Highlands, occupies that part of the county lying northwest of a line passing near Morristown, Boonton and Riverdale (fig. 2). It consists of several broad, rounded or flat-topped ridges separated from each other by deep and generally narrow valleys. Altitudes of more than 1,000 feet are quite common on the ridges; a few exceed 1,300 feet. The larger topographic features of the Highlands show a marked northeast-southwest trend; however, some of the prominent valleys, such as the Rockaway and the Pequannock, are transverse to the regional trend.

The Piedmont province, which occupies the southeastern part of the county, is chiefly a lowland of gently rounded hills with a few ridges and isolated hills rising conspicuously above the plain. Most of this area lies at altitudes of about 200 to 400 feet. Several large swamps, of which the Great Swamp is the most extensive (fig. 1), occupy a large part of the lower lying areas. The topography of much of the Piedmont province in Morris County has been considerably modified by the Wisconsin Glaciation, the last of the great Pleistocene ice advances in North America.

Morris County lies within three major drainage basins—the Passaic, the Raritan, and the Delaware. The eastern two-thirds of the county is drained by the Passaic River and its major tributaries, the Pequannock, Pompton, Rockaway, and Whippany Rivers (fig. 1). Most of the southwestern part of the county lies in the Raritan River drainage basin which is drained by the North and South Branches of the Raritan River and the Lamington River. The Musconetcong River, which flows into the Delaware River, drains a narrow area along the western border of the county.

### CLIMATE

The climate of Morris County, and of the State as a whole, is largely continental, mainly owing to the predominance of winds from the interior of North America. Winters are controlled by polar continental air masses, and summers by tropical air masses which, although maritime in origin, display long continental trajectories over very warm land masses before

Table 2.—Population of municipalities in Morris County, N. J.  
since 1940—Continued

(Data from U. S. Bureau of Census)

<i>Municipality</i>	<i>1960</i>	<i>1950</i>	<i>1940</i>
Mountain Lakes	4,037	2,806	2,205
Mt. Arlington	1,246	639	456
Mt. Olive Township	3,807	2,597	1,526
Netcong	2,765	2,284	2,157
Parsippany-Troy Hills Township	25,557	15,290	10,976
Passaic Township	5,537	3,429	2,664
Pequannock Township	10,553	5,254	2,856
Randolph Township	7,295	4,293	2,160
Riverdale	2,596	1,352	1,110
Rockaway	5,413	3,812	3,514
Rockaway Township	10,356	4,418	2,423
Roxbury Township	9,983	5,707	4,455
Victory Gardens	1,085	Part of Randolph Twp.	
Washington Township	3,330	2,147	1,870
Wharton	5,006	3,853	3,854
Total for county	261,620	164,371	125,732

The economy of Morris County is primarily industrial. The principal manufactured items include chemicals, electrical goods and machinery, other machinery, and rubber products (New Jersey Department of Conservation and Economic Development, 1960). Farmland comprises about 16 percent of the total land area of which the principal products are dairy, poultry, corn, oats, and some vegetables (U. S. Dept. of Commerce, 1959).

## GEOLOGY

### INTRODUCTION

Various rock types representing several geologic periods crop out in Morris County. The oldest of these are the Precambrian crystalline rocks exposed in the northwestern two-thirds of the county, in the New England province. Associated with the Precambrian rocks are long narrow belts of Paleozoic sedimentary rocks—shales, sandstones, and limestones.

The southeastern third, or the Piedmont province, of the county is underlain by Triassic sandstones and shales with interbedded basaltic lava flows. Unconsolidated deposits of glacial and fluvial origin overlie much of the Triassic outcrop area, and, to a lesser extent, parts of the New England province. These deposits consist of stratified and unstratified sand, clay, and gravel deposited by various glacial phenomena and streams.

Brief descriptions of the formations exposed in Morris County are presented in table 3. The generalized geologic map (fig. 2) shows the areal extent of the various rock units and their structural relationships.

### DISTRIBUTION AND LITHOLOGY OF THE MAJOR ROCK UNITS

#### Precambrian Rocks

Crystalline rocks of Precambrian age underlie almost all of the northwestern two-thirds of the county (fig. 2). They are mainly granitoid gneisses and pegmatites but include also schists, crystalline limestone or marble, magnetite, and a few small quartz veins. For purposes of mapping, these rocks have been divided into four formations—the Franklin Limestone, the Pochuck Gneiss, the Losee Gneiss, and the Byram Gneiss. These formations are considered as a unit in this report because their water-bearing properties are virtually similar.

The gneisses, of which the Byram and Losee are most abundant, are distinguished by their color and mineral composition. The dark-colored gneisses that owe their color to an abundance of hornblende, pyroxene, or biotite have been grouped together under the name Pochuck Gneiss. The Byram Gneiss is generally brownish-gray and contains potash feldspar as an essential mineral component. The Losee Gneiss includes light-colored granitoid rocks, many of them nearly white, which contain soda-lime feldspar as an essential and characteristic mineral component.

Table 3.—Stratigraphic table describing the rocks exposed in Morris County

<i>Era</i>	<i>Period</i>	<i>Formation</i>	<i>Thickness (feet)</i>	<i>Lithology</i>	<i>Character of topography and soil</i>
Cenozoic	Quaternary	Alluvium	0-25	Sands, clays, and gravels deposited along stream channels	Valley bottoms; sandy clay-loam soil
		Glacial drift	0-400	Sands, clays, and gravels of glacial origin	Low linear hills; valley bottoms
		Unconformity			
Mesozoic	Triassic	Watchung Basalt	200-450	Three basaltic lava flows interbedded with the Newark Group; only one crops out in Morris County	Low linear hills
		Brunswick Formation	6,000-8,000	Interbedded, soft, red sandstones, shales, conglomerates, and arkoses	Wide rolling lowland; sandy clay-loam soil
		Unconformity			
Paleozoic	Devonian	Cornwall Shale	1,000±	Dark thick-bedded shale, somewhat sandy toward the top	Low rolling hills; sandy clay soils
		Kanouse Sandstone	215	Fine-grained white quartz conglomerate, with greenish sandstone above.	Valley bottoms and low ridges; sandy soil
		Unconformity			
	Silurian	Decker Limestone	50	Dark gray impure siliceous and shaly limestone	Valley bottoms
		Longwood Shale	200±	Soft red shale	Valley bottoms; clay soil
		Green Pond Conglomerate	1,500±	Coarse quartz conglomerate, interbedded with and grading upward into quartzite and sandstone	High, steep-sided, even-crested ridges; sandy soil
		Unconformity			

Table 3.—Stratigraphic table describing the rocks exposed in Morris County—Continued

<i>Era</i>	<i>Period</i>	<i>Formation</i>	<i>Thickness (feet)</i>	<i>Lithology</i>	<i>Character of topography and soil</i>
Paleozoic	Ordovician	Martinsburg Shale	3,000±	Fine black shale, slate, and sandstone; sandstones dark to bluish gray, in part calcareous, and most numerous in upper portion of formation	High rolling hills; stony clay and loamy soils, generally thin
		Jacksonburg Limestone	135-150	Dark fossiliferous limestone and shale; limestone conglomerate at the base	High slopes; clayey soils
		Unconformity			
	Cambrian	Kittatinny Limestone	2,500-3,000±	Massive-bedded bluish-gray magnesian limestone containing layers of black chert and oolite; shales and interbedded thin limestones at top and base	Valley floors and rolling hills; locally rough "warty" topography; clayey soils, in places thin
		Hardyston Quartzite	5-200	Arkosic quartzite, in places conglomeritic	Hill slopes
Precambrian		Byram, Losee, and Pochuck Gneisses and Franklin Limestone		Gneisses of both sedimentary and igneous origin; crystalline limestone	High ridges with plateau-like summits and steep slopes; thick stony soils in areas not covered by glacial drift

The Franklin Limestone is generally a white coarsely crystalline marble. Its principal mineral component is calcite but dolomite predominates in some areas.

The gneisses generally occur as tabular masses that strike northeast and dip steeply to the southeast. The Franklin Limestone occurs as small isolated masses within the gneissic complex.

#### Paleozoic Rocks

Rocks of Paleozoic age crop out in three parallel belts (fig. 2) within Morris County. The belts trend northeast-southwest, similar to the major structural features of the gneissic complex with which they are associated. The Paleozoic rocks have been complexly folded and faulted, and these belts are remnants of the once continuous folds.

The first belt lies along the westernmost edge of the county. The width of this belt within the county is less than a mile.

A second belt traverses the county from Newfoundland to Middle Valley, attaining its maximum width at its northeastern end where it is about 4 miles wide. At its southwestern end, it is about 1 mile wide.

The third belt of Paleozoic rocks crops out to the west of Mendham. Within the county, this belt has a length of 5 miles and a maximum width of about 1 mile.

The Paleozoic rocks cropping out in Morris County consist of conglomerate, sandstone, quartzite, shale, and limestone. These rocks have been divided into several formations which are from oldest to youngest, respectively: the Hardystone Quartzite of Early Cambrian age, the Kittatinny Limestone of Late Cambrian and Early Ordovician age, the Jacksonburg Limestone and Martinsburg Shale of Ordovician age, the Green Pond Conglomerate, Longwood Shale, and Decker Limestone of Silurian age, and the Kanouse Sandstone and Cornwell Shale of Middle Devonian age. The lithology of each of these formations is described briefly in table 3.

Except for the Kittatinny Limestone, the Paleozoic formations are not important aquifers within the county because of their limited areal extent and their poor water-bearing properties. Therefore, the Paleozoic formations are not differentiated on the geologic map (fig. 2) except where the Kittatinny Limestone crops out over an extensive area.

#### Triassic Rocks

Rocks of Triassic age underlie the entire southeastern third of the county, (fig. 2). The Triassic System, known as the Newark Group,

consists of alternating soft sandstones and shales with three sandwiched sheets of basalt.

The sedimentary rocks of the Newark Group are generally reddish-brown, although black, gray, and green beds are present locally. For the most part, the rocks consist of thin-bedded sandstones and shales. Near the northwestern margin of the Triassic rocks, conglomerate beds are interlayered with the beds of sandstone and shale. The conglomerates contain pebbles and boulders of many different rock types—granite gneiss, limestone, basalt, sandstone, quartzite, and slate. Because of their varied composition, the conglomerate beds do not exhibit a uniform color.

Sandwiched with the beds of sandstone and shale are three extensive sheets of basalt, only one of which—the uppermost sheet—is exposed in Morris County. The basalt sheets were formed by lava flows which were extruded at three different times during the accumulation of the sedimentary rocks of the Newark Group. The basalt is much more resistant to erosion than are the shale and sandstone, and therefore forms prominent ridges. The first sheet forms First Watchung Mountain, the second sheet forms Second Watchung Mountain, and the third sheet, the only one exposed in Morris County, forms a discontinuous ridge whose parts in Morris County are called Long Hill and Hook Mountain (fig. 2). This basalt sheet is about 450 feet thick at Hook Mountain and about 250 feet thick at Long Hill (Darton & others, 1908, p. 10).

The Triassic rocks generally exhibit a monoclinical structure; the strata dip gently to the west-northwest at about 8° to 10°. Local flexures occur in some areas, particularly in the area surrounding Morristown. Here the rocks have been warped into a gentle anticline whose axis trends northeast-southwest. The basalt sheets have virtually the same attitude as the sedimentary rocks.

#### Quaternary Rocks

The Quaternary rocks comprise the unconsolidated surficial deposits which mantle the bedrock surface over a large part of Morris County. These deposits are as a rule of local distribution and consist of clay, silt, sand, gravel, and boulders and, in many places, are without systematic arrangement. They are glacial, lacustrine, or fluvial in origin.

The deposits of Pleistocene age represent two or possibly three of the stages into which the Pleistocene of North America has been subdivided. They are chiefly of glacial origin but include also fluvial deposits that are believed to be contemporaneous with one of the glacial invasions.

South of the terminal moraine of the last (Wisconsin) glaciation lie many patches of older glacially derived material, the age of which cannot be determined with certainty but which belong to one or more of the earlier glaciations (fig. 3).

The drift is generally thin, but in some places it has a thickness of 30 feet. The oxidation and deep coloration of the matrix, deep disintegration of most of the stony material, the absence of calcareous and other soluble material, and the fragmentary and much eroded character of the deposits are indicative of a deposit much older than the sediments of the Wisconsin Glaciation.

Glacial drift of Wisconsin age covers most of the northern half of Morris County. The material is till, sand, gravel, and lacustrine silt and clay. The deposits fall into three general classes—terminal moraine, ground moraine, and stratified drift, which is of several sorts including lacustrine and fluvial deposits. Figure 3 is an outline map of Morris County showing the extent of the terminal moraine and stratified drift deposits. Because the emphasis in this report is on the water-bearing properties of the Quaternary deposits, the deposits of ground moraine have been excluded from the map since they function mainly as a confining bed. The terminal moraine is emphasized to show the southernmost extent of the Wisconsin Glaciation.

The terminal moraine extends irregularly from east to west across Morris County from Chatham to Hackettstown (fig. 3). Chatham, Madison, Morris Plains, Denville, Rockaway, Wharton, and Netcong lie upon it or close to its borders.

Stratified drift of the Wisconsin Glaciation is widely distributed throughout Morris County. South of the terminal moraine, near Dover and Madison, considerable areas of stratified drift form outwash plains or valley trains. North of the moraine such drift, mostly in the form of low terraces, forms narrow belts in the valleys. At several places, however, it forms distinct kames. A few distinct ridges have the forms of eskers.

The lithologic character of the stratified drift differs from place to place with differences in the character of the underlying rock. Much of it is poorly sorted, although the stones are generally fairly well rounded and worn. Its thickness is not readily estimated, for wells rarely reach its base. Its depth is perhaps on the average two or three times that of the ground moraine (average ground moraine thickness in this area 5 to 12 feet).

Subsurface deposits of stratified drift have been encountered in numerous borings and wells along the eastern margin of Morris County. They are found as channel-fill deposits in pre-Pleistocene stream valleys. The general coarse texture of the material and their moderate areal distribution make them a substantial ground-water reservoir. These water-bearing deposits are used extensively in the outlined triangular area near and northeast of Chatham and Morris Plains (fig. 3). These channel deposits as yet are not well defined. Additional work is needed to define better the character and extent of these deposits. An intensive study would probably indicate other areas within Morris County that are underlain by highly permeable channel-fill deposits.

lower elevations. Ground water is discharged directly to the streams wherever they intersect the water table and supports streamflow during periods of no precipitation. See figure 4.

In the swampland areas that are underlain by clay and silt, such as those along the Passaic River, discharge of ground water to the streams is restricted by low permeability of the materials and the slight hydraulic gradients (Vecchioli and others, 1962). During the vegetative growing season, most of the ground-water discharge occurs in these areas as evapotranspiration and very little is discharged to the streams. Consequently, dry-weather streamflow is not augmented significantly by these areas; rather, it may even be reduced by the high rate of evapotranspiration.

In addition to the natural discharge of ground water by seepage into streams and by evapotranspiration, ground water is discharged artificially by the pumping of wells. Generally, the pumping has not been of sufficient magnitude or concentration to affect significantly the natural pattern of ground-water flow. However, in a few places of continuous heavy withdrawals, the artesian head has been lowered regionally as will be discussed later. In some areas, wells near streams that are in hydraulic continuity with the aquifer reverse the natural gradients when they are being pumped and thus induce recharge from the streams; this also will be discussed further.

## WATER-BEARING PROPERTIES OF MAJOR ROCK UNITS

### Precambrian Rocks

Precambrian crystalline rocks underlie almost all of the northwestern two-thirds of Morris County and are the only source of ground water in most of this area (fig. 2).

In the Precambrian rocks ground water occurs under water-table conditions. In some of the lower lying areas, the rocks are overlain by clay beds which confine the water, resulting in local artesian conditions. Virtually all the storage and movement of ground water in these rocks occurs in fractures that have been enlarged by weathering. The yield of a well tapping the Precambrian rocks depends largely on the size and number of intersecting fractures encountered by the well, a factor which varies considerably from place to place and also with depth. The capacity of the fractures to store and transmit water decreases with depth and experience has shown it is not worthwhile generally to drill deeper than about 300 feet when seeking to develop a water supply. If, within the first 300 feet of drilling, a well does not yield the required

supply, a better chance for success may be obtained by drilling a second well rather than by deepening the first well.

The yields of wells tapping Precambrian rocks in Morris County range considerably. Of 79 large-diameter public supply, industrial, and commercial wells, the maximum yield is 400 gpm, the minimum 4 gpm. The distribution of the yields is as follows:

<i>Yield (gpm)</i>	<i>Number of Wells</i>
0- 25	14
26- 50	20
51- 75	16
76-100	8
101-125	4
126-150	3
151-175	2
176-200	4
201-225	3
226-250	1
251-275	2
276-300	1
375-400	1

Figure 5 is a plot of the yield of these wells and the number of reports in groupings of 25 gallons per minute (fig. 5). As can be seen from the figure, there are at least two groups or populations of well yields. The bulk of these data are grouped in the 0 to 100 gpm range, and average 48 gpm. The remainder can be grouped from 100 to 400 gpm, and average 195 gpm. Precambrian wells in the 0 to 100 gpm range are probably deriving water from the regional fracture network whereas the majority of the higher yielding wells (over 100 gpm) either intercept or are located near major fault zones. Fault zones are areas along which rocks have ruptured and where there has been substantial vertical or horizontal movement. Such zones form a more extensive ground-water reservoir than is developed in regional fracture network.

The depths of the 79 large-diameter wells range from 50 to 822 feet, and average 223 feet. There is no apparent relationship between depth and yield of the wells tapping Precambrian rocks in Morris County.

Specific capacities of 56 wells tapping Precambrian rocks range from 0.06 to 15.10 and average 1.77 gpm per ft.




Figure 5.—Number of wells tapping the aquifers in the Precambrian rocks having yields within ranges indicated.

There was no opportunity to conduct pumping tests on wells tapping the Precambrian rocks during this investigation; hence, coefficients of transmissibility and storage were not determined. However, these coefficients can be estimated using specific capacities of wells (Theis, 1954) and other known hydrologic properties of the rocks. Coefficient of storage is estimated to be 0.001 based on prevailing water-table conditions and the low porosity of Precambrian rocks. Employing an average specific capacity of about 1.8 gpm per ft., the coefficient of transmissibility is estimated to be 2,000 to 3,000 gpd per ft. These values of transmissibility and storage are based on average conditions, and they are intended to indicate only an order of magnitude. Undoubtedly, the actual coefficients will depart considerably from the estimated values in some places.

The hydraulic characteristics of Precambrian rocks indicate that extreme care must be taken in developing new supplies near existing ones. Wells should be located to provide the least practical amount of mutual interference. Detailed hydrologic information at each site is necessary to evaluate adequately the possibility of developing moderate to large ground-water supplies from these rocks.

Water from the Precambrian rocks in Morris County generally is of suitable chemical quality for most uses. (See table 8.) It is soft (less than 60 ppm) to moderately hard, (60 to 120 ppm) the pH ranges from slightly acidic to slightly alkaline. Iron occurs in objectionable concentrations in some areas.

#### Paleozoic Rocks

Paleozoic rocks are minor aquifers in Morris County because of their limited areal extent. (See fig. 2.) Moreover, most Paleozoic rocks have poor water-bearing properties and are capable of sustaining only small domestic supplies. The Kittatinny Limestone is an exception, as will be discussed below. Locally, the sandstones are capable of yielding moderate to large supplies.

Because few wells tap Paleozoic rocks in Morris County, data are sparse regarding the water-bearing properties of these rocks. However, the mode of occurrence of ground water in these rocks varies considerably depending upon the lithology. Consequently, some general statements can be made as to the expected potential yields.

In shale formations, most of the ground water that is available to wells occurs in interconnecting fractures. Generally, openings provided

The average yield of 37 large-diameter public-supply, industrial, and commercial wells tapping these rocks is 142 gpm, ranging between 4 and 650 gpm. The distribution of the yields is as follows:

<i>Yield (gpm)</i>	<i>Number of Wells</i>
0- 50	11
51-100	8
101-150	3
151-200	8
201-300	5
>300	2

The depths of the 37 wells range from 90 to 985 feet and average 368 feet. Specific capacities of 34 wells range from 0.03 to 33.33 and average 4.57 gpm per foot with six of the wells greater than 4 gpm per foot.

Most wells drilled into the basalt produce small quantities of water from depths of less than 300 feet. The yield of 5 large-diameter public supply wells ranged from 30 to 53 gpm. Rarely is a well drilled that produces no water or that yields more than 50 gpm. The specific capacities of wells that tap the basalt are generally much less than 1 gpm per foot.

Except for hardness-forming constituents, water from the Triassic rocks generally does not contain objectionable concentrations of any chemical constituents. (See table 8.) However, the hardness of the water ranges from moderately hard (60 to 120 ppm) to very hard (over 180 ppm), and in some places a high sulfate content imparts a noncarbonate hardness to the water. Water from the basalt locally may contain objectionable amounts of iron as well as hardness-forming constituents. The pH of the water from the Triassic rocks is generally slightly alkaline.

#### Quaternary Rocks

The Quaternary rocks comprise the unconsolidated surficial deposits which mantle the bedrock over a large part of Morris County. These deposits are as a rule of local distribution and consist of clay, silt, sand, gravel, and boulders which fall into three general classes—terminal moraine, ground moraine, and stratified drift. Of the three, only the stratified drift deposits merit detailed consideration for their water-bearing properties. These stratified drift deposits form the mineral framework for the most highly developed ground-water reservoir in the county. Ground-water withdrawals in Morris County obtained from the aquifers in the stratified drift deposits amount to 24 mgd or 77 percent of the

total diversions. The deposits are generally capable of sustaining large yields (over 200 gpm) of a good quality of water to wells.

Unconfined ground water occurs in the stratified drift deposits where they are not mantled by the glacial till. The unconfined drift deposits which are well illustrated in figure 3, are related and closely associated with the present-day alignment of the surface-drainage network. Some of the drift was deposited as a valley train or outwash plain when the direction of river flow was different than it is today, but the association is evident. The unconfined deposits associated with the Rockaway River are the most extensively developed in Morris County. The public supplies of Wharton, Dover, Rockaway, Mountain Lakes, and Boonton are drawn in large part from the drift deposits. Figure 3 indicates the areas from which moderate to large supplies have been developed from the stratified drift deposits. The unconfined aquifer is recharged directly from precipitation on the outcrop area of the stratified drift.

Ground water occurs under confined conditions in the stratified drift deposits where they are overlain by clay or silt beds which are part of the glacial till. These confined drift deposits are concealed and their regional extent is not as apparent as the unconfined drift. These water-bearing deposits are used extensively in the outlined area near and northeast of Chatham and Morris Plains, (fig. 3). They are sinuous in nature and restricted to pre-existing stream or river channels. Additional geologic and geophysical work will determine the character and extent of these deposits and also indicate other areas within Morris County that are probably underlain by highly permeable channel-fill deposits.

The confined drift deposits are recharged in part from the underlying and adjacent bedrock. Water entering fractures in the bedrock is derived from precipitation in the upland outcrop areas. This water moves under artesian pressure in response to the hydraulic gradient through the fracture network to the buried channel deposits. The original static levels in many of the wells tapping these deposits in the lowland areas in the southeastern part of the county were above land surface, producing flowing artesian wells.

In the Florham Park-Chatham area, the confined drift deposits have been extensively developed. Figure 6 is a generalized geologic cross section from the Allied Chemical well in Morris Township to the Commonwealth Water Company well in Millburn Township, Essex County—which shows the continuous nature of the confined channel deposit. The



piezometric surface shown indicates a regional slope to the southeast, indicating the general direction of ground-water movement. The original piezometric head in the Madison-Station Road-well field (well A in fig. 6) in 1898 was 204 feet above sea level or about 6 feet below to 10 feet above land surface, depending on the individual well location. Figure 7 illustrates the regional decline in water level in the Madison area since 1900. Since 1953, continuous water-level recorders have been maintained in increasing numbers throughout this area. The continuous decline in average water level is related to increases in pumpage. Continued increases in pumpage will mean a continued decline in the regional piezometric surface.

In Wharton and Dover, the municipal supplies are obtained from the unconfined or semi-confined drift deposits along the Rockaway River (fig. 3). Under static or nonpumping conditions, the movement of ground water is toward the river. Under pumping conditions, the gradient is reversed and there is movement of water from the Rockaway River toward the pumping wells. The location of a well near and in hydraulic continuity with a river is very advantageous. The induced recharge from the river substantially increases the amount of ground water available in the area. This pattern of pumpage has the advantage of utilizing surface water that otherwise would be lost to the area.

The Quaternary deposits are the most productive aquifers in Morris County based on their permeability, and present and potential yield. As part of the regional investigation of the ground-water resources, 13 detailed aquifer tests were made by the Geological Survey on wells tapping the drift deposits (table 4). Analysis of the test data indicates an average coefficient of transmissibility of the aquifers of about  $135,000 \text{ gpd}$  per foot, and coefficient of storage of about  $3.9 \times 10^{-4}$ .

The average yield of 127 large-diameter public supply, industrial, and commercial wells tapping the stratified drift deposits is 502 gpm, ranging between 20 and 2,200 gpm. The distribution of the yields is as follows:

Yield (gpm)	Number of Wells
0- 49	3
50- 99	11
100-199	12
200-499	48
500-999	33
>1,000	20




Figure 7.—Graph showing average water levels in the

Table 4.—Coefficients of storage and transmissibility for the Quaternary deposits as computed from aquifer tests

Owner and location	Test well number	Number wells used	Pumping rate, gpm	Transmissibility (T) gpd/ft.	Storage (S)
Commonwealth Water Company,	49-50-51	5	1,700	137,000	$3.3 \times 10^{-4}$
Canoe Brook field,				113,000	$5.0 \times 10^{-4}$
Millburn Twp.,				122,000	$3.5 \times 10^{-4}$
Essex Co., N. J.	E	2	120	185,000	$4.6 \times 10^{-4}$
				66,700	$5.8 \times 10^{-4}$
	49	1	1,170	66,400	$1.1 \times 10^{-3}$
				134,000	$2.3 \times 10^{-4}$
Chatham Water Dept., Chatham, N. J.	1	1	1,150	69,400	$1.5 \times 10^{-4}$
	1	1	1,150	242,000	$3.5 \times 10^{-4}$
Madison Water Dept., Madison, N. J.	B	4	1,200	259,000	$3.3 \times 10^{-4}$
				229,200	$2.3 \times 10^{-4}$
				211,500	$2.7 \times 10^{-4}$
	C	1	1,200	229,000	$3.8 \times 10^{-4}$
				162,000	$2.0 \times 10^{-4}$
Esso Eng. and Design Co., Florham Park, N. J.	1	1	1,150	100,000	$2.0 \times 10^{-4}$
				92,800	$2.0 \times 10^{-4}$
Allied Chemical Co., Morris Twp., N. J.	2	1	675	12,800	$4.7 \times 10^{-4}$
	2	1	517	14,500	$5.7 \times 10^{-4}$
				9,600	$4.0 \times 10^{-4}$
Florham Park Water Dept., Florham Park, N. J.	Columbia Ave.	1	1,040	113,000	$9.3 \times 10^{-4}$
				100,000	$9.0 \times 10^{-4}$
Greystone Park State Hospital, Morris Plains, N. J.	2	2	400	166,000	$1.5 \times 10^{-4}$
				156,600	$1.8 \times 10^{-4}$
Wharton Water Dept., Wharton, N. J.	1	1	410	187,500	$5.2 \times 10^{-4}$
				191,700	$5.0 \times 10^{-4}$

The average specific capacity of 110 large-diameter wells is 30.86 gpm per foot; these range between 0.24 and 500 gpm per foot.

Except for hardness-forming constituents, water from the stratified drift deposits generally does not contain objectionable concentrations of any chemical constituents. (See table 8.) However, the hardness of the water ranges from soft to very hard. The distribution of total hardness is as follows:

Total hardness (ppm)	Number of wells
< 60 (soft)	4
61-120 (moderately hard)	13
121-180 (hard)	7
> 180 (very hard)	4

The four wells having a total hardness over 180 ppm also have higher than normal chlorides and nitrates. This association of constituents suggests a local low grade pollution problem, probably resulting from either sewage or from the use of chemical fertilizers in the vicinity.

## WATER SUPPLY

### Utilization of Ground Water

An average of almost 31 mgd (million gallons daily) of ground water was withdrawn from aquifers in Morris County during 1960. Of this, about 16 mgd were pumped for public supply (table 5). Pumpage for industrial, commercial, and institutional use amounted to 11 mgd and pumpage for other uses, including domestic, farm, and small industrial use, accounted for 4 mgd.

Quaternary aquifers were the source of 77 percent, or 24 mgd, of the pumpage. (See table 6.) Precambrian aquifers supplied 4 mgd, Triassic aquifers 2 mgd, and Paleozoic aquifers 1 mgd.

Nearly half of the average daily withdrawal occurred in five municipalities. Pumpage in Hanover Township, amounting to 4.8 mgd, exceeded by far that in any other municipality (fig. 9). Parsippany-Troy Hills Township, Florham Park, Dover, and Roxbury Township each had pumpage of more than 2 mgd. Only four municipalities—Butler, Netcong, Pequannock Township, and Victory Gardens—had no reportable pumpage.

ATTACHMENT E

## MONITORING WELL RECORD

Well Permit No. 25 41836  
Atlas Sheet Coordinates 25 12 621OWNER IDENTIFICATION - Owner AUSTIN, PETER  
Address P.O. BOX 29  
City MORRIS PLAINS State NJ Zip Code \_\_\_\_\_WELL LOCATION - If not the same as owner please give address. Owner's Well No. MW-1  
County MORRIS Municipality MORRISTOWN TOWNSHIP Lot No. 11 Block No. 4801  
Address Peter Austin, 89 MORRIS ST.TYPE OF WELL (as per Well Permit Categories) MONITORING Date well completed 9.8.92  
Regulatory Program Requiring Well \_\_\_\_\_ Case I.D. # \_\_\_\_\_

CONSULTING FIRM/FIELD SUPERVISOR (if applicable) \_\_\_\_\_ Tele. # \_\_\_\_\_

## WELL CONSTRUCTION

Total depth drilled 22 ft.Well finished to 22 ft.

Borehole diameter:

Top 6 in.Bottom 6 in.Well was finished: ☐ above grade  
☒ flush mountedIf finished above grade, casing  
height (stick up) above land  
surface \_\_\_\_\_ ft.Was steel protective casing installed?  
☐ Yes ☒ NoStatic water level after drilling 5 ft.Water level was measured using tapeWell was developed for 1 hours at 10' gpmMethod of development pumpWas permanent pumping equipment installed? ☐ Yes ☒ No

Pump capacity \_\_\_\_\_ gpm

Pump type: \_\_\_\_\_

Drilling Method air w/ casingDrilling Fluid \_\_\_\_\_ Type of Rig B-50Name of Driller Donald Grahamer JrHealth and Safety Plan submitted? ☒ Yes ☐ NoLevel of Protection used on site (circle one) None D C B AN.J. License No. M1212Name of Drilling Company EMMIT WELL DRILLING

I certify that I have drilled the above-referenced well in accordance with all well permit requirements and all applicable State rules and regulations.

Driller's Signature Donald Grahamer Jr.Date 10-24-92

COPIES: White &amp; Green - DEPE Canary - Driller Pink - Owner Goldenrod - Health Dept.

PLATE 2D

ATTACHMENT E1

	Depth to Top (ft.) [From land surface]	Depth to Bottom (ft.)	Diameter (inches)	Type and Material
Inner Casing	6"	12	2	PVC
Outer Casing (Not Protective Casing)				
Screen (Note slot size)	12	22	2	PVC .020
Tail Piece				
Gravel Pack	11	22		Morie #2
Annular Seal/Grout	0	11		B. Pellets / Port / und
Method of Grouting	tremie			

## GEOLOGIC LOG

(Copies of other geologic logs and/or geophysical logs should be attached.)

attached

MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION  
(One form must be completed for each well)

Name of Permittee: Peter Austin  
Name of Facility: VIP Cleaners/Former Morristown Tire Facility  
Location: 89 Morris Street, Morristown, New Jersey 07960  
NJDES Permit No: \_\_\_\_\_

CERTIFICATION

Well Permit Number (As assigned by NJDEP's Well Drilling Permit Section (609-984-6831)): 2 5 -4 1 8 3 6  
Owner's Well Number (As shown on the application or plans): MW-1  
Well Completion Date: September 8, 1992  
Distance from Top of Casing (cap off) to ground surface (one-hundredth of a foot): -0.38 feet  
Total Depth of Well (one-hundredth of a foot): -22.50 feet  
Depth to Top of Screen from Top of Casing (one-hundredth of a foot): -11.62 feet  
Screen Length (feet): 10.00 feet  
Screen or Slot Size: 0.020 inch  
Screen or Slot Material: PVC  
Casing Material: (PVC, Steel or Other-Specify): PVC  
Casing Diameter (inches): 2.0 inches  
Static Water Level from Top of Casing at the Time of Installation (one-hundredth of a foot): -6.0 feet  
Yield (gallons per minute): N/A Monitoring well  
Length of Time Well Pumped or Bailed: 0 Hours 20 Minutes  
Lithologic Log: Attach

Authentication

I certify under penalty of law that, where applicable, I meet the requirements as specified on the reverse of this page, that I have personally examined and am familiar with the information submitted in the document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

James Johnston  
Name (Type or Print)

James Johnston  
Signature

New Jersey Professional Engineer  
Certification or License No. GE 35273

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

ATTACHMENT E2  
PLATE 2E

GROUND WATER MONITORING WELL CERTIFICATION - FORM B - LOCATION CERTIFICATION

Name of Permittee: PETER AUSTIN  
Name of Facility: 89 MORRIS STREET  
Location: TOWN OF MORRISTOWN, MORRIS COUNTY, NEW JERSEY  
NJPDES Number: \_\_\_\_\_

LAND SURVEYOR'S CERTIFICATION

Well Permit Number (As assigned by NJDEP's Water Allocation Section, 609-984-6831):

25-41836

This number must be permanently affixed to the well casing.

Longitude (one-hundredth of a second):

West 74° 28' 40.07"

Latitude (one hundredth of a second):

North 40° 47' 47.61"

Elevation of Top of Casing (cap off)  
(one-hundredth of a foot):

329.93'

Elevation of Top of PVC or Collar (cap off)  
(one-hundredth of a foot):

329.55'

Owners Well Number (As shown on the application or plans):

MW-1

AUTHENTICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

Gerald G. DeGroat 11/6/92  
PROFESSIONAL LAND SURVEYOR'S SIGNATURE

Gerald G. DeGroat, L.S.  
PROFESSIONAL LAND SURVEYOR'S NAME  
(Please print or type)


SEAL

N.J. L.S. NO. 26791  
PROFESSIONAL LAND SURVEYOR'S LICENSE #

ATTACHMENT E3

PLATE 3.

## WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is  
Top of Well Casing  
Unless Otherwise Noted.

\*Depth Below Land Surface  
\*\* Top of Casing

VIP Cleaners/  
Project Morristown Tire Well MW-1  
Town/City Morristown  
County Morris State New Jersey  
Permit No. 25-41836  
Land-Surface Elevation  
and Datum 329.93 feet ☒ Surveyed  
☐ Estimated  
Installation Date(s) September 8, 1992  
Drilling Method Air rotary  
Drilling Contractor Summit Drilling, Bridgewater,  
Drilling Fluid N/A

Development Techniques(s) and Date(s)  
Truck mounted centrifugal pump/  
evacuate and recharge  
September 8, 1992

Fluid Loss During Drilling \_\_\_\_\_ Gallon  
Water Removed During Development \_\_\_\_\_ Gallon  
Static Depth to Water \_\_\_\_\_ feet below T.O.C.  
Pumping Depth to Water \_\_\_\_\_ feet below T.O.C.  
Pumping Duration \_\_\_\_\_ Hours

Well Purpose Groundwater sampling,  
Remedial investigation  
subsequent to UST removal/discharge  
Remarks Flush mounted completion

Prepared by \_\_\_\_\_  
ATTACHMENT FA  
PLATE

## LOG OF BORING

BORING NO. MW-2  
 SURFACE ELEV. 329.93'  
 COMPLETION DATE 9-08-92

WATER LEVEL: 6'-0"  
 DATE:  
 JOB NUMBER: 5182

DEPTH FEET	SAMPLES	RESISTANCE STANDARD	MOISTURE CONTENT%	SYMBOL	DESCRIPTION
0					4" Bituminous concrete, crushed stone sub-base
-		7			Fill material - gray silty clay, trace to little ash, medium stiff, moist
-		7			
5		25			- Fill material grading to brown-gray clayey silt, little fine sand, little ash, moist, very stiff
-					
10		32			
-				ML	Light brown silt, trace to little fine sand, moist, very stiff
-					
15		23			- grading to very moist
-					
20		8		SP	Light brown fine sand, trace to little silt, loose, wet
-					
25					Boring completed @ 22 1/2' on 9-08-92
-					
30					

PMK GROUP

MW15182

PLATE 2A

ATTACHMENT F5





January 8, 1993

**PRINCIPALS:**

Philip M. Keegan  
James Ferris, P.E.  
Gerald Perricone, P.E.  
James Johnston, P.E.

**MANAGING PARTNERS**

Terry C. Damon  
Robert M. Gerard

State of New Jersey  
Department of Environmental Protection  
and Energy  
Division of Responsible Party Site Remediation  
401 East State Street  
CN 028  
Trenton, New Jersey 08625-0028

Attn: Mr. Eric Sussman

**RE: REMEDIAL INVESTIGATION ADDENDUM REPORT  
UNDERGROUND STORAGE TANK CLOSURE  
VIP CLEANERS/FORMER MORRISTOWN TIRE FACILITY  
89 MORRIS STREET  
MORRISTOWN, NEW JERSEY  
UST #0228873  
TMS #C91-4319  
CASE #92-02-14-1003  
PMK GROUP #5182**

RECEIVED  
STATE OF NEW JERSEY  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF RESPONSIBLE PARTY SITE REMEDIATION  
JAN 13 1993

Dear Mr. Sussman:

A review of site specific field logs has indicated that the static groundwater level reading prior to purging and sampling, measured on September 24, 1992 from within the casing of the groundwater monitoring well that had been installed at the subject site, to be 8.96 feet below the adjoining ground surface grade. It appears that this measurement was not included in the text of the Remedial Investigation Report dated November 23, 1992.

Additionally, the Chain of Custody included in the report for the groundwater samples collected from the referenced monitoring well on September 24, 1992 appears to indicate an incorrect date of sample relinquishment. The date on the bottom of the Chain of Custody Record should read 9/24/92, to be consistent with the groundwater sampling date.

ATTACHMENT F



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 1/24/92

GENERAL INFORMATION

PURVEYOR/  
FACILITY PARSIPPANY TROY HILLS WATER DEPARTMENT

FILE LOCATION PARSIPPANY TROY HILLS TWP, MORRIS CTY PW-ID # 1429001

MAILING ADDRESS 1001 PARPAPPANY BOULEVARD, PARPAPPANY NJ 07054

ADMIN. JACK FERRARO REQUIRED T-1  
LICENSES W-4

BUSINESS  
TELEPHONE # Admin.: 201 263 7099 Licensed Operators: T-4 W-4 JACK FERRARO

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): 18 ACTIVE WELLS SEE  
ATTACHED SHEET A.

Est Tot Eff Cap: 11.628MGD

TREATMENT: source, type, capacities(mgd): GAS CHLORINATION AT ALL  
WELLS 1016 CAP.

Est Tot Eff Cap: 11.628MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): 10 ACTIVE STORAGE  
TANKS SEE SHEET ATTACHED B

Est Tot Cap: 10.5MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):

6" LINE WITH MOUNTAIN LAKES

6" LINE WITH DENVILLE

6" LINE WITH RANDOLPH Est Tot Avail: \_\_\_\_\_

AUXILIARY POWER: location, type, capabilities: RIGHT ANGLE DRIVE AT WELL 12, 13,  
14, 15, 19 AND BOOSTERS 1, 3, 4, 5. DIESEL GENERATOR  
AT WELL 4, 2, 8

ATTACHMENT FE



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max JULY 91 11.810MGD Min FEB 91 5.243MGD Annual Average 8.12MGD

BULK PURCHASES (provider, mgd) SOUTHEAST MORRIS COUNTY MUA

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 12,945 % METERED 100

MUNICIPALITIES SERVED (est. services in each) ALL OF PASSIPPANY TROY HILLS TWP

TOTAL ESTIMATED POPULATION SERVICED 48,478

CURRENT/RECENT WATER RESTRICTIONS NONE

NEW CONSTRUCTION (Project Numbers) NEW BOOSTER FOR WELL #10, PAINT THREE TANKS, 16" MAIN

DISTRIBUTION MAINS: Sizing 4" (min) to 16" (max)  
Pressures 20PSI (min) to 175PSI (max)  
Hydrants/Flushing Program 1500 /yearly

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
A-200	24HR	6/90 10/90 4/91 12/91
Coliform	65 MONTH	88 MONTH THRU 12/91
Inorganics	3YRS	6/88 6/91
Nitrate	"	" "
Trihalomethanes	QUARTERLY	2, 5, 8, 11/91
Organics	—	—
Turbidity	—	—
SECONDARIES	3YRS	9/88 6/91
RADIOLOGICAL	4YR	begin 8/91

NAME OF LABORATORY PARTROY WATER DEPT (Coliform) CERTIFICATION # 14076

ADDRESS PASSAIC VALLEY WATER COMM # 16047

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES WELL #7 OFF LINE

TREATMENT DEFICIENCIES NONE



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICES



COMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLY

DATE 12/21/90

GENERAL INFORMATION

SURVEYOR/ FACILITY <u>SOUTHEAST MORRIS COUNTY M. U. A.</u>	
FILE LOCATION <u>MORRISTOWN, MORRIS COUNTY</u>	PW-ID # <u>1424001</u>
MAILING ADDRESS <u>101 WESTERN AVENUE, MORRISTOWN, N.J. 07960</u>	
ADMIN. <u>WILLIAM HUTCHINSON, SUPERINTENDANT</u>	REQUIRED T-3 LICENSES W-4
BUSINESS TELEPHONE # Admin. <u>(201) 538-5600</u> Licensed Operators: T-3	W-4

326-6866 FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): SEE ATTACHMENT #1

Est Tot Eff Cap: 14.102MGD

TREATMENT: source, type, capacities(mgd): SEE ATTACHMENT #1

Est Tot Eff Cap: 14.102MGD

FINISHED WATER STORAGE capacities(mg): SEE ATTACHMENT #2

EMERGENCY INTERC

0" w/ RANDOL

GREYSTONE

AUXILIARY POWER

PROVIDE POWER FOR BOILER

1424001  
01 4,5,7,8,9,11  
02 2,3,4,5,8,13  
03 1,2,3,4,5  
04 12,15

112 MG

1 MVA,

6" w/

GENERATORS



DELIVERY INFORMATION

WATER DELIVERED WATER (mgd, month, year) Max Min Annual Average

BULK PURCHASES (provider, mgd) FROM MORRIS COUNTY MUA @ .7MGD.

BULK SALES (customer, mgd) PARSIPPANY TROY HILLS @ .096MGD

NUMBER OF SERVICES 16,900 % METERED 100%

MUNICIPALITIES SERVED (est. services in each) MORRIS TOWNSHIP (6160) MORRISTOWN (4073) HANOVER TWP (4143) MORRIS PLAINS (1811) MENDHAM (342) HARDING (284) FLORHAM PARK (31) PARTRAY (22) CHATHAM (21) RANDOLPH (13)

CURRENT/RECENT WATER RESTRICTIONS NONE

NEW CONSTRUCTION (Project Numbers) NONE

DISTRIBUTION MAINS: Sizing 4" (min) to 24" (max) Pressures 28PSI (min) to 200PSI (max) Hydrants/Flushing Program 1800/ANNUAL

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	75/YEAR 6/MO	OK TACU 11/90
Inorganics	YEARLY	9/90
Nitrate	"	"
Trihalomethanes	QUARTERLY	2, 5, 9, 11, 90
Organics	3 YRS	12/88 9/90
Turbidity	DAILY	DAILY
A-280	2 X YR	6/89 11/85 6/90 8/90
SECONDARIES	YEARLY	12/88 6/85 6/90
SODIUM	YEARLY	12/88 " "
RADIOLOGICAL	4 YRS	12/88 DUE 92

NAME OF LABORATORY TOWNLEY RESEARCH CERTIFICATION # 18071

ADDRESS GARDEN STATE LAB 07044  
WATER WORKS LAB 07673

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE

TREATMENT DEFICIENCIES NONE

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION  
DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE 10/3/89 & 4/9/90

## GENERAL INFORMATION

PURVEYOR/  
FACILITY Madison Water Department

FILE LOCATION Madison Borough, Morris County PW-ID # 1417001

MAILING ADDRESS Municipal Building, Kings Rd., Madison, NJ 07940

ADMIN. James Allison - Twp. Administrator REQUIRED T-1  
LICENSES W-3

BUSINESS 521 DiBasso (200) 377-3007, 822-3571

TELEPHONE # Admin.: (201) 593-3038 Licensed Operators: T-3 W-4

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): Well A (1.08 MGD) - John Ave; Well B (1.69 MGD) - John Ave;  
Well C (1.92 MGD) - North Rd; Well D (1.2 MGD) - Cleveland St; Well E (1.7 MGD) - Niles Ave. Wells A & B have  
been off-line since June '86 due to contamination. Well D tested MCL's for tetrachloroethene  
for 9 months during Jan '89 thru May '90 (inclusive) Est Tot Eff Cap: \_\_\_\_\_

TREATMENT: source, type, capacities(mgd): Gas chlorination (w/ T-10lb capacity) at all wells

Est Tot Eff Cap: 7.59 MGDFINISHED WATER STORAGE: descriptions, locations, capacities(mgd): Two elevated tanks:Madison Avenue 0.5 MGMidwood Terrace 0.75 MGEst Tot Cap: 1.25 MGEMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): oral agreements for emergency use for:Florham Park Water Dept - 6" @ Ridge Lake Central; 8" @ Greenwood & Rosedale; 6" @ Brookdale.Northeast Morris County MUA - 6" @ Morris Tpk & Kitchell Rd (Morris Twp); (1) Chatham Water Dept - 10" @ Division &  
in Chatham Box; (1) N.J. Amer. Water Co. - 8" @ Watchung & Nox (Chatham Twp) Est Tot Avail: UNKNOWNAUXILIARY POWER: location, type, capabilities: Kohler diesel generator @ Wells B & D; gasoline powered  
generators @ Wells C & E; portable generators available for Chlorination



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

Sept '88		DELIVERY INFORMATION		Sept '88 - Aug '89	
PLANT DELIVERED WATER (med month year) Max 2.155 MGD		Aug '88 Min 1.462 MGD		Annual Average 1.755 MGD	
BULK PURCHASES (provider, mgd) None					
BULK SALES (customer, mgd) None					
NUMBER OF SERVICES 4800				% METERED	
MUNICIPALITIES SERVED (est. services in each) Madison Borough - 4767, Chatham & Morris Twp - 33					
				TOTAL ESTIMATED POPULATION SERVED 18,700	
CURRENT/RECENT WATER RESTRICTIONS None					
NEW CONSTRUCTION (Project Numbers) 4" main replacement					
DISTRIBUTION MAINS: Sizing 4" (min) to 12" (max) Pressures 48 psi (min) to 135 psi (max) Hydrants/Flushing Program No flushing for 2 yrs.					

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
A280+	twice/yr.	2/89, 11/89
Coliform*	22/month	done 22/month
Inorganics*	once/3 yrs.	done 1/4/90
Nitrate*	" "	done 1/4/90
Trihalomethanes	once/quarter	2/89, 6/89, 9/89, 3/90
Organics		
Turbidity		
Radionuclides	once/4 yrs.	done 1986
Secondary Parameters*	once/3 yrs.	done 1/4/90

NAME OF LABORATORY \*Madison Health Lab CERTIFICATION # 14049

ADDRESS 2a Central Ave - Madison

+Townley Research & Consulting, Inc. - CEA #18071 - 1750 W. Front St., Plainfield, NJ 08063 (MCL)  
COMPLIANCE EVALUATION

SOURCE DEFICIENCIES Wells A & D consistently exceed maximum contaminant levels for tetrachloroethylene; Wells B & E have had concentrations at or above MCL's for tetrachloroethylene on a periodic basis; pollution sources (underground storage tanks) exists within 100ft of all wells.

TREATMENT DEFICIENCIES Doors to all Chlorine Rooms lack panic type hardware

ATTACHMENT F6



DIVISION OF WATER RESOURCES  
ENFORCEMENT & REGULATORY SERVICESCOMPLIANCE EVALUATION INSPECTION  
PUBLIC COMMUNITY WATER SUPPLYDATE July 27, 1989

## GENERAL INFORMATION

SURVEYOR/ FACILITY <u>Florham Park Water Department</u>	
FILE LOCATION <u>Florham Park Borough / Morris County</u>	PW-ID # <u>1411001</u>
MAILING ADDRESS <u>111 Ridgedale Ave, Florham Park, N.J. 07932</u>	
ADMIN. <u>Dwight Longley</u>	REQUIRED T - 3 LICENSES W - 4
BUSINESS TELEPHONE # Admin.: <u>377-5800</u>	Licensed Operators: T-3 <u>R. Tantiello</u> W-4 <u>R. Tantiello</u>

## FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): Well #1 - Capped and Sealed  
Well #2 - 1000 GPM (1.4 MGD) - on Columbia Avenue  
Well #3 - 650 GPM (0.936 MGD) - at the Recreation Field  
Well #4 - 1300 GPM (1.872 MGD) - on Elm Street Est Tot Eff Cap: 4.248 MGD

TREATMENT: source, type, capacities(mgd): All three wells have Gas Chlorination (WRT - capacity of 10<sup>th</sup> / day, cc)  
Wells 2, 3 and 4 are sequestered with Sodium Hexametaphosphate for manganese.  
A chlorine detector and a Scott Air Pack is located in the Well House  
of Well #4. Est Tot Eff Cap: 4.248 MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): There are two storage tanks.  
1. 0.25 MG elevated tank at Columbia Turnpike  
2. 1.00 MG standpipe at Pollard Avenue  
Est Tot Cap: 1.25 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):  
1. Madison Water Department: 6" - 12" lines - 0.500 MGD  
2. East Hanover Water Department: 8" lines - 0.500 MGD  
Est Tot Avail: 1.0 MGD

AUXILIARY POWER: location, type, capabilities:  
Well #2 - Propane engine with a right angle drive.  
Well #3 - Gasoline engine with a right angle drive.  
Well #4 - Diesel Generator.

ATTACHMENT F1



NJDEP - DIVISION OF WATER RESOURCES  
PUBLIC COMMUNITY WATER SUPPLY INSPECTION



Page 2

DELIVERY INFORMATION

TOTAL DELIVERED WATER July '88 Feb '89 Annual 7188 - 6189  
(mgd, month, year) Max 1.908 MGD Min 0.875 MGD Average 1.209 MGD

BULK PURCHASES (provider, mgd) NONE

BULK SALES (customer, mgd) NONE

NUMBER OF SERVICES 3,040 % METERED 100

MUNICIPALITIES SERVED  
(est. services in each) 1. Madison - 3 services

2. East Hanover - 10 services

3. Balance in Florham Park

TOTAL ESTIMATED  
POPULATION SERVICED 11,579

CURRENT/RECENT WATER RESTRICTIONS Odd and Even Days - Lawns, Car washing, Since 1982.

NEW CONSTRUCTION  
(Project Numbers) Very Little

DISTRIBUTION MAINS: Sizing 4" (min) to 12" (max)  
Pressures 55 psi (min) to 90 psi (max)  
Hydrants/Flushing Program ~350 hydrants/ once per year

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	13 per month	13 per month
Inorganics	Every three years	Done 2/87; Due 2/90
Nitrate	"	"
Trihalomethanes	Four per year	Done 8/88, 11/88, 2/89, 7/89; Due 9/89, 12/89
Organics	"	"
Turbidity	"	"
A-280	Twice per year	Done 11/88, 3/89; Due 12/89
Secondary	Every three years	Done 2/87; Due 2/90
Radiochemical	Every four years - Gt'y	Done 1986; Due 1990

NAME OF LABORATORY Madison Health Dept. Environmental Profile Labs. CERTIFICATION # 14049/15526  
ADDRESS Madison, New Jersey Toms River, N.J.

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE


REAGENT DEFICIENCIES NONE

ATTACHMENT F8

ATTACHMENT G

SOIL SURVEY OF

# Morris County, New Jersey



United States Department of Agriculture  
Soil Conservation Service

In cooperation with  
New Jersey Agricultural Experiment Station  
Cook College, Rutgers University

and the  
New Jersey Department of Agriculture  
State Soil Conservation Committee

ATTACHMENT GL

IIC—50 to 96 inches, strong-brown (7.5YR 5/6) and yellowish-brown (10YR 5/6) gravelly fine sandy loam; massive; friable; 15 percent angular pebbles of limestone; mildly alkaline; abrupt, wavy boundary. 10 to 50 inches thick.

R—96 inches, thinly bedded, hard, impure, gray limestone bedrock.

The solum ranges from 40 to 60 inches in thickness. Depth to the fragipan ranges from 20 to 36 inches, and depth to bedrock is 5 to 8 feet or more. In most places the contact of the granitic gneiss drift in the upper part of the profile with the weathered limestone in the lower part of the profile is ill defined. In some places where the drift is very thin, a major part of the solum consists of material formed in material weathered from limestone. In other places the upper material is so thick that the solum includes material weathered from limestone. The content of angular pebbles and cobbles ranges from 5 to 20 percent, and scattered stones are in some places. In areas that are not limed, reaction is medium acid near the surface and neutral to mildly alkaline in the lower part. In areas that are limed, reaction is less acid near the surface.

The A horizon is 10YR in hue, 3 or 4 in value, and 2 to 3 in chroma.

The matrix of the B horizon is 4 or 5 in value and 6 to 8 in chroma. High-chroma mottles are 5YR or 7.5YR in hue, 5 or 6 in value, and 6 to 8 in chroma. Low-chroma mottles are 7.5YR or 10YR in hue, 6 to 7 in value, and 1 to 3 in chroma. Depth to mottles ranges from 10 to 18 inches. This horizon ranges from heavy loam to clay loam or silty clay loam. In most places it has moderate, medium, subangular blocky structure above the fragipan and weak, very coarse, prismatic; weak, very thick, platy; or weak, very coarse, prismatic with massive interiors in the fragipan. The B horizon ranges from friable above the fragipan to firm or extremely firm in the fragipan. The coarse fragments range from almost completely granitic gneiss in the upper part to largely limestone chips in the lower part.

The C horizon has value of 4 or 5 and chroma of 6 to 8. In some places isolated spots or speckles of high chroma are in a lower chroma matrix. These bright spots are small chips of highly weathered limestone. This horizon is loam to sandy loam and their gravelly analogs.

Turbotville soils are associated with Washington, Bartley, Cokesbury, and Edneyville soils. They have low-chroma mottles, whereas Washington and Edneyville soils are not mottled. Turbotville soils do not have the low-chroma matrix horizon that is common in Cokesbury soils. They have low-chroma mottles nearer to the surface than Bartley soils.

**Turbotville loam, 0 to 3 percent slopes (TuA).**—This nearly level soil is in swales that cross terraces and at the margins of terraces that extend along the base of valley side slopes. Included in mapping are small areas of Cokesbury and Bartley soils.

The dominant properties that affect the use of this nearly level soil are slow runoff; its low position on the landscape, where it receives drainage from surrounding higher areas; and a water table that is locally perched on the slowly permeable fragipan.

This soil is used for pasture, hay, cultivated crops, and woodland. If it is used for intensive cultivation or improved pasture, improvement of drainage is necessary. Drainage diversions, subsurface interceptor drains, and spot drainage are effective in helping to improve the soil for intensive farming. Poor drainage limits the use of this soil for community development. Capability unit IIw-71.

**Turbotville loam, 3 to 8 percent slopes (TuB).**—This soil has the profile described as representative of the series. Included in mapping are small areas of Bartley, Edneyville, and Washington soils and some areas of stony

or bouldery soils. This soil is in small, narrow waterways or elongated areas at the base of steeper slopes within large areas of better drained soils. It is generally managed along with areas of surrounding soils.

This gently sloping soil has lateral seepage on top of the fragipan and a seasonally perched water table. The hazard of erosion is moderate.

In areas that are not drained, pasture, hay, and woodland are common uses. For intensive cultivation, improvement of drainage is necessary. Using drainage diversions, subsurface interceptor drains, and spot drainage are suitable practices. In addition, a crop rotation, strip cropping, and diversions help to control erosion. Poor drainage and susceptibility to erosion limit the use of this soil for community development. Establishing a vegetative cover early during development, helps to reduce erosion. Capability unit IIe-71.

## Urban Land

Urban land consists mostly of areas that are either paved or built upon. The soils in the remaining open spaces have been reworked to the extent that the original profile cannot be recognized. The characteristics of the material are variable.

Areas of Urban land are in community development. They are not suited to other purposes.

**Urban land (Ua).**—This mapping unit is in areas that are mostly well-drained, deep sandy, gravelly, or stony material of assorted glacial deposits. The areas are on uplands that mostly range from gently sloping to strongly sloping. The surface has been smoothed and in most places leveled. Included in mapping are areas of moderately steep soils and small areas of undisturbed Rockaway, Hibernia, Riverhead, and Boonton soils and the Ellington loamy subsoil variant. Not assigned to a capability unit.

**Urban land, wet (Ub).**—This mapping unit is in areas that are mostly poorly drained to very poorly drained silty and clayey soils. These areas are on low positions in the landscape and are nearly level. They have slow permeability and are shallow over a seasonal high water table. Included in mapping were small undisturbed areas of Whippany and Parsippany soils. Most of this mapping unit results from cut and fill operations associated with site preparation to achieve slightly elevated areas of better drained soil. Not assigned to a capability unit.

**Urban land-Edneyville complex (Ue).**—This complex consists of well-drained gravelly and loamy soils. Slopes range from 3 to 25 percent but are commonly 8 to 15 percent. The depth to bedrock is variable, depending on the amount of cut or fill, but ranges from 1 foot or 2 feet in deep cuts to more than 10 feet in other areas.

This complex is about 45 percent cut and fill land and 40 percent Edneyville soils. The soils are in a complex pattern, and it is impractical to map them separately. Making up the remaining percentage are Parker and other soils. In most places the soil or soil material is 15 to 20 percent angular pebbles, but in deep cuts angular coarse fragments as large as stones are more prevalent.

Permeability is moderate, and the available water capacity is moderate or low. Runoff is moderate to rapid, and the hazard of erosion is moderate to moderately severe. Not assigned to a capability unit.

**Urban land-Haledon complex (Uh).**—This complex consists of somewhat poorly drained and well-drained soils that have a high proportion of silt and fine sand. Slopes are commonly 3 to 8 percent but range to as much as 15 percent in a few areas. The soil material is more or less gravelly and cobbly glacial deposits of material derived mainly from red and brown shale and sandstone, traprock, and granitic gneiss. The depth to and the kind of bedrock are variable because of the thickness of the glacial deposits. Fractured red shale and basalt are extensive.

This complex is about 40 percent cut and fill land and a nearly equal percentage of Haledon soils. About 20 percent is Boonton, Holyoke, and other soils.

Depth to the water table is generally more than 10 feet. In areas where the fragipan has not been removed, a seasonally perched water table is on top of the fragipan within a depth of 2 feet. Permeability is slow to very slow in the fragipan. If this complex is used for community development, lateral seepage to foundations and to the surface on steeper slopes and in excavations is likely. Runoff is moderate to rapid, depending on slope. The hazard of erosion is moderate to severe, depending on slope. Not assigned to a capability unit.

**Urban land-Neshaminy complex (Uk).**—This complex consists of well-drained, gently sloping stony soils. Slopes commonly range from 3 to 8 percent. The soil material is mainly weathered traprock and some small thin fragments of brown shale and sandstone. Depth to bedrock is variable, depending on the amount of excavation or fill, but ranges from 1 foot to more than 10 feet.

This complex is about 40 percent Neshaminy soils and 40 percent soils that have been disturbed by the activities of man to the extent that the original soil profile no longer remains. The soils occur in a complex pattern, and they cannot be mapped separately. Most areas also include small areas of more sloping Neshaminy soils, soils that are similar to this Neshaminy soil but have a mottled subsoil, Penn soils, and Ellington loamy subsoil variants.

This complex is deep over a water table and has moderate permeability, rapid runoff, moderate to severe hazard of erosion, and high available water capacity. Practices are needed to help control runoff and erosion, particularly on deep cuts. Suitable practices include constructing diversions, seeding with adapted grasses to help control erosion, and constructing retaining walls to stabilize deep cuts. Not assigned to a capability unit.

**Urban land-Penn complex (Um).**—This complex consists of well-drained soils that are underlain by red shale bedrock. It is near the bottom of slopes of the Watchung Mountains. Slopes commonly range from 0 to 10 percent. The soil material is residuum weathered from the underlying shale bedrock.

This complex is about 40 percent cut and fill land and 40 percent Penn soils. The soils are in a complex pattern and cannot be mapped separately. Making up the

rest of the complex are small areas of Klinesville and Reaville soils.

On the sloping soils rapid runoff, a moderate hazard of erosion, and a moderate to low available water capacity are the major limitations. In construction areas, establishment of grass cover and diversion of long slopes by use of diversions or streets are beneficial in controlling runoff and erosion. Not assigned to a capability unit.

**Urban land-Preakness complex (Un).**—This complex consists of poorly drained, nearly level gravelly and sandy soils. The soil material is loose, relatively unweathered, stratified and sorted sandy and gravelly glacial outwash.

This complex is about 50 percent soils that have been disturbed by the activities of man to the extent that the original profile no longer remains and 40 percent Preakness soils. These soils occur in a complex pattern, and they cannot be mapped separately. Making up the remaining 10 percent are mainly Pompton and Riverhead soils.

Under natural drainage conditions the water table is at or near the surface for long periods during fall, winter, and spring. This complex is subject to flooding for long periods. In many places depth to the water table is increased, and the hazard of flooding is reduced by improved drainage or filling of low areas. Determination of the kind and degree of limitations to use of this complex requires onsite investigation. Not assigned to a capability unit.

**Urban land-Riverhead complex (Up).**—This complex consists of well-drained, nearly level to strongly sloping sandy and gravelly soils. It is mainly on undulating outwash terraces and plains in valleys, and in basins within and near the granitic highlands. Most areas are within the valleys of the Rockaway and Musconetcong River and in the basin formerly occupied by glacial Lake Passaic in the vicinity of Pompton Plains. Slopes range from 0 to 20 percent but are typically 5 to 12 percent. The underlying material is loose, unweathered, stratified and sorted sand and gravel outwash, mostly of granitic material that contains some shale, sandstone, quartzite, and conglomerate. Coarse fragments are mainly gravel and a few cobbles, but in places there are stones and boulders. Depth to a seasonally high water table is generally more than 10 feet.

This complex is about 55 percent soils that have been disturbed by man to the extent that the original profile no longer remains and 35 percent Riverhead soils. Making up the remaining percentage are areas of Otisville and Pompton soils.

Permeability is rapid, and runoff is moderate. If this complex is used for community development, practices are needed to control runoff and erosion. Using a grass cover and diversions in critical areas are suitable practices. Not assigned to a capability unit.

**Urban land-Rockaway complex, gently sloping and sloping (UrC).**—This complex consists of well-drained, gently sloping or sloping gravelly sandy loam soils. It is mainly in upland areas of intensive residential or industrial development in the vicinity of Rockaway, Dover, and Boonton. Slopes range from 0 to 15 percent.

ATTACHMENT H

# BUREAU OF FIELD OPERATIONS - SITE ASSESSMENT SECTION

## REPORT OF PHONE CALL

DATE November 4, 1993

TIME 10:00 A.M.

SITE NAME VIP Cleaners

LOCATION 89 Morris Street, Morristown, Morris County.

CALLER David Dibblee HSMS IV

PERSON CONTACTED Peter Austin

PHONE NO. [REDACTED]

AFFILIATION Owner, Block 4801 Lot 11, Morristown, Morris County

Personally Identifiable  
Information

removed by  
EPA PRS -  
8/9/13

SUMMARY OF CALL Mr Austin returned a call made earlier in the week.  
Permission to enter the V.I.P Cleaners site was granted verbally  
from Mr. Austin. A contact was given by the name David Kawash  
of the Michele Arnold Hair Salon. It was discussed that several  
tenants are at this location; a hair salon, cleaners, auto detailing,  
and a garden center. Mr Austin gave his home phone in Florida.  
(listed above) for further questions and information requests.

David E. Dibblee  
SIGNATURE

ATTACHMENT H1



ATTACHMENT I



State of New Jersey  
Department of Environmental Protection and Energy  
Division of Publicly Funded Site Remediation

CN 413  
Trenton, NJ 08625-0413  
Tel. # 609-984-2902  
Fax. # 609-633-2360

Jeanne M. Fox  
Acting Commissioner

Anthony J. Farro  
Director

TO: VIP Cleaners file  
FROM: David Dibblee, HSMS IV  
RE: December 13, 1993 Pre Sampling Assessment (PSA)

On December 13, 1993 David Dibblee and Andrew Cyr met with Sonny Din of VIP Cleaners at 89 Morris Street, Morristown, Morris County for an inspection of the facility and interview. Mr. Din explained that approximately 4 years ago he started his business, known as VIP cleaners, at 89 Morris Street. Prior to his business the store was a retail computer shop. Dry cleaning was conducted at the site until approximately 1 1/2 years ago when he ceased dry cleaning operations at the site. At this time he became a "drop" shop where clothes to be dry cleaned are dropped off and picked up by customers. Only "spot" cleaning of clothes is conducted at the site using very small amounts of dry cleaning chemicals. Mr. Din indicated that he believed that the entire site was at one time a dry cleaning business operated by current site owner, Peter Austin. (He believed the name to be Carolina Laundry)

An inspection of the space occupied by VIP Cleaners was conducted which found no floor drains, septic or other pathways to groundwater. The inspection then moved to the outside of the building. No drains, with the exception of a storm drain on the west side of the building, or pathways to ground water were discovered here. The entire site was paved.

Upon completing the exterior inspection we entered the shop located at the rear of the VIP Cleaners store. This was a car detailing and electronics store operated by Curt Bush. Mr. Bush was interviewed regarding his history at the site. He indicated that he has been at the site for approximately 6 years and prior to his occupancy a lawn mower repair shop operated in his shop space. Mr. Bush believed this business was at the site for only a short time, possibly only a couple of years. To his knowledge prior to the lawnmower shop being at the site, the entire site was known as Carolina Laundry or Cleaners. He also indicated that a small section of the building was used by Morristown Memorial Hospital as a cleaning shop for its linens etc. at the time the entire site was

a dry cleaning operation. Since the section of the building occupied by Mr. Bush contained garage bays it was asked if floor drains existed in these areas. He had indicated that there were floor drains in his garages but that he had these installed himself when he originally opened his business. At this time he displayed photographs of the renovations he had made to the building, including the floor drain installation. These drains are connected to the sanitary sewer.

The remaining shop at the rear of the building was a gardening shop which sold plants and garden supplies. The exterior of this building was inspected which did not reveal any suspect areas of concern. The inspectors left the site at 1100 hours.

ATTACHMENT J



**State of New Jersey**  
**Department of Environmental Protection and Energy**  
Division of Publicly Funded Site Remediation

CN 413  
Trenton, NJ 08625-0413  
Tel. # 609-984-2902  
Fax. # 609-633-2360

Jeanne M. Fox  
Acting Commissioner

Anthony J. Farro  
Director

The population residing within a 4-mile radius of the VIP Cleaners site was compiled from the EPA GEMS database and available population data from the 1990 census. For populations within a 1/2 mile of the site, the area for the respective distance interval was calculated in square miles and multiplied by the residents per square mile from the 1990 census.

0 - 1/4 mile:

$$0.25^2 \times 3.14 = 0.19625 \text{ sq. miles} \times 5,510 = 1,080$$

1/4 - 1/2 mile:

$$0.5^2 \times 3.14 = 0.785 - 0.19625 = 0.58875 \text{ sq. miles} \times 5,510 = 3,245$$

The remaining population data was taken from the EPA GEMS database for the respective distance intervals.

1/2 -	1	5,875
1 -	2	13,285
2 -	3	6,260
3 -	4	29,145

ATTACHMENT K

INDUSTRIAL CORROSION MANAGEMENT INC.  
1152 Route 10  
Randolph, NJ 07869  
Phone # (201) 584-0330

TASK IV  
NJDEPE-CLP FORMAT  
INORGANIC/ORGANIC SAMPLE DATA SUMMARY PACKAGE

VI062194  
SDG NO. 498

CONTRACT X-26174/A60084  
PROFESSIONAL LABORATORY ANALYTICAL  
SERVICES FOR NJDEPE

ANALYTICAL DATA PACKAGE FOR THE ANALYSIS OF  
NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION & ENERGY  
TRENTON, NEW JERSEY 08625

DIVISION: DPFSR

BUREAU: Site Assessment

CASE NAME: VI 062194

CASE #:

Note: This is a two sided form. Data Qualifiers on reverse side.

[illegible]

LABORATORY NAME: Industrial Corrosion Mgmt. Inc.

LOCATION: 1152 Route 10  
Randolph, NJ

NJDEPE CERTIFICATION No: 14116  
(IF APPLICABLE)

DATE SUBMITTED: 8/2/94

Paula K. Blaze  
LABORATORY QA OFFICER  
(PRINT)

(PRINT)  
Richard S. Levine  
LABORATORY MANAGER:  
(PRINT)

LABORATORY QA OFFICER:  
(SIGNATURE) *[Signature]*

(SIGNATURE) Richard J. Gurnea  
LABORATORY MANAGER:  
(SIGNATURE)

NUDEPE FORM A-1A (8/91)

ATTACHMENT K2



1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

498\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0841

Level: (low/med) LOW

Date Received: 06/24/94

% Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

74-87-3-----	Chloromethane	10.	U
74-83-9-----	Bromomethane	10.	U
75-01-4-----	Vinyl Chloride	10.	U
75-00-3-----	Chloroethane	10.	U
75-09-2-----	Methylene Chloride	10.	U
67-64-1-----	Acetone	10.	U
75-15-0-----	Carbon Disulfide	10.	U
75-35-4-----	1,1-Dichloroethene	10.	U
75-34-3-----	1,1-Dichloroethane	10.	U
540-59-0-----	1,2-Dichloroethene (total)	10.	U
67-66-3-----	Chloroform	10.	U
107-06-2-----	1,2-Dichloroethane	10.	U
78-93-3-----	2-Butanone	10.	U
71-55-6-----	1,1,1-Trichloroethane	10.	U
56-23-5-----	Carbon Tetrachloride	10.	U
75-27-4-----	Bromodichloromethane	10.	U
78-87-5-----	1,2-Dichloropropane	10.	U
10061-01-5-----	cis-1,3-Dichloropropene	10.	U
79-01-6-----	Trichloroethene	10.	U
124-48-1-----	Dibromochloromethane	10.	U
79-00-5-----	1,1,2-Trichloroethane	10.	U
71-43-2-----	Benzene	10.	U
10061-02-6-----	trans-1,3-Dichloropropene	10.	U
75-25-2-----	Bromoform	10.	U
108-10-1-----	4-Methyl-2-Pentanone	10.	U
591-78-6-----	2-Hexanone	10.	U
127-18-4-----	Tetrachloroethene	10.	U
79-34-5-----	1,1,2,2-Tetrachloroethane	10.	U
108-88-3-----	Toluene	10.	U
108-90-7-----	Chlorobenzene	10.	U
100-41-4-----	Ethylbenzene	10.	U
100-42-5-----	Styrene	10.	U
1330-20-7-----	Xylene (total)	10.	U

1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

498\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0841

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

498

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190939

Sample wt/vol: 1050.0 (g/mL) ML

Lab File ID: I2108

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N

pH: \_\_\_\_\_

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

108-95-2-----Phenol	10.	U
111-44-4-----bis(2-Chloroethyl)ether	10.	U
95-57-8-----2-Chlorophenol	10.	U
541-73-1-----1,3-Dichlorobenzene	10.	U
106-46-7-----1,4-Dichlorobenzene	10.	U
95-50-1-----1,2-Dichlorobenzene	10.	U
95-48-7-----2-Methylphenol	10.	U
108-60-1-----2,2'-oxybis(1-Chloropropane)	10.	U
106-44-5-----4-Methylphenol	10.	U
621-64-7-----N-Nitroso-di-n-propylamine	10.	U
67-72-1-----Hexachloroethane	10.	U
98-95-3-----Nitrobenzene	10.	U
78-59-1-----Isophorone	10.	U
88-75-5-----2-Nitrophenol	10.	U
105-67-9-----2,4-Dimethylphenol	10.	U
111-91-1-----bis(2-Chloroethoxy)methane	10.	U
120-83-2-----2,4-Dichlorophenol	10.	U
120-82-1-----1,2,4-Trichlorobenzene	10.	U
91-20-3-----Naphthalene	10.	U
106-47-8-----4-Chloroaniline	10.	U
87-68-3-----Hexachlorobutadiene	10.	U
59-50-7-----4-Chloro-3-methylphenol	10.	U
91-57-6-----2-Methylnaphthalene	10.	U
77-47-4-----Hexachlorocyclopentadiene	10.	U
88-06-2-----2,4,6-Trichlorophenol	10.	U
95-95-4-----2,4,5-Trichlorophenol	24.	U
91-58-7-----2-Chloronaphthalene	10.	U
88-74-4-----2-Nitroaniline	24.	U
131-11-3-----Dimethylphthalate	10.	U
208-96-8-----Acenaphthylene	10.	U
606-20-2-----2,6-Dinitrotoluene	10.	U
99-09-2-----3-Nitroaniline	24.	U
83-32-9-----Acenaphthene	10.	U

1C  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

498

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190939

Sample wt/vol: 1050.0 (g/mL) ML

Lab File ID: I2108

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: decanted: (Y/N)

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Section Volume: 2.0 (uL)

Dilution Factor: 1.0

PC Cleanup: (Y/N) N

pH:

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

51-28-5-----2,4-Dinitrophenol	24.	U
100-02-7-----4-Nitrophenol	24.	U
132-64-9-----Dibenzofuran	10.	U
121-14-2-----2,4-Dinitrotoluene	10.	U
84-66-2-----Diethylphthalate	10.	U
7005-72-3-----4-Chlorophenyl-phenylether	10.	U
86-73-7-----Fluorene	10.	U
100-01-6-----4-Nitroaniline	24.	U
534-52-1-----4,6-Dinitro-2-methylphenol	24.	U
86-30-6-----N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----4-Bromophenyl-phenylether	10.	U
118-74-1-----Hexachlorobenzene	10.	U
87-86-5-----Pentachlorophenol	24.	U
85-01-8-----Phenanthrene	10.	U
120-12-7-----Anthracene	10.	U
86-74-8-----Carbazole	10.	U
84-74-2-----Di-n-butylphthalate	10.	U
206-44-0-----Fluoranthene	10.	U
129-00-0-----Pyrene	10.	U
85-68-7-----Butylbenzylphthalate	10.	U
91-94-1-----3,3'-Dichlorobenzidine	10.	U
56-55-3-----Benzo(a)anthracene	10.	U
218-01-9-----Chrysene	10.	U
117-81-7-----bis(2-Ethylhexyl)phthalate	10.	U
117-84-0-----Di-n-octylphthalate	10.	U
205-99-2-----Benzo(b)fluoranthene	10.	U
207-08-9-----Benzo(k)fluoranthene	10.	U
50-32-8-----Benzo(a)pyrene	10.	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----Dibenz(a,h)anthracene	10.	U
191-24-2-----Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

3/90

1F  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

498

Sample Name: ICM, Inc.

Contract: A60084

Sample Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190939

Sample wt/vol: 1050.0 (g/mL) ML

Lab File ID: I2108

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH: \_\_\_\_\_

Number TICs found: 3

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. - -	UNKNOWN	11.23	2.	BJ
2. - -	UNKNOWN	12.71	5.	BJ
3. - -	UNKNOWN	16.48	3.	J
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

## PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

498

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDS No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190939

Sample wt/vol: 1040.0 (g/mL) ML

Lab File ID: 01249

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Received: 06/24/94

Extraction: (SepF/Cont/Sonc) SEPF

Date Extracted: 06/29/94

Concentrated Extract Volume: 10000.0 (uL)

Date Analyzed: 07/19/94

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

SPC Cleanup: (Y/N) N

pH: 6.8

Sulfur Cleanup: (Y/N) N

## CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/L

Q

319-84-6	alpha-BHC	.048	U
319-85-7	beta-BHC	.048	U
319-86-8	delta-BHC	.048	U
58-89-9	gamma-BHC (Lindane)	.048	U
76-44-8	Heptachlor	.048	U
309-00-2	Aldrin	.048	U
1024-57-3	Heptachlor epoxide	.048	U
959-98-8	Endosulfan I	.048	U
60-57-1	Dieldrin	.096	U
72-55-9	4,4'-DDE	.096	U
72-20-8	Endrin	.096	U
33213-65-9	Endosulfan II	.096	U
72-54-8	4,4'-DDD	.096	U
1031-07-8	Endosulfan Sulfate	.096	U
50-29-3	4,4'-DDT	.096	U
72-43-5	Methoxychlor	.48	U
53494-70-5	Endrin ketone	.096	U
7421-93-4	Endrin aldehyde	.096	U
5103-71-9	alpha-Chlordane	.048	U
5103-74-2	gamma-Chlordane	.048	U
8001-35-2	Toxaphene	4.8	U
12674-11-2	Aroclor-1016	.96	U
11104-28-2	Aroclor-1221	1.9	U
11141-16-5	Aroclor-1232	.96	U
53469-21-9	Aroclor-1242	.96	U
12672-29-6	Aroclor-1248	.96	U
11097-69-1	Aroclor-1254	.96	U
11096-82-5	Aroclor-1260	.96	U

FORM I PEST

3/90

1  
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

498

b Name: ICM \_\_\_\_\_ Contract: A60084 \_\_\_\_\_

Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS No.: \_\_\_\_\_ SDG No.: 498 \_\_\_\_\_

Matrix (soil/water): WATER

Lab Sample ID: 190939 \_\_\_\_\_

Level (low/med): LOW \_\_\_\_\_

Date Received: 06/24/94

Solids: \_\_\_\_\_ 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L \_\_\_\_\_

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	5070	-		P
7440-36-0	Antimony	29.8	U		P
7440-38-2	Arsenic	1.9	B	W	F
7440-39-3	Barium	119	B		P
7440-41-7	Beryllium	0.30	U		P
7440-43-9	Cadmium	1.9	U		P
7440-70-2	Calcium	112000	-		P
7440-47-3	Chromium	10.2	-		P
7440-48-4	Cobalt	4.6	U		P
7440-50-8	Copper	18.8	B		P
7439-89-6	Iron	10700	-		P
7439-92-1	Lead	5.9	-		F
7439-95-4	Magnesium	49500	-		P
7439-96-5	Manganese	260	-		P
7439-97-6	Mercury	0.10	U		CV
7440-02-0	Nickel	8.1	U		P
7440-09-7	Potassium	3850	B		P
7782-49-2	Selenium	1.4	U	W	F
7440-22-4	Silver	2.7	U		P
7440-23-5	Sodium	68800	-		P
7440-28-0	Thallium	2.0	B	W	F
7440-62-2	Vanadium	23.4	B		P
7440-66-6	Zinc	47.3	-		P
	Cyanide	19.6	-		AS

Color Before: WHITE \_\_\_\_\_

Clarity Before: CLOUDY

Texture: \_\_\_\_\_

Color After: COLORLESS

Clarity After: CLEAR \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

SEE CASE NARRATIVE FOR CYANIDE COLOR/CLARITY INFORMATION.

SAMPLE CONTAINS SOME SEDIMENT.

FORM I - IN

ILMO3.0

1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

499\_\_

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/Vol: 5.000 (g/mL) ML

Lab File ID: C0842

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L Q

74-87-3	Chloromethane	10.	U
74-83-9	Bromomethane	10.	U
75-01-4	Vinyl Chloride	10.	U
75-00-3	Chloroethane	10.	U
75-09-2	Methylene Chloride	10.	U
67-64-1	Acetone	10.	U
75-15-0	Carbon Disulfide	10.	U
75-35-4	1,1-Dichloroethene	10.	U
75-34-3	1,1-Dichloroethane	10.	U
540-59-0	1,2-Dichloroethene (total)	10.	U
67-66-3	Chloroform	10.	U
107-06-2	1,2-Dichloroethane	10.	U
78-93-3	2-Butanone	10.	U
71-55-6	1,1,1-Trichloroethane	10.	U
56-23-5	Carbon Tetrachloride	10.	U
75-27-4	Bromodichloromethane	10.	U
78-87-5	1,2-Dichloropropane	10.	U
10061-01-5	cis-1,3-Dichloropropene	10.	U
79-01-6	Trichloroethene	10.	U
124-48-1	Dibromochloromethane	10.	U
79-00-5	1,1,2-Trichloroethane	10.	U
71-43-2	Benzene	10.	U
10061-02-6	trans-1,3-Dichloropropene	10.	U
75-25-2	Bromoform	10.	U
108-10-1	4-Methyl-2-Pentanone	10.	U
591-78-6	2-Hexanone	10.	U
127-18-4	Tetrachloroethene	30.	
79-34-5	1,1,2,2-Tetrachloroethane	10.	U
108-88-3	Toluene	10.	U
108-90-7	Chlorobenzene	10.	U
100-41-4	Ethylbenzene	10.	U
100-42-5	Styrene	10.	U
1330-20-7	Xylene (total)	10.	U



1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

499\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0842

Level: (low/med) LOW

Date Received: 06/24/94

% Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM I VOA-TIC

3/90

1B  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

499\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID: 190940

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2109

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH: \_\_\_\_\_

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

108-95-2-----Phenol	10.	U
111-44-4-----bis(2-Chloroethyl) ether	10.	U
95-57-8-----2-Chlorophenol	10.	U
541-73-1-----1,3-Dichlorobenzene	10.	U
106-46-7-----1,4-Dichlorobenzene	10.	U
95-50-1-----1,2-Dichlorobenzene	10.	U
95-48-7-----2-Methylphenol	10.	U
108-60-1-----2,2'-oxybis(1-Chloropropane)	10.	U
106-44-5-----4-Methylphenol	10.	U
621-64-7-----N-Nitroso-di-n-propylamine	10.	U
67-72-1-----Hexachloroethane	10.	U
98-95-3-----Nitrobenzene	10.	U
78-59-1-----Isophorone	10.	U
88-75-5-----2-Nitrophenol	10.	U
105-67-9-----2,4-Dimethylphenol	10.	U
111-91-1-----bis(2-Chloroethoxy) methane	10.	U
120-83-2-----2,4-Dichlorophenol	10.	U
120-82-1-----1,2,4-Trichlorobenzene	10.	U
91-20-3-----Naphthalene	10.	U
106-47-8-----4-Chloroaniline	10.	U
87-68-3-----Hexachlorobutadiene	10.	U
59-50-7-----4-Chloro-3-methylphenol	10.	U
91-57-6-----2-Methylnaphthalene	10.	U
77-47-4-----Hexachlorocyclopentadiene	10.	U
88-06-2-----2,4,6-Trichlorophenol	10.	U
95-95-4-----2,4,5-Trichlorophenol	25.	U
91-58-7-----2-Chloronaphthalene	10.	U
88-74-4-----2-Nitroaniline	25.	U
131-11-3-----Dimethylphthalate	10.	U
208-96-8-----Acenaphthylene	10.	U
606-20-2-----2,6-Dinitrotoluene	10.	U
99-09-2-----3-Nitroaniline	25.	U
83-32-9-----Acenaphthene	10.	U

FORM I SV-1

3/90

1C  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

499

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190940

Conc: (wt/vol): 1000.0 (g/mL) ML

Lab File ID: I2109

Level: (low/med) LOW

Date Received: 06/24/94

Preparation: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N

pH: \_\_\_\_\_

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

51-28-5-----	2,4-Dinitrophenol	25.	U
100-02-7-----	4-Nitrophenol	25.	U
132-64-9-----	Dibenzofuran	10.	U
121-14-2-----	2,4-Dinitrotoluene	10.	U
84-66-2-----	Diethylphthalate	.8	BJ
7005-72-3-----	4-Chlorophenyl-phenylether	10.	U
86-73-7-----	Fluorene	10.	U
100-01-6-----	4-Nitroaniline	25.	U
534-52-1-----	4,6-Dinitro-2-methylphenol	25.	U
86-30-6-----	N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----	4-Bromophenyl-phenylether	10.	U
118-74-1-----	Hexachlorobenzene	10.	U
87-86-5-----	Pentachlorophenol	25.	U
85-01-8-----	Phenanthrene	10.	U
120-12-7-----	Anthracene	10.	U
86-74-8-----	Carbazole	10.	U
84-74-2-----	Di-n-butylphthalate	10.	U
206-44-0-----	Fluoranthene	10.	U
129-00-0-----	Pyrene	10.	U
85-68-7-----	Butylbenzylphthalate	10.	U
91-94-1-----	3,3'-Dichlorobenzidine	10.	U
56-55-3-----	Benzo(a)anthracene	10.	U
218-01-9-----	Chrysene	10.	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10.	U
117-84-0-----	Di-n-octylphthalate	10.	U
205-99-2-----	Benzo(b)fluoranthene	10.	U
207-08-9-----	Benzo(k)fluoranthene	10.	U
50-32-8-----	Benzo(a)pyrene	10.	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----	Dibenz(a,h)anthracene	10.	U
191-24-2-----	Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

3/90

1F  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

499

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190940

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2109

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

GC Cleanup: (Y/N) N pH: \_\_\_\_\_

Number TICs found: 10

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 127-18-4	TETRACHLORO-ETHENE	3.06	5.	J
2. - -	UNKNOWN	9.81	3.	J
3. - -	UNKNOWN	10.50	2.	J
4. - -	UNKNOWN	11.24	2.	BJ
5. 65-85-0	BENZOIC ACID	11.47	10.	J
6. - -	UNKNOWN	12.50	6.	J
7. - -	UNKNOWN	12.89	20.	BJ
8. - -	UNKNOWN	12.95	4.	J
9. 143-07-7	DODECANOIC ACID	16.53	8.	J
10. 134-62-3	DIETHYL METHYL BENZAMIDE	16.65	4.	J
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM I SV-TIC

3/90

# PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: ICM, Inc.

Contract: A60084

499

Lab Code: ICM

Case No.:

SAS No.:

SDS No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190940

Sample wt/vol: 1050.0 (g/mL) ML

Lab File ID: 01250

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Received: 06/24/94

Extraction: (SepF/Cont/Sonc) SEPF

Date Extracted: 06/29/94

Concentrated Extract Volume: 10000.0 (uL)

Date Analyzed: 07/19/94

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

PC Cleanup: (Y/N) N

pH: 6.8

Sulfur Cleanup: (Y/N) N

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) ug/L

Q

319-84-6	alpha-BHC	.048	U
319-85-7	beta-BHC	.048	U
319-86-8	delta-BHC	.048	U
58-89-9	gamma-BHC (Lindane)	.048	U
76-44-8	Heptachlor	.048	U
309-00-2	Aldrin	.048	U
1024-57-3	Heptachlor epoxide	.048	U
959-98-8	Endosulfan I	.048	U
60-57-1	Dieldrin	.095	U
72-55-9	4,4'-DDE	.095	U
72-20-8	Endrin	.095	U
33213-65-9	Endosulfan II	.095	U
72-54-8	4,4'-DDD	.095	U
1031-07-8	Endosulfan Sulfate	.095	U
50-29-3	4,4'-DDT	.095	U
72-43-5	Methoxychlor	.48	U
53494-70-5	Endrin ketone	.095	U
7421-93-4	Endrin aldehyde	.095	U
5103-71-9	alpha-Chlordane	.048	U
5103-74-2	gamma-Chlordane	.048	U
8001-35-2	Toxaphene	4.8	U
12674-11-2	Aroclor-1016	.95	U
11104-28-2	Aroclor-1221	1.9	U
11141-16-5	Aroclor-1232	.95	U
53469-21-9	Aroclor-1242	.95	U
12672-29-6	Aroclor-1248	.95	U
11097-69-1	Aroclor-1254	.95	U
11096-82-5	Aroclor-1260	.95	U

FORM 1 PEST

3/90

1  
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

499

Name: ICM

Contract: A60084

Code: \_\_\_\_\_

Case No.: \_\_\_\_\_

SAS No.: \_\_\_\_\_

SDG No.: 498

Matrix (soil/water): WATER

Lab Sample ID: 190940

Level (low/med): LOW

Date Received: 06/24/94

Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	114000	—	—	P
7440-36-0	Antimony	29.8	U	—	P
7440-38-2	Arsenic	5.6	B	W	F
7440-39-3	Barium	801	—	—	P
7440-41-7	Beryllium	7.3	—	—	P
7440-43-9	Cadmium	1.9	U	—	P
7440-70-2	Calcium	138000	—	—	P
7440-47-3	Chromium	208	—	—	P
7440-48-4	Cobalt	92.9	—	—	P
7440-50-8	Copper	312	—	—	P
7439-89-6	Iron	215000	—	—	P
7439-92-1	Lead	115	—	—	F
7439-95-4	Magnesium	75600	—	—	P
7439-96-5	Manganese	6110	—	—	P
7439-97-6	Mercury	0.10	U	—	CV
7440-02-0	Nickel	961	—	—	P
7440-09-7	Potassium	14900	—	—	P
7782-49-2	Selenium	8.5	—	S	F
7440-22-4	Silver	2.7	U	—	P
7440-23-5	Sodium	108000	—	—	P
7440-28-0	Thallium	3.1	B	W	F
7440-62-2	Vanadium	361	—	—	P
7440-66-6	Zinc	745	—	—	P
	Cyanide	10.0	U	—	AS

Color Before: LT\_BROWN

Clarity Before: CLOUDY

Texture: \_\_\_\_\_

Color After: COLORLESS

Clarity After: CLEAR

Artifacts: \_\_\_\_\_

Comments:

SEE CASE NARRATIVE FOR CYANIDE COLOR/CLARITY INFORMATION.

SAMPLE CONTAINS SOME SEDIMENT.

FORM I - IN

ILMO3.0

1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: ICM, Inc.

Contract: A60084

501\_\_

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0836

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L Q

74-87-3	Chloromethane	10.	U
74-83-9	Bromomethane	10.	U
75-01-4	Vinyl Chloride	120.	
75-00-3	Chloroethane	6.	J
75-09-2	Methylene Chloride	10.	U
67-64-1	Acetone	10.	U
75-15-0	Carbon Disulfide	10.	U
75-35-4	1,1-Dichloroethene	2.	J
75-34-3	1,1-Dichloroethane	10.	U
540-59-0	1,2-Dichloroethene (total)	820.	E
67-66-3	Chloroform	10.	U
107-06-2	1,2-Dichloroethane	10.	U
78-93-3	2-Butanone	10.	U
71-55-6	1,1,1-Trichloroethane	10.	U
56-23-5	Carbon Tetrachloride	10.	U
75-27-4	Bromodichloromethane	10.	U
78-87-5	1,2-Dichloropropane	10.	U
10061-01-5	cis-1,3-Dichloropropene	10.	U
79-01-6	Trichloroethene	430.	E
124-48-1	Dibromochloromethane	10.	U
79-00-5	1,1,2-Trichloroethane	10.	U
71-43-2	Benzene	10.	U
10061-02-6	trans-1,3-Dichloropropene	10.	U
75-25-2	Bromoform	10.	U
108-10-1	4-Methyl-2-Pentanone	10.	U
591-78-6	2-Hexanone	10.	U
127-18-4	Tetrachloroethene	1700.	E
79-34-5	1,1,2,2-Tetrachloroethane	10.	U
108-88-3	Toluene	10.	U
108-90-7	Chlorobenzene	10.	U
100-41-4	Ethylbenzene	10.	U
100-42-5	Styrene	10.	U
1330-20-7	Xylene (total)	10.	U

1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

501\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0836

Level: (low/med) LOW

Date Received: 06/24/94

% Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM I VOA-TIC

3/90



1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

501\_\_ DL

Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: .250 (g/mL) ML

Lab File ID: C0844

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 20.0

1 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

74-87-3	Chloromethane	200.	U	
74-83-9	Bromomethane	200.	U	
75-01-4	Vinyl Chloride	200.	U	
75-00-3	Chloroethane	200.	U	
75-09-2	Methylene Chloride	200.	U	
67-64-1	Acetone	200.	U	
75-15-0	Carbon Disulfide	200.	U	
75-35-4	1,1-Dichloroethene	200.	U	
75-34-3	1,1-Dichloroethane	200.	U	
540-59-0	1,2-Dichloroethene (total)	730.		D
67-66-3	Chloroform	200.	U	
107-06-2	1,2-Dichloroethane	200.	U	
78-93-3	2-Butanone	200.	U	
71-55-6	1,1,1-Trichloroethane	200.	U	
56-23-5	Carbon Tetrachloride	200.	U	
75-27-4	Bromodichloromethane	200.	U	
78-87-5	1,2-Dichloropropane	200.	U	
10061-01-5	cis-1,3-Dichloropropene	200.	U	
79-01-6	Trichloroethene	390.		D
124-48-1	Dibromochloromethane	200.	U	
79-00-5	1,1,2-Trichloroethane	200.	U	
71-43-2	Benzene	200.	U	
10061-02-6	trans-1,3-Dichloropropene	200.	U	
75-25-2	Bromoform	200.	U	
108-10-1	4-Methyl-2-Pentanone	200.	U	
591-78-6	2-Hexanone	200.	U	
127-18-4	Tetrachloroethene	2600.		D
79-34-5	1,1,2,2-Tetrachloroethane	200.	U	
108-88-3	Toluene	200.	U	
108-90-7	Chlorobenzene	200.	U	
100-41-4	Ethylbenzene	200.	U	
100-42-5	Styrene	200.	U	
1330-20-7	Xylene (total)	200.	U	

VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

501\_\_ DL

Company Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: .250 (g/mL) ML

Lab File ID: C0844

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 20.0

1 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

501\_\_

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID: 190941

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2110

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH: \_\_\_\_\_

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

108-95-2-----Phenol	10.	U
111-44-4-----bis(2-Chloroethyl) ether	10.	U
95-57-8-----2-Chlorophenol	10.	U
541-73-1-----1,3-Dichlorobenzene	10.	U
106-46-7-----1,4-Dichlorobenzene	10.	U
95-50-1-----1,2-Dichlorobenzene	10.	U
95-48-7-----2-Methylphenol	10.	U
108-60-1-----2,2'-oxybis(1-Chloropropane)	10.	U
106-44-5-----4-Methylphenol	10.	U
621-64-7-----N-Nitroso-di-n-propylamine	10.	U
67-72-1-----Hexachloroethane	10.	U
98-95-3-----Nitrobenzene	10.	U
78-59-1-----Isophorone	10.	U
88-75-5-----2-Nitrophenol	10.	U
105-67-9-----2,4-Dimethylphenol	10.	U
111-91-1-----bis(2-Chloroethoxy) methane	10.	U
120-83-2-----2,4-Dichlorophenol	10.	U
120-82-1-----1,2,4-Trichlorobenzene	10.	U
91-20-3-----Naphthalene	10.	U
106-47-8-----4-Chloroaniline	10.	U
87-68-3-----Hexachlorobutadiene	10.	U
59-50-7-----4-Chloro-3-methylphenol	10.	U
91-57-6-----2-Methylnaphthalene	10.	U
77-47-4-----Hexachlorocyclopentadiene	10.	U
88-06-2-----2,4,6-Trichlorophenol	10.	U
95-95-4-----2,4,5-Trichlorophenol	25.	U
91-58-7-----2-Chloronaphthalene	10.	U
88-74-4-----2-Nitroaniline	25.	U
131-11-3-----Dimethylphthalate	10.	U
208-96-8-----Acenaphthylene	10.	U
606-20-2-----2,6-Dinitrotoluene	10.	U
99-09-2-----3-Nitroaniline	25.	U
83-32-9-----Acenaphthene	10.	U

1C  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

501\_\_

Lab Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID: 190941

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2110

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N)\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/20/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH: \_\_\_\_\_

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

51-28-5-----2,4-Dinitrophenol	25.	U
100-02-7-----4-Nitrophenol	25.	U
132-64-9-----Dibenzofuran	10.	U
121-14-2-----2,4-Dinitrotoluene	10.	U
84-66-2-----Diethylphthalate	10.	U
7005-72-3-----4-Chlorophenyl-phenylether	10.	U
86-73-7-----Fluorene	10.	U
100-01-6-----4-Nitroaniline	25.	U
534-52-1-----4,6-Dinitro-2-methylphenol	25.	U
86-30-6-----N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----4-Bromophenyl-phenylether	10.	U
118-74-1-----Hexachlorobenzene	10.	U
87-86-5-----Pentachlorophenol	25.	U
85-01-8-----Phenanthrene	10.	U
120-12-7-----Anthracene	10.	U
86-74-8-----Carbazole	10.	U
84-74-2-----Di-n-butylphthalate	10.	U
206-44-0-----Fluoranthene	10.	U
129-00-0-----Pyrene	10.	U
85-68-7-----Butylbenzylphthalate	10.	U
91-94-1-----3,3'-Dichlorobenzidine	10.	U
56-55-3-----Benzo(a)anthracene	10.	U
218-01-9-----Chrysene	10.	U
117-81-7-----bis(2-Ethylhexyl)phthalate	3.	J
117-84-0-----Di-n-octylphthalate	10.	U
205-99-2-----Benzo(b)fluoranthene	10.	U
207-08-9-----Benzo(k)fluoranthene	10.	U
50-32-8-----Benzo(a)pyrene	10.	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----Dibenz(a,h)anthracene	10.	U
191-24-2-----Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

3/90

## EPA SAMPLE NO.

501

Contract: A60084

Case No. :

SAS No.:

SDG No.: 498:

Lab Sample ID: 190941

Lab File ID: I2110

Date Received: 06/24/94

Date Extracted: 06/29/94

Date Analyzed: 07/20/94

Dilution Factor: 1.0

pH: \_\_\_\_\_

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

FORM I SV-TIC

3/90

## PESTICIDE ORGANICS ANALYSIS DATA SHEET

LPH SAMPLE NO.

501

Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDS No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190941

Sample Wt/vol: 1030.0 (g/mL) ML

Lab File ID: 01251

Moisture: decanted: (Y/N)

Date Received: 06/24/94

Extraction: (Sept/Cont/Sonc) SEPF

Date Extracted: 06/29/94

Concentrated Extract Volume: 10000.0 (uL)

Date Analyzed: 07/19/94

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

GPC Cleanup: (Y/N) N

pH: 6.9

Sulfur Cleanup: (Y/N) N

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

319-84-6	alpha-BHC	.049	U
319-85-7	beta-BHC	.049	U
319-86-8	delta-BHC	.049	U
58-89-9	gamma-BHC (Lindane)	.049	U
76-44-8	Heptachlor	.049	U
309-00-2	Aldrin	.049	U
1024-57-3	Heptachlor epoxide	.049	U
959-98-8	Endosulfan I	.049	U
60-57-1	Dieldrin	.097	U
72-55-9	4,4'-DDE	.097	U
72-20-8	Endrin	.097	U
33213-65-9	Endosulfan II	.097	U
72-54-8	4,4'-DDD	.097	U
1031-07-8	Endosulfan Sulfate	.097	U
50-29-3	4,4'-DDT	.097	U
72-43-5	Methoxychlor	.49	U
53494-70-5	Endrin ketone	.097	U
7421-93-4	Endrin aldehyde	.097	U
5103-71-9	alpha-Chlordane	.049	U
5103-74-2	gamma-Chlordane	.049	U
8001-35-2	Toxaphene	4.9	U
12674-11-2	Aroclor-1016	.97	U
11104-28-2	Aroclor-1221	1.9	U
11141-16-5	Aroclor-1232	.97	U
53469-21-9	Aroclor-1242	.97	U
12672-29-6	Aroclor-1248	.97	U
11097-69-1	Aroclor-1254	.97	U
11096-82-5	Aroclor-1260	.97	U

FORM I PEST

3/90

1  
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

501

Name: ICM \_\_\_\_\_ Contract: A60084 \_\_\_\_\_

Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS No.: \_\_\_\_\_ SDG No.: 498 \_\_\_\_\_

Matrix (soil/water): WATER

Lab Sample ID: 190941 \_\_\_\_\_

pH (low/med): LOW \_\_\_\_\_

Date Received: 06/24/94

Solids: \_\_\_\_\_ 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L \_\_\_\_\_

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	724	—	—	P
7440-36-0	Antimony	29.8	U	—	P
7440-38-2	Arsenic	1.6	U	—	F
7440-39-3	Barium	181	B	—	P
7440-41-7	Beryllium	0.30	U	—	P
7440-43-9	Cadmium	2.5	B	—	P
7440-70-2	Calcium	94100	—	—	P
7440-47-3	Chromium	2.8	U	—	P
7440-48-4	Cobalt	4.6	U	—	P
7440-50-8	Copper	4.5	B	—	P
7439-89-6	Iron	2190	—	—	P
7439-92-1	Lead	1.8	B	—	F
7439-95-4	Magnesium	33400	—	—	P
7439-96-5	Manganese	724	—	—	P
7439-97-6	Mercury	0.10	U	—	CV
7440-02-0	Nickel	8.1	U	—	P
7440-09-7	Potassium	11600	—	—	P
7782-49-2	Selenium	1.4	U	—	F
7440-22-4	Silver	2.7	U	—	P
7440-23-5	Sodium	50600	—	—	P
7440-28-0	Thallium	1.6	U	—	F
7440-62-2	Vanadium	4.9	B	—	P
7440-66-6	Zinc	37.0	—	—	P
	Cyanide	10.0	U	—	AS

Color Before: COLORLESS Clarity Before: CLEAR Texture: \_\_\_\_\_

Color After: COLORLESS Clarity After: CLEAR Artifacts: \_\_\_\_\_

Comments:

SEE CASE NARRATIVE FOR CYANIDE COLOR/CLARITY INFORMATION. \_\_\_\_\_  
SAMPLE CONTAINS SOME SEDIMENT. \_\_\_\_\_

FORM I - IN

ILMO3.0

1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: ICM, Inc.

Contract: A60084

502\_\_

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0839

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

1 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

74-87-3	Chloromethane	10.	U
74-83-9	Bromomethane	10.	U
75-01-4	Vinyl Chloride	120.	
75-00-3	Chloroethane	7.	J
75-09-2	Methylene Chloride	10.	U
67-64-1	Acetone	10.	U
75-15-0	Carbon Disulfide	10.	U
75-35-4	1,1-Dichloroethene	10.	U
75-34-3	1,1-Dichloroethane	2.	J
540-59-0	1,2-Dichloroethene (total)	10.	U
67-66-3	Chloroform	800.	E
107-06-2	1,2-Dichloroethane	1.	J
78-93-3	2-Butanone	10.	U
71-55-6	1,1,1-Trichloroethane	10.	U
56-23-5	Carbon Tetrachloride	10.	U
75-27-4	Bromodichloromethane	10.	U
78-87-5	1,2-Dichloropropane	10.	U
10061-01-5	cis-1,3-Dichloropropene	2.	J
79-01-6	Trichloroethene	10.	U
124-48-1	Dibromochloromethane	430.	E
79-00-5	1,1,2-Trichloroethane	10.	U
71-43-2	Benzene	10.	U
10061-02-6	trans-1,3-Dichloropropene	10.	U
75-25-2	Bromoform	10.	U
108-10-1	4-Methyl-2-Pentanone	10.	U
591-78-6	2-Hexanone	10.	U
127-18-4	Tetrachloroethene	10.	U
79-34-5	1,1,2,2-Tetrachloroethane	1700.	E
108-88-3	Toluene	10.	U
108-90-7	Chlorobenzene	10.	U
100-41-4	Ethylbenzene	10.	U
100-42-5	Styrene	10.	U
1330-20-7	Xylene (total)	10.	U



VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

502\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0839

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

502\_\_ DL

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: .250 (g/mL) ML

Lab File ID: C0843

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 20.0

11 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

74-87-3	Chloromethane	200.	U
74-83-9	Bromomethane	200.	U
75-01-4	Vinyl Chloride	200.	U
75-00-3	Chloroethane	200.	U
75-09-2	Methylene Chloride	200.	U
67-64-1	Acetone	200.	U
75-15-0	Carbon Disulfide	200.	U
75-35-4	1,1-Dichloroethene	200.	U
75-34-3	1,1-Dichloroethane	200.	U
540-59-0	1,2-Dichloroethene (total)	820.	D
67-66-3	Chloroform	200.	U
107-06-2	1,2-Dichloroethane	200.	U
78-93-3	2-Butanone	200.	U
71-55-6	1,1,1-Trichloroethane	200.	U
56-23-5	Carbon Tetrachloride	200.	U
75-27-4	Bromodichloromethane	200.	U
78-87-5	1,2-Dichloropropane	200.	U
10061-01-5	cis-1,3-Dichloropropene	200.	U
79-01-6	Trichloroethene	420.	D
124-48-1	Dibromochloromethane	200.	U
79-00-5	1,1,2-Trichloroethane	200.	U
71-43-2	Benzene	200.	U
10061-02-6	trans-1,3-Dichloropropene	200.	U
75-25-2	Bromoform	200.	U
108-10-1	4-Methyl-2-Pentanone	200.	U
591-78-6	2-Hexanone	200.	U
127-18-4	Tetrachloroethene	3000.	D
79-34-5	1,1,2,2-Tetrachloroethane	200.	U
108-88-3	Toluene	200.	U
108-90-7	Chlorobenzene	200.	U
100-41-4	Ethylbenzene	200.	U
100-42-5	Styrene	200.	U
1330-20-7	Xylene (total)	200.	U

1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

502\_\_ DL

Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: .250 (g/mL) ML

Lab File ID: C0843

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 20.0

Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

502

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498

ix: (soil/water) WATER

Lab Sample ID: 190942

ple wt/vol: 1030.0 (g/mL) ML

Lab File ID: I2119

l: (low/med) LOW

Date Received: 06/24/94

oisture: decanted: (Y/N)

Date Extracted: 06/29/94

entrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

ection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

108-95-2-----Phenol	10.	U
111-44-4-----bis(2-Chloroethyl) ether	10.	U
95-57-8-----2-Chlorophenol	10.	U
541-73-1-----1,3-Dichlorobenzene	10.	U
106-46-7-----1,4-Dichlorobenzene	10.	U
95-50-1-----1,2-Dichlorobenzene	10.	U
95-48-7-----2-Methylphenol	10.	U
108-60-1-----2,2'-oxybis(1-Chloropropane)	10.	U
106-44-5-----4-Methylphenol	10.	U
621-64-7-----N-Nitroso-di-n-propylamine	10.	U
67-72-1-----Hexachloroethane	10.	U
98-95-3-----Nitrobenzene	10.	U
78-59-1-----Isophorone	10.	U
88-75-5-----2-Nitrophenol	10.	U
105-67-9-----2,4-Dimethylphenol	10.	U
111-91-1-----bis(2-Chloroethoxy)methane	10.	U
120-83-2-----2,4-Dichlorophenol	10.	U
120-82-1-----1,2,4-Trichlorobenzene	10.	U
91-20-3-----Naphthalene	10.	U
106-47-8-----4-Chloroaniline	10.	U
87-68-3-----Hexachlorobutadiene	10.	U
59-50-7-----4-Chloro-3-methylphenol	10.	U
91-57-6-----2-Methylnaphthalene	10.	U
77-47-4-----Hexachlorocyclopentadiene	10.	U
88-06-2-----2,4,6-Trichlorophenol	10.	U
95-95-4-----2,4,5-Trichlorophenol	24.	U
91-58-7-----2-Chloronaphthalene	10.	U
88-74-4-----2-Nitroaniline	24.	U
131-11-3-----Dimethylphthalate	10.	U
208-96-8-----Acenaphthylene	10.	U
606-20-2-----2,6-Dinitrotoluene	10.	U
99-09-2-----3-Nitroaniline	24.	U
83-32-9-----Acenaphthene	10.	U

1C  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

502

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190942

Sample wt/vol: 1030.0 (g/mL) ML

Lab File ID: I2119

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

GPC Cleanup: (Y/N) N

pH: \_\_\_\_\_

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

51-28-5-----	2,4-Dinitrophenol	24.	U
100-02-7-----	4-Nitrophenol	24.	U
132-64-9-----	Dibenzofuran	10.	U
121-14-2-----	2,4-Dinitrotoluene	10.	U
84-66-2-----	Diethylphthalate	10.	U
7005-72-3-----	4-Chlorophenyl-phenylether	10.	U
86-73-7-----	Fluorene	10.	U
100-01-6-----	4-Nitroaniline	24.	U
534-52-1-----	4,6-Dinitro-2-methylphenol	24.	U
86-30-6-----	N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----	4-Bromophenyl-phenylether	10.	U
118-74-1-----	Hexachlorobenzene	10.	U
87-86-5-----	Pentachlorophenol	24.	U
85-01-8-----	Phenanthrene	10.	U
120-12-7-----	Anthracene	10.	U
86-74-8-----	Carbazole	10.	U
84-74-2-----	Di-n-butylphthalate	10.	U
206-44-0-----	Fluoranthene	10.	U
129-00-0-----	Pyrene	10.	U
85-68-7-----	Butylbenzylphthalate	10.	U
91-94-1-----	3,3'-Dichlorobenzidine	10.	U
56-55-3-----	Benzo(a)anthracene	10.	U
218-01-9-----	Chrysene	10.	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	3.	J
117-84-0-----	Di-n-octylphthalate	10.	U
205-99-2-----	Benzo(b)fluoranthene	10.	U
207-08-9-----	Benzo(k)fluoranthene	10.	U
50-32-8-----	Benzo(a)pyrene	10.	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----	Dibenz(a,h)anthracene	10.	U
191-24-2-----	Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

3/90

1F  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

502\_\_

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID: 190942

Sample wt/vol: 1030.0 (g/mL) ML

Lab File ID: I2119

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N

pH: \_\_\_\_\_

Number TICs found: 16

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 127-18-4	TETRACHLORO-ETHENE	3.06	500.	J
2. 95-16-9	BENZOTHAZOLE	11.70	2.	J
3. - -	UNKNOWN	12.38	2.	J
4. - -	UNKNOWN	12.67	2.	J
5. - -	UNKNOWN	13.67	3.	J
6. - -	UNKNOWN	16.31	2.	J
7. - -	UNKNOWN	19.03	2.	J
8. - -	UNKNOWN	21.67	7.	J
9. - -	UNKNOWN	21.79	10.	J
10. - -	UNKNOWN	24.07	5.	J
11. - -	UNKNOWN	24.17	30.	J
12. - -	UNKNOWN	24.26	30.	J
13. - -	UNKNOWN	26.42	80.	J
14. - -	UNKNOWN	28.40	100.	J
15. - -	UNKNOWN	30.53	70.	J
16. - -	UNKNOWN	32.75	20.	J
17. - -				
18. - -				
19. - -				
20. - -				
21. - -				
22. - -				
23. - -				
24. - -				
25. - -				
26. - -				
27. - -				
28. - -				
29. - -				
30. - -				

## PESTICIDE ORGANICS ANALYSIS DATA SHEET

502

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190942

Sample wt/vol: 1020.0 (g/mL) ML

Lab File ID: 01252

% Moisture: decanted: (Y/N)

Date Received: 06/24/94

Extraction: (SepH/Cont/Sonc) SEPH

Date Extracted: 06/29/94

Concentrated Extract Volume: 10000.0 (uL)

Date Analyzed: 07/19/94

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

GPC Cleanup: (Y/N) N

pH: 6.9

Sulfur Cleanup: (Y/N) N

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

Q

319-84-6	alpha-BHC	.049	U
319-85-7	beta-BHC	.049	U
319-86-8	delta-BHC	.049	U
58-89-9	gamma-BHC (Lindane)	.049	U
76-44-8	Heptachlor	.049	U
309-00-2	Aldrin	.049	U
1024-57-3	Heptachlor epoxide	.049	U
959-98-8	Endosulfan I	.049	U
60-57-1	Dieldrin	.098	U
72-55-9	4,4'-DDE	.098	U
72-20-8	Endrin	.098	U
33213-65-9	Endosulfan II	.098	U
72-54-8	4,4'-DDD	.098	U
1031-07-8	Endosulfan Sulfate	.098	U
50-29-3	4,4'-DDT	.098	U
72-43-5	Methoxychlor	.49	U
53494-70-5	Endrin ketone	.098	U
7421-93-4	Endrin aldehyde	.098	U
5103-71-9	alpha-Chlordane	.049	U
5103-74-2	gamma-Chlordane	.049	U
8001-35-2	Toxaphene	4.9	U
12674-11-2	Aroclor-1016	.98	U
11104-28-2	Aroclor-1221	2.0	U
11141-16-5	Aroclor-1232	.98	U
53469-21-9	Aroclor-1242	.98	U
12672-29-6	Aroclor-1248	.98	U
11097-69-1	Aroclor-1254	.98	U
11096-82-5	Aroclor-1260	.98	U

FORM I PEST

3/90

1  
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

502

Name: ICM \_\_\_\_\_ Contract: A60084 \_\_\_\_\_

Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS No.: \_\_\_\_\_ SDG No.: 498 \_\_\_\_\_

ix (soil/water): WATER \_\_\_\_\_ Lab Sample ID: 190942 \_\_\_\_\_

el (low/med): LOW \_\_\_\_\_ Date Received: 06/24/94

lids: \_\_\_\_\_ 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L\_

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	715	—	—	P
7440-36-0	Antimony	29.8	U	—	P
7440-38-2	Arsenic	1.6	U	—	F
7440-39-3	Barium	179	B	—	P
7440-41-7	Beryllium	0.30	U	—	P
7440-43-9	Cadmium	1.9	U	—	P
7440-70-2	Calcium	93300	—	—	P
7440-47-3	Chromium	2.8	U	—	P
7440-48-4	Cobalt	4.6	U	—	P
7440-50-8	Copper	5.2	B	—	P
7439-89-6	Iron	2280	—	—	P
7439-92-1	Lead	1.0	B	—	F
7439-95-4	Magnesium	33200	—	—	P
7439-96-5	Manganese	717	—	—	P
7439-97-6	Mercury	0.10	U	—	CV
7440-02-0	Nickel	8.1	U	—	P
7440-09-7	Potassium	12000	—	—	P
7782-49-2	Selenium	2.1	B	W	F
7440-22-4	Silver	2.7	U	—	P
7440-23-5	Sodium	50500	—	—	P
7440-28-0	Thallium	1.6	U	W	F
7440-62-2	Vanadium	5.3	B	—	P
7440-66-6	Zinc	29.1	—	—	P
	Cyanide	10.0	U	—	AS

r Before: COLORLESS \_\_\_\_\_ Clarity Before: CLEAR \_\_\_\_\_ Texture: \_\_\_\_\_

r After: COLORLESS \_\_\_\_\_ Clarity After: CLEAR \_\_\_\_\_ Artifacts: \_\_\_\_\_

ments: \_\_\_\_\_  
 SEE CASE NARRATIVE FOR CYANIDE COLOR/CLARITY INFORMATION. \_\_\_\_\_  
 SAMPLE CONTAINS SOME SEDIMENT. \_\_\_\_\_

FORM I - IN

ILMO3.0



1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

503\_\_

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0835

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

1 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L Q

74-87-3	-----Chloromethane	10.	U
74-83-9	-----Bromomethane	10.	U
75-01-4	-----Vinyl Chloride	10.	U
75-00-3	-----Chloroethane	10.	U
75-09-2	-----Methylene Chloride	10.	U
67-64-1	-----Acetone	10.	U
75-15-0	-----Carbon Disulfide	10.	U
75-35-4	-----1,1-Dichloroethene	10.	U
75-34-3	-----1,1-Dichloroethane	10.	U
540-59-0	-----1,2-Dichloroethene (total)	10.	U
67-66-3	-----Chloroform	10.	U
107-06-2	-----1,2-Dichloroethane	10.	U
78-93-3	-----2-Butanone	10.	U
71-55-6	-----1,1,1-Trichloroethane	10.	U
56-23-5	-----Carbon Tetrachloride	10.	U
75-27-4	-----Bromodichloromethane	10.	U
78-87-5	-----1,2-Dichloropropane	10.	U
10061-01-5	-----cis-1,3-Dichloropropene	10.	U
79-01-6	-----Trichloroethene	10.	U
124-48-1	-----Dibromochloromethane	10.	U
79-00-5	-----1,1,2-Trichloroethane	10.	U
71-43-2	-----Benzene	10.	U
10061-02-6	-----trans-1,3-Dichloropropene	10.	U
75-25-2	-----Bromoform	10.	U
108-10-1	-----4-Methyl-2-Pentanone	10.	U
591-78-6	-----2-Hexanone	10.	U
127-18-4	-----Tetrachloroethene	10.	U
79-34-5	-----1,1,2,2-Tetrachloroethane	10.	U
108-88-3	-----Toluene	10.	U
108-90-7	-----Chlorobenzene	10.	U
100-41-4	-----Ethylbenzene	10.	U
100-42-5	-----Styrene	10.	U
1330-20-7	-----Xylene (total)	10.	U

1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

503\_\_

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0835

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

GC Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

Soil Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

503\_\_

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID: 190943

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2120

Level: (low/med) LOW

Date Received: 06/24/94

Disturbance: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N

pH: \_\_\_\_\_

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

108-95-2-----Phenol	10.	U
111-44-4-----bis(2-Chloroethyl) ether	10.	U
95-57-8-----2-Chlorophenol	10.	U
541-73-1-----1,3-Dichlorobenzene	10.	U
106-46-7-----1,4-Dichlorobenzene	10.	U
95-50-1-----1,2-Dichlorobenzene	10.	U
95-48-7-----2-Methylphenol	10.	U
108-60-1-----2,2'-oxybis(1-Chloropropane)	10.	U
106-44-5-----4-Methylphenol	10.	U
621-64-7-----N-Nitroso-di-n-propylamine	10.	U
67-72-1-----Hexachloroethane	10.	U
98-95-3-----Nitrobenzene	10.	U
78-59-1-----Isophorone	10.	U
88-75-5-----2-Nitrophenol	10.	U
105-67-9-----2,4-Dimethylphenol	10.	U
111-91-1-----bis(2-Chloroethoxy) methane	10.	U
120-83-2-----2,4-Dichlorophenol	10.	U
120-82-1-----1,2,4-Trichlorobenzene	10.	U
91-20-3-----Naphthalene	10.	U
106-47-8-----4-Chloroaniline	10.	U
87-68-3-----Hexachlorobutadiene	10.	U
59-50-7-----4-Chloro-3-methylphenol	10.	U
91-57-6-----2-Methylnaphthalene	10.	U
77-47-4-----Hexachlorocyclopentadiene	10.	U
88-06-2-----2,4,6-Trichlorophenol	10.	U
95-95-4-----2,4,5-Trichlorophenol	25.	U
91-58-7-----2-Chloronaphthalene	10.	U
88-74-4-----2-Nitroaniline	25.	U
131-11-3-----Dimethylphthalate	10.	U
208-96-8-----Acenaphthylene	10.	U
606-20-2-----2,6-Dinitrotoluene	10.	U
99-09-2-----3-Nitroaniline	25.	U
83-32-9-----Acenaphthene	10.	U

1C  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

503\_\_

b Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

trix: (soil/water) WATER

Lab Sample ID: 190943

ole wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2120

vel: (low/med) LOW

Date Received: 06/24/94

isture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

ncentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

raction Volume: 2.0 (uL)

Dilution Factor: 1.0

g Cleanup: (Y/N) N pH: \_\_\_\_\_

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

51-28-5-----2,4-Dinitrophenol	25.	U
100-02-7-----4-Nitrophenol	25.	U
132-64-9-----Dibenzofuran	10.	U
121-14-2-----2,4-Dinitrotoluene	10.	U
84-66-2-----Diethylphthalate	10.	U
7005-72-3-----4-Chlorophenyl-phenylether	10.	U
86-73-7-----Fluorene	10.	U
100-01-6-----4-Nitroaniline	25.	U
534-52-1-----4,6-Dinitro-2-methylphenol	25.	U
86-30-6-----N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----4-Bromophenyl-phenylether	10.	U
118-74-1-----Hexachlorobenzene	10.	U
87-86-5-----Pentachlorophenol	25.	U
85-01-8-----Phenanthrene	10.	U
120-12-7-----Anthracene	10.	U
86-74-8-----Carbazole	10.	U
84-74-2-----Di-n-butylphthalate	10.	U
206-44-0-----Fluoranthene	10.	U
129-00-0-----Pyrene	10.	U
85-68-7-----Butylbenzylphthalate	10.	U
91-94-1-----3,3'-Dichlorobenzidine	10.	U
56-55-3-----Benzo(a)anthracene	10.	U
218-01-9-----Chrysene	10.	U
117-81-7-----bis(2-Ethylhexyl)phthalate	10.	U
117-84-0-----Di-n-octylphthalate	10.	U
205-99-2-----Benzo(b)fluoranthene	10.	U
207-08-9-----Benzo(k)fluoranthene	10.	U
50-32-8-----Benzo(a)pyrene	10.	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----Dibenz(a,h)anthracene	10.	U
191-24-2-----Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

3/90

1F  
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

503

Name: ICM, Inc.

Contract: A60084

Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190943

Sample wt/vol: 1000.0 (g/mL) ML

Lab File ID: I2120.

Level: (low/med) LOW

Date Received: 06/24/94

Disturbance: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Extracted: 06/29/94

Concentrated Extract Volume: 1000.0 (uL)

Date Analyzed: 07/21/94

Injection Volume: 2.0 (uL)

Dilution Factor: 1.0

Cleanup: (Y/N) N pH: \_\_\_\_\_

Number TICs found: 1

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	8.48	7.	BJ
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1D  
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

503

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID: 190943

Sample wt/vol: 1050.0 (g/mL) ML

Lab File ID: 01253

Moisture: \_\_\_\_\_ decanted: (Y/N) \_\_\_\_\_

Date Received: 06/24/94

Extraction: (SepF/Cont/Sonc) SEPF

Date Extracted: 06/29/94

Concentrated Extract Volume: 10000.0 (uL)

Date Analyzed: 07/19/94

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

PC Cleanup: (Y/N) N

pH: 8.1

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

(ug/L or ug/Kg) ug/L Q

CAS NO.	COMPOUND		
319-84-6	alpha-BHC	.048	U
319-85-7	beta-BHC	.048	U
319-86-8	delta-BHC	.048	U
58-89-9	gamma-BHC (Lindane)	.048	U
76-44-8	Heptachlor	.048	U
309-00-2	Aldrin	.048	U
1024-57-3	Heptachlor epoxide	.048	U
959-98-8	Endosulfan I	.048	U
60-57-1	Dieldrin	.095	U
72-55-9	4,4'-DDE	.095	U
72-20-8	Endrin	.095	U
33213-65-9	Endosulfan II	.095	U
72-54-8	4,4'-DDD	.095	U
1031-07-8	Endosulfan Sulfate	.095	U
50-29-3	4,4'-DDT	.095	U
72-43-5	Methoxychlor	.48	U
53494-70-5	Endrin ketone	.095	U
7421-93-4	Endrin aldehyde	.095	U
5103-71-9	alpha-Chlordane	.048	U
5103-74-2	gamma-Chlordane	.048	U
8001-35-2	Toxaphene	4.8	U
12674-11-2	Aroclor-1016	.95	U
11104-28-2	Aroclor-1221	1.9	U
11141-16-5	Aroclor-1232	.95	U
53469-21-9	Aroclor-1242	.95	U
12672-29-6	Aroclor-1248	.95	U
11097-69-1	Aroclor-1254	.95	U
11096-82-5	Aroclor-1260	.95	U

FORM I PEST

3/90

1  
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

503

Lab Name: ICM Contract: A60084

Lab Code: Case No.: SAS No.: SDG No.: 498

Matrix (soil/water): WATER

Lab Sample ID: 190943

Level (low/med): LOW

Date Received: 06/24/94

Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	34.6	U		P
7440-36-0	Antimony	29.8	U		P
7440-38-2	Arsenic	1.6	U		F
7440-39-3	Barium	0.40	U		P
7440-41-7	Beryllium	0.30	U		P
7440-43-9	Cadmium	1.9	U		P
7440-70-2	Calcium	28.9	B		P
7440-47-3	Chromium	2.8	U		P
7440-48-4	Cobalt	4.6	U		P
7440-50-8	Copper	4.2	U		P
7439-89-6	Iron	7.2	B		P
7439-92-1	Lead	0.92	U		F
7439-95-4	Magnesium	29.4	U		P
7439-96-5	Manganese	4.4	U		P
7439-97-6	Mercury	0.10	U		CV
7440-02-0	Nickel	8.1	U		P
7440-09-7	Potassium	536	U		P
7782-49-2	Selenium	1.4	U	W	F
7440-22-4	Silver	2.7	U		P
7440-23-5	Sodium	71.0	B		P
7440-28-0	Thallium	1.6	U		F
7440-62-2	Vanadium	2.1	U		P
7440-66-6	Zinc	1.3	U		P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

SEE\_CASE\_NARRATIVE\_FOR\_CYANIDE\_COLOR/CLARITY\_INFORMATION.

FORM I - IN

ILMO3.0

1A  
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

504\_\_

Sample Name: ICM, Inc.

Contract: A60084

Sample Code: ICM

Case No.:

SAS No.:

SDG No.: 498\_\_

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0834

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec. \_\_\_\_\_

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

1 Extract Volume: \_\_\_\_\_ (uL)

Soil Aliquot Volume: \_\_\_\_\_ (uL)

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

74-87-3	Chloromethane	10.	U
74-83-9	Bromomethane	10.	U
75-01-4	Vinyl Chloride	10.	U
75-00-3	Chloroethane	10.	U
75-09-2	Methylene Chloride	10.	U
67-64-1	Acetone	10.	U
75-15-0	Carbon Disulfide	10.	U
75-35-4	1,1-Dichloroethene	10.	U
75-34-3	1,1-Dichloroethane	10.	U
540-59-0	1,2-Dichloroethene (total)	10.	U
67-66-3	Chloroform	10.	U
107-06-2	1,2-Dichloroethane	10.	U
78-93-3	2-Butanone	10.	U
71-55-6	1,1,1-Trichloroethane	10.	U
56-23-5	Carbon Tetrachloride	10.	U
75-27-4	Bromodichloromethane	10.	U
78-87-5	1,2-Dichloropropane	10.	U
10061-01-5	cis-1,3-Dichloropropene	10.	U
79-01-6	Trichloroethene	10.	U
124-48-1	Dibromochloromethane	10.	U
79-00-5	1,1,2-Trichloroethane	10.	U
71-43-2	Benzene	10.	U
10061-02-6	trans-1,3-Dichloropropene	10.	U
75-25-2	Bromoform	10.	U
108-10-1	4-Methyl-2-Pentanone	10.	U
591-78-6	2-Hexanone	10.	U
127-18-4	Tetrachloroethene	10.	U
79-34-5	1,1,2,2-Tetrachloroethane	10.	U
108-88-3	Toluene	10.	U
108-90-7	Chlorobenzene	10.	U
100-41-4	Ethylbenzene	10.	U
100-42-5	Styrene	10.	U
1330-20-7	Xylene (total)	10.	U



VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

504

Lab Name: ICM, Inc.

Contract: A60084

Lab Code: ICM

Case No.:

SAS No.:

SDG No.: 498

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5.000 (g/mL) ML

Lab File ID: C0834

Level: (low/med) LOW

Date Received: 06/24/94

Moisture: not dec.

Date Analyzed: 07/03/94

Column: SP1000 ID: 2.00 (mm)

Dilution Factor: 1.0

1 Extract Volume: (uL)

Soil Aliquot Volume: (uL)

Number TICs found: 0

CONCENTRATION UNITS:  
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

ATTACHMENT L



# State of New Jersey

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

CHRISTINE TODD WHITMAN  
Governor

ROBERT C. SHINN, JR.  
Commissioner

SEP 21 1994

### MEMORANDUM

TO: Frank Sorce  
Site Assessment Section

THROUGH: Greg Toffoli, Section Chief *for GT 9/21/94*  
Joseph Sanguiliano *9/21/94*  
Quality Assurance Section  
Bureau of Environmental Measurements and Quality Assurance

FROM: Dr. Winnie Chu  
Quality Assurance Section *WZ 9/20/94*  
Bureau of Environmental Measurements and Quality Assurance

SUBJECT: Quality Assurance Data Review -- Site Name: VIP Drycleaners, Morristown.  
Samples were analyzed by Industrial Corrosion Management, Inc., Randolph,  
New Jersey according to Contract X-26174 task IV deliverables. The reviewed  
samples were:

<u>Field ID</u>	<u>Lab ID</u>	<u>VTSR</u>	<u>Matrix</u>
504/Trip Blank	190944	6/24/94	Aqueous
503/Field Blank-bailer	190943	6/24/94	Aqueous
498	190939	6/24/94	Aqueous
499	190940	6/24/94	Aqueous
501	190941	6/24/94	Aqueous
502	190942	6/24/94	Aqueous

The Quality Assurance Section, Bureau of Environmental Measurements and Quality Assurance, Division of Publicly Funded Site Remediation has reviewed the above referenced six (6) samples according to NJDEP CLP deliverables requirements. The samples were analyzed according to CLP SOWs OLM01.8 for TCL organics and ILM03.0 for inorganics, which included Target

Analytes List (TAL) metals and total cyanides. A detailed data validation report is available for your review. Specific comments are provided below.

The analytical data reported (after several resubmissions by the laboratory) are acceptable with those exceptions noted below. Please refer to the attached "Target and Nontarget (TIC) Analyte Data Summary List" for individual samples and analytical results instead of the data reported on the Form I's in the original data package.

#### General Comments

The laboratory resubmitted the corrected Form I's, i.e., "organic analysis data sheet" (OADS) for many samples due to errors in the mass spectra positive/negative identifications in the VOA fraction. However, the laboratory neglected to initial/date these resubmitted corrections.

#### VOA Fraction

The analytical data reported are acceptable after the above mentioned resubmissions by the laboratory.

#### BNA Fraction and Pesticide/ Aroclor Fractions

The analytical data reported are acceptable.

#### Inorganics

Certain analytes are qualified because of the QA/QC outliers in post-digestion spike recoveries from Furnace AA analyses (footnotes 3 and 5). Please refer to the specific footnotes in the attachment for the affected analytes.

If you have any questions concerning this review, please contact this office at 3-0752.

attachment

c. William Lowry, BEMQA

## Page 1 of 7

SAMPLING DATE: 6/23/94

**SAMPLE MATRIX: AQUEOUS, ug/L**

ATTACHMENT L3

## Page 2

SAMPLING DATE: 6/23/94

**SAMPLE MATRIX: AQUEOUS, ug/L**

[illegible]

# TARGET ANALYTE DATA SUMMARY

Page 3

SITE NAME: VIP Drycleaners, Morristown

SAMPLING DATE: 6/23/94

LAB NAME: Industrial Corrosion Management, Inc.

SAMPLE MATRIX: AQUEOUS, ug/L

TRACTION	SAMPLE ID	ANALYTE	METHOD BLANK CONC	LAB REPORT CONC	QA REPORT CONC	QA DECISIONS	FOOTNOTE
Inorganics	501	Aluminum	42J	724	724		
		Barium	U	181J	181J	qualify	2
		Cadmium	U	3J	3J	qualify	2
		Calcium	35J	94100	94100		
		Copper	U	5J	5J	qualify	2
		Iron	42J	2190	2190		
		Lead	U	2J	2J	qualify	2
		Magnesium	U	33400	33400		
		Manganese	U	724	724		
		Potassium	U	11600	11600		
		Sodium	48J	50600	50600		
		Vanadium	U	5J	5J	qualify	2
		Zinc	U	37	37		
Inorganics	502	Aluminum	42J	715	715		
		Barium	U	179J	179J	qualify	2
		Calcium	35J	93300	93300		
		Copper	U	5J	5J	qualify	2
		Iron	42J	2280	2280		
		Lead	U	1J	1J	qualify	2
		Magnesium	U	33200	33200		
		Manganese	U	717	717		
		Potassium	U	12000	12000		
		Selenium	U	2J	2J	qualify	2,5
		Sodium	48J	50500	50500		
		Thallium	U	UJ	UJ	qualify	3
		Vanadium	U	5J	5J	qualify	2
		Zinc	U	29	29		

## Page 4

SAMPLING DATE: 6/23/94

SAMPLE MATRIX: AQUEOUS, ug/L

[illegible]



# TARGET & NON-TARGET (TIC) ANALYTE DATA SUMMARY

Page 5

NAME: VIP Drycleaners, Morristown

SAMPLING DATE: 6/23/94

NAME: Industrial Corrosion Management, Inc.

SAMPLE MATRIX: AQUEOUS, ug/L

OTE: Only those nontarget compounds that require QAS action are provided below.

FRACTION	SAMPLE ID/DF	ANALYTE	METHOD BLANK CONC	LAB REPORT CONC	QA REPORT CONC	QA DECISIONS	FOOTNOTE
VOA	Trip Blank	Methylene Chloride	10U	2J	2J	qualify	2
		Acetone	10U	18	18		
		No TIC.					
VOA	Field Blank	Methylene Chloride	10U	2J	2J	negate	6
		Acetone	10U	15	15J	negate	6
		No TIC.					
VOA	498	Tetrachloroethene	10U	4J	4J	qualify	2
		No TIC.					
VOA	499	Acetone	10U	12	12J	negate	6
		Tetrachloroethene	10U	30	30		
		No TIC.					
VOA	501	Vinyl Chloride	10U	120	120		
		Chloroethane	10U	6J	6J	qualify	2
		1,1-Dichloroethene	10U	2J	2J	qualify	2
		1,2-Dichloroethene (total)	10U	820E	820E	qualify	7
		Trichloroethene	10U	430E	430E	qualify	7
		Tetrachloroethene	10U	1700E	1700E	qualify	7
		No TIC.					
VOA	501DL/20	1,2-Dichloroethene (total)	10U	730D	730D		8
		Trichloroethene	10U	390D	390D		8
		Tetrachloroethene	10U	2600D	2600D		8
		No TIC.					

TARGET & NON-TARGET (TIC) ANALYTE DATA SUMMARY

Page 6

CLIENT NAME: VIP Drycleaners, Morristown

SAMPLING DATE: 6/23/94

LAB NAME: Industrial Corrosion Management, Inc.

SAMPLE MATRIX: AQUEOUS, ug/L

NOTE: Only those nontarget compounds that require QAS action are provided below.

FRACTION	SAMPLE ID/DF	ANALYTE	METHOD BLANK CONC	LAB REPORT CONC	QA REPORT CONC	QA DECISIONS	FOOTNOTE
VOA	502	Vinyl Chloride	10U	120	120		
		Chloroethane	10U	7J	7J	qualify	2
		1,1-Dichloroethene	10U	2J	2J	qualify	2
		1,2-Dichloroethene (total)	10U	800E	800E	qualify	7
		Chloroform	10U	1J	1J	qualify	2
		1,2-Dichloropropane	10U	2J	2J	qualify	2
		Trichloroethene	10U	430E	430E	qualify	7
		Tetrachloroethene	10U	1700E	1700E	qualify	7
		No TIC.					
VOA	502DL/20	1,2-Dichloroethene (total)	10U	820D	820D		8
		Trichloroethene	10U	420D	420D		8
		Tetrachloroethene	10U	3000D	3000D		8
		No TIC.					

# TARGET ANALYTE DATA SUMMARY

Page 7

CLIENT NAME: VIP Drycleaners, Morristown

SAMPLING DATE: 6/23/94

LAB NAME: Industrial Corrosion Management, Inc.

SAMPLE MATRIX: AQUEOUS, ug/L

FRACTION	SAMPLE ID/DF	ANALYTE	METHOD BLANK CONC	LAB REPORT CONC	QA REPORT CONC	QA DECISIONS	FOOTNOTE
Pesticide/Arochlor	Field Blank	None detected					
Pesticide/Arochlor	498	None detected					
Pesticide/Arochlor	499	None detected					
Pesticide/Arochlor	501	None detected					
Pesticide/Arochlor	502	None detected					

#### FOOTNOTES:

1. The value reported in the sample is less than or equal to 3x the value in the Method Blank/ Preparation Blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable foreign laboratory contamination unrelated to the actual sample. The end-user is alerted that a reportable quantity of the analyte was detected. When the sample was diluted prior to analysis and/ or the value reported was corrected to dry weight basis, as indicated by the dilution factor and/ or %solids, the comparison to the "Blanks" was prior to these corrections.
2. The concentration of this analyte was less than the CRQL/CRDL but greater than the instrument detection limit (IDL). The concentration is considered estimated since the value obtained is at the low end of the instrument performance. When the sample was diluted prior to analysis and/ or the value reported was corrected to dry weight basis, as indicated by the dilution factor and/ or %solids, the comparison to the "Blanks" was prior to these corrections.
3. The reported metal value is qualified (J positive and UJ for non-detects) because the post-digestion spike recovery for Furnace AA analysis is below the control limit while the sample absorbance is less than 50 percent of the spike absorbance.
4. The laboratory used the Method of Standard Addition (MSA) analysis for this analyte.
5. The reported positive metal value is qualified (J positive) because the post-digestion spike recovery for Furnace AA analysis is above the control limit while the sample absorbance is less than 50 percent of the spike absorbance.
6. The value reported in the sample is less than or equal to 3x the value in the Trip Blank. It is the policy of NJDEP-DPFSR to negate the reported value due to probable foreign contamination unrelated to the actual sample. The end-user is alerted that a reportable quantity of the analyte was detected. When the sample was diluted prior to analysis and/ or the value reported was corrected to dry weight basis, as indicated by the dilution factor and/ or %solids, the comparison to the "Blanks" was prior to these corrections.
7. The compounds exceeds the calibration range of the instrument and it is indicated with the "E" qualifier.
8. The CLP program requires dilutions to be indicated with the "D" qualifier. The comparison to the "Blanks" or the CRQL/ CRDL was prior to the dilution corrections.